

MaineDOT
**Best Management Practices
for Erosion and
Sedimentation Control**



February 2008

TABLE OF CONTENTS

I. INTRODUCTION

A. WHY THIS MANUAL	Sec-I:1
B. IMPACT FROM DEVELOPMENT	Sec-I:2
C. EROSION AND SEDIMENTATION	Sec-I:3
1. The Principles and Factors	Sec-I:3
2. The Erosion Process	Sec-I:11
3. Erosion Control	Sec-I:12
4. The Sedimentation Process	Sec-I:13
5. Sedimentation Control	Sec-I:13
6. Rules of Thumb	Sec-I:14

II. STANDARDS AND COMMITMENT

A. TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	Sec-II:1
1. The ESC Plan	Sec-II:1
2. Six Principles of Erosion and Sedimentation Control	Sec-II:1
3. Spill Prevention	Sec-II:4
4. MaineDOT Procedures	Sec-II:5
5. SEWPCP Content	Sec-II:5
B. POST CONSTRUCTION STORMWATER MANAGEMENT AND COMPLIANCE	Sec-II:7
C. REGULATORY COMPLIANCE FOR MAINEDOT AND MTA	Sec-II:9
1. Stormwater Management Law	Sec-II:9
2. Maine Construction General Permit	Sec-II:11
D. GUIDANCE FOR SENSITIVE WATER BODIES	Sec-II:13
1. History	Sec-II:13
2. Standard	Sec-II:13

III. BEST MANAGEMENT PRACTICES

A. HOW TO USE THIS MANUAL	Sec-III:1
B. SHEET AND RILL EROSION CONTROL (SR-EC)	Sec-III:5
1. Hydraulic Mulch	Sec-III:7
2. Hay and Straw Mulch	Sec-III:9
3. Erosion Control Mix	Sec-III:13
4. Erosion Control Blanket	Sec-III:15
5. Turf Reinforced Matting	Sec-III:19
6. Plastic Sheeting	Sec-III:21
7. Riprap	Sec-III:23
8. Seeding and Landscape Plantings	Sec-III:25
9. Surface Roughening	Sec-III:27
10. Gradient Terrace	Sec-III:29
11. Hillside Diversion	Sec-III:31
C. SHEET AND RILL SEDIMENTATION CONTROL (SR-SC)	Sec-III:37
1. Silt Fence	Sec-III:39
2. Erosion Control Mix Berm	Sec-III:43
3. Continuous Contained Berm	Sec-III:45
4. Vegetative Filter Strips	Sec-III:47
D. CONCENTRATED FLOW EROSION CONTROL (CF-EC)	Sec-III:51
1. Channel Linings	Sec-III:53
2. Temporary Channel Lining - Plastic Sheeting	Sec-III:57
3. Riprap Downspouts	Sec-III:59
4. Temporary Slope Drains	Sec-III:63
5. Energy Dissipators - Riprap Apron and Plunge Pool	Sec-III:67
6. Culverts - Inlet and Outlet Protection	Sec-III:73
E. CONCENTRATED FLOW SEDIMENTATION CONTROL (CF-SC)	Sec-III:77
1. Check Dams	Sec-III:79
2. Sediment Traps	Sec-III:83
3. Storm Drain Inlet Protection	Sec-III:87

F. IN WATER WORK	Sec-III:95
1. Floating Turbidity Curtain	Sec-III:97
2. Temporary Stream Crossing	Sec-III:99
3. Temporary Stream Diversion	Sec-III:101
4. Cofferdams	Sec-III:107
5. Dewatering	Sec-III:111
6. Temporary Sediment Basin	Sec-III:115
7. Geotextile Filter Bags	Sec-III:119
G.MISCELLANEOUS	Sec-III:123
1. Dust Control	Sec-III:125
2. Sweeping & Vacuuming	Sec-III:127
3. Construction Entrance/Exit	Sec-III:129
4. Winter Stabilization	Sec-III:133

APPENDICES

Appendix A, Soil and Water Conservation	
District Contract Information	App-A:1
Appendix B, MaineDOT, MTA, MDEP Stormwater MOA	App-B:1
Appendix C, Standard Specification 656	App-C:1
Appendix D, Common Values and Unit Conversions	App-D:1

