

Client:	Maine Department of Marine Resources	Addendum No.:	001
Project:	Insulation and Roof Upgrade BGS Project #2361	Addendum Date:	26-August-2014
Site Location:	Vieno's Way, Rockland, Maine	Issued By:	Curtis Dow

Distribution (Bidders)	Company	E-Mail
------------------------	---------	--------

Mike Adams	Ganneston Construction	<a href="mailto:mikeadams@gannestonconstruction.com">mikeadams@gannestonconstruction.com</a>
Jonathan Field	D.H. Pinnette & Sons	<a href="mailto:jonathan@dhpinnacle.com">jonathan@dhpinnacle.com</a>
Bob Gladu	Gladu roofing Co., Inc.	<a href="mailto:gladuroofing@gmail.com">gladuroofing@gmail.com</a>
Hayward Kingsbury	Roof Systems of Maine	<a href="mailto:info@roofsystemsofmaine.com">info@roofsystemsofmaine.com</a>
Keith Smith	KWS & Son	<a href="mailto:kevin@kwsandson.com">kevin@kwsandson.com</a>
Scott St. Peter	IRC	<a href="mailto:scott@ircmaine.com">scott@ircmaine.com</a>
Eric Wass	Coastal Copper & Slate	<a href="mailto:Coastalcopper@roadrunner.com">Coastalcopper@roadrunner.com</a>

Distribution (Owner)	Company	E-Mail
Marlowe Sonksen	MDMR	<a href="mailto:marlowe.sonksen@maine.gov">marlowe.sonksen@maine.gov</a>
Robert Gurney	BGS	<a href="mailto:robert.gurney@maine.gov">robert.gurney@maine.gov</a>

## Bidder Questions

No.	Question/Bid Clarification	Response
1.	Can the bid timeframe be extended?	The bid submission date has been changed to <b>Wednesday, September 3, 2014 at 2:00 p.m.</b> Bids must be received prior to this timeframe to be eligible. Refer to the original Notice to Contractors for submission procedures.
2.	What rooftop equipment is to be removed from the roof?	1) The Air Handling Unit located on the west side of the roof is to be removed. 2) The Flue stack in the north east corner is to be removed.
3.	What rooftop equipment is to remain?	The mechanical exhaust located in the middle of the roof is to remain and the Contractor will be responsible for any additional wiring needed, electrical disconnect and additional curb and support reinforcement needed to maintain the operation of the equipment.

4.	Is the flashing supposed to cover the bond beam on the north elevation?	Yes the rooftop flashing is to be extended down to cover the bond beam and overlap the vinyl siding.
5.	Is the vinyl siding that is missing or damaged on the north elevation to be replaced?	Yes. The vinyl siding on the north elevation is that is missing or damaged is to be replaced.
6.	Are all vent stacks to receive new flashings	Yes. All vent sacks are to receive new flashings pursuant to the vent stack detail B/A1.1 on Sheet A1.1.
7.	Is Contractor responsible for ensuring existing roof drainage slopes correctly, that piping is operable and functional with no leaks?	Yes. Contractor shall ensure that existing roof drainage slopes correctly, that piping is operable and functional with no leaks?
8.	Will the MDMR staff be responsible for moving materials and equipment from work areas prior to the contractor commencing work as needed?	Yes. The MDMR staff will move materials and equipment as needed provided they are given a minimum 72 hour advance notice of areas where work is to be performed.

**END OF BID ADDENDUM NO. 001**