

DOCUMENT 009100

ADDENDA

ADDENDUM NUMBER ONE (002)

DATE: August 8, 2016

PROJECT: **RE-BID Temporary Milk and Blood Lab
Marquardt Building
Augusta, Maine**

PROJECT NUMBER: Ames Associates Project NO. 2015114

CLIENT: State of Maine, Bureau of general Services
Augusta, Maine 04416

ARCHITECT: Ames Associates, LLC

TO: Prospective Bidders

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated July 20, 2016, with amendments and additions noted below.

The Bidder is to acknowledge receipt of this Addendum in the space provided in the Bid Form of the Project Manual. Failure to do so may disqualify the Bidder.

This Addendum consists of **TWO (2)** pages.

1.0 Changes to the specifications:

No Changes

2.0 QUESTIONS AND ANSWERS:

2.1 Key note 10 on QL102 is on the plan but not in the legend. Can you explain what this refers to?

ANSWER: *Note 10 should say Electrical raceway; see electrical drawings*

2.2 Can you clarify the "utility space framing" and "removable panel" called for in detail 1 & 2 on QL901?

ANSWER: *See specifications*

2.3 Is utility space framing required between the island cabinets? If so, please clarify.

ANSWER: *Yes, See specifications*

2.4 Building sections 1 & 2/A105 calls for 2" SPF in the typical exterior wall section. Is this blocking as needed for the casework?

ANSWER: *The detail refers to the infill wall at the bathroom. And yes, wood blocking as needed for the cabinets at this wall is required.*

2.5 Are the backsplashes all epoxy?

ANSWER: *Yes. See specifications*

2.6 Is clear silicone approved for installation of epoxy tops, including edge to edge joints and backsplash to top?

ANSWER: *Yes. See specifications.*

3.0 Attachments:

None

-- END OF DOCUMENT --