



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

November 13, 2007
Subject: **Houlton**
Project No. STP-9192(00)X
Pin No. 9192.00
Amendment No. 1

DAVID A. COLE
COMMISSIONER

Dear Sir/Ms:

Please make the following change to the Bid Documents:

In the Bid Book, REMOVE the existing "Schedule of Items" dated 071022, twelve page total (pages 3 thru 14 of the book) and REPLACE with the attached updated "Schedule of Items" dated 071113, twelve pages total.

In the Plan Sheets, on sheet four of sixty-two titled: "Estimated Quantities" on item number "603.199 - 600mm Culvert Pipe Option III" DELETE the existing quantity of 82.300 and REPLACE with 93.03. Make this change in pen and ink.

On sheet six of sixty-two titled: "Drainage Sheet" within the row for station numbers 3+009.6 to 3+142.3 LT, under "Culvert Pipe, RCP" in the column named "Class" DELETE the existing III and REPLACE with IV. Make this change in pen and ink.

On sheet six of sixty-two titled: "Drainage Sheet" within the row for station numbers 3+142.3 to 3+205 LT, under "Culvert Pipe, Option III" in the column named "Size mm" DELETE the existing 600 and in the column named "Length" DELETE the existing 62.7. Make this change in pen and ink.

On sheet six of sixty-two titled: "Drainage Sheet" within the row for station numbers 3+142.3 to 3+205 LT, under "Culvert Pipe, RCP" in the column named "Size mm" ADD the following: "600" in the column named "Length" ADD the following 62.7 and in the column named "Class" ADD the following III. Make this change in pen and ink.

The following questions have been received.

Question: The 600mm, RCP @ Station 3+009.6 to 3+142.3 LT (132.7m) is shown on sheet 6 of 62 as Class III, but the item 603.41- 610mm RCP is shown as a Class IV. Could you please verify the two pay items 603.195 and 603.41?

Response: See changes made earlier in this amendment.



PRINTED ON RECYCLED PAPER

Question: Will the surplus millings that need to be hauled to the Oakfield Maintenance yard need to be processed to a 1" minus, or does the processing only apply to the amount of material we will need for placement on the job? Please clarify.

Response: Surplus pavement salvage that is to be hauled to Oakfield MDOT maintenance lot does not need to be processed to 25mm (1") minus. Only the pavement salvage material used on the project needs to be processed to 25mm minus.

Consider these changes and information prior to submitting your bid on November 14, 2007.

Sincerely,

A handwritten signature in black ink, appearing to read "S. Bickford FOR". The signature is stylized and written in a cursive-like font.

Scott Bickford

Contracts & Specifications Engineer

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009192.00

PROJECT(S): STP-9192(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 HIGHWAY ITEMS
(BASIS OF AWARD - SECTION 0001 COMBINED WITH 0003)

0010	203.20 COMMON EXCAVATION	27412.000 M3				
0020	203.21 ROCK EXCAVATION	40.000 M3				
0030	203.2312 HEALTH AND SAFETY PLAN	LUMP	LUMP			
0040	203.2333 DISPOSAL OF SPECIAL EXCAVATION	50.000 MG				
0050	203.25 GRANULAR BORROW	25.000 M3				
0060	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	100.000 M3				
0070	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	140.000 M3				
0080	304.13 DENSE GRADED CRUSHED AGGREGATE SUBBASE	25138.000 M3				
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	1300.000 MG				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009192.00

PROJECT(S): STP-9192(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	403.210 HOT MIX ASPHALT 9.5 MM NOMINAL MAX SIZE	2600.000 MG				
0110	403.211 HOT MIX ASPHALT (SHIM)	100.000 MG				
0120	403.213 HOT MIX ASPHALT 12.5 MM, BASE	6050.000 MG				
0130	409.15 BITUMINOUS TACK COAT APPLIED	9090.000 L				
0140	411.12 CRUSHED STONE SURFACE	10.000 MG				
0150	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			
0160	603.15 300 MM CULVERT PIPE OPTION I	67.000 M				
0170	603.159 300 MM CULVERT PIPE OPTION III	609.500 M				
0180	603.16 375 MM CULVERT PIPE OPTION I	8.000 M				
0190	603.169 375 MM CULVERT PIPE OPTION III	27.000 M				
0200	603.17 450 MM CULVERT PIPE OPTION I	37.000 M				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009192.00

PROJECT(S): STP-9192(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	603.179 450 MM CULVERT PIPE OPTION III	120.000 M				
0220	603.19 600 MM CULVERT PIPE OPTION I	27.000 M				
0230	603.195 600 MM RCP CLASS III	65.700 M				
0240	603.199 600 MM CULVERT PIPE OPTION III	93.030 M				
0250	603.41 600 MM REINFORCED CONCRETE PIPE CLASS IV	132.700 M				
0260	603.45 1219 MM REINFORCED CONCRETE PIPE CLASS IV	51.200 M				
0270	604.072 CATCH BASIN TYPE A1-C	47.300 EA				
0280	604.092 CATCH BASIN TYPE B1-C	3.000 EA				
0290	604.247 CATCH BASIN TYPE F5-C	7.000 EA				
0300	604.252 CATCH BASIN TYPE A5-C	5.000 EA				
0310	605.09 150 MM UNDERDRAIN TYPE B	650.000 M				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009192.00

PROJECT(S): STP-9192(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	605.10 150 MM UNDERDRAIN OUTLET	6.000 M				
0330	605.11 300 MM UNDERDRAIN TYPE C	1594.000 M				
0340	605.12 375 MM UNDERDRAIN TYPE C	357.000 M				
0350	605.13 450 MM UNDERDRAIN TYPE C	112.000 M				
0360	605.15 600 MM UNDERDRAIN TYPE C	150.000 M				
0370	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	137.000 M				
0380	606.231 GUARDRAIL TYPE 3C - 4.5 M RADIUS AND LESS	4.000 M				
0390	606.232 GUARDRAIL TYPE 3C - OVER 4.5 M RADIUS	42.000 M				
0400	606.241 GUARDRAIL TYPE 3D - 4.5M RADIUS AND LESS	3.810 M				
0410	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	7.000 EA				
0420	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	16.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009192.00

PROJECT(S): STP-9192(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	606.355 GUARDRAIL MOWING DELINEATORS	6.000 EA				
0440	606.79 GUARDRAIL 350 FLARED TERMINAL	1.000 EA				
0450	608.26 CURB RAMP DETECTABLE WARNING FIELD	21.000 M2				
0460	609.11 VERTICAL CURB TYPE 1	1930.000 M				
0470	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	185.000 M				
0480	609.15 SLOPED CURB TYPE 1	30.000 M				
0490	609.234 TERMINAL CURB TYPE 1 - 1.2 METER	181.000 EA				
0500	609.237 TERMINAL CURB TYPE 1 - 2.1 METER	37.000 EA				
0510	609.31 CURB TYPE 3	580.000 M				
0520	609.40 RESET CURB TYPE 5	41.000 M				
0530	610.08 PLAIN RIPRAP	120.000 M3				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009192.00

PROJECT(S): STP-9192(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	613.319 EROSION CONTROL BLANKET	420.000 M2				
0550	615.07 LOAM	1200.000 M3				
0560	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	68.000 UN				
0570	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	39.000 UN				
0580	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	13.000 UN				
0590	619.1201 MULCH - PLAN QUANTITY	120.000 UN				
0600	620.54 STABILIZATION GEOTEXTILE	1000.000 M2				
0610	620.58 EROSION CONTROL GEOTEXTILE	220.000 M2				
0620	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	7600.000 M				
0630	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	110.000 M2				
0640	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009192.00

PROJECT(S): STP-9192(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0650	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0660	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	20.000 HR				
0670	631.11 AIR TOOL (INCLUDING OPERATOR)	20.000 HR				
0680	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR				
0690	631.132 SMALL BULLDOZER (INCLUDING OPERATOR)	20.000 HR				
0700	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0710	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0720	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR				
0730	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR				
0740	639.18 FIELD OFFICE TYPE A	1.000 EA				
0750	652.31 TYPE I BARRICADE	40.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009192.00

PROJECT(S): STP-9192(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0760	652.311 TYPE II BARRICADE	10.000 EA				
0770	652.33 DRUM	40.000 EA				
0780	652.34 CONE	100.000 EA				
0790	652.35 CONSTRUCTION SIGNS	110.000 M2				
0800	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	300.000 CD				
0810	652.38 FLAGGER	7000.000 HR				
0820	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0830	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	100.000 M2				
0840	659.10 MOBILIZATION	LUMP	LUMP			
SECTION 0001 TOTAL						.

SECTION 0002 SEWER & WATER WORK - ATTACHMENT 1
 (MUST BID OPTION)
 ALT GROUP OP1

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009192.00

PROJECT(S): STP-9192(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0850	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	20.000 M3				
0860	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	160.000 CD				
0870	652.38 FLAGGER	2000.000 HR				
0880	659.10 MOBILIZATION	LUMP	LUMP			
0890	801.01 PUMP STATION WITH SELF PRIMING PUMPS	LUMP	LUMP			
0900	801.142 100 MM FORCE MAIN	190.000 M				
0910	801.162 150 MM PVC BUILDING SEWER	138.000 M				
0920	801.17 200 MM PVC SANITARY SEWER (SDR-35)	575.000 M				
0930	801.18 300 MM PVC SANITARY SEWER (SDR-35)	79.000 M				
0940	801.194 450 MM PVC SANITARY SEWER (SDR-35)	40.000 M				
0950	802.201 SEWAGE PUMPING ALLOWANCE	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009192.00

PROJECT(S): STP-9192(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0960	803.01 TEST PITS	6.000 EA				
0970	803.16 1.2 M DIAMETER PRECAST SEWER MANHOLE	14.000 EA				
0980	822.3301 150 MM CLASS 52 CEMENT LINED DUCTILE IRON WATERMAIN	111.000 M				
0990	822.3402 200 MM CLASS 52 CEMENT LINED DUCTILE IRON WATERMAIN	62.000 M				
1000	822.3603 300 MM CLASS 51 CEMENT LINED DUCTILE IRON WATERMAIN	1967.000 M				
1010	823.311 300MM GATE VALVE WITH BOX	13.000 EA				
1020	823.3251 200MM GATE VALVE WITH BOX	9.000 EA				
1030	823.33 150MM GATE VALVE WITH BOX	13.000 EA				
1040	824.303 FIRE HYDRANT WITH VALVE BOX, COMPLETE	6.000 EA				
1050	824.31 REMOVE FIRE HYDRANT	7.000 EA				
1060	824.34 RECONNECT EXISTING HYDRANT	3.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009192.00

PROJECT(S): STP-9192(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1070	825.311 19 MM CORPORATION	42.000 EA				
1080	825.312 19 MM CURB STOP	42.000 EA				
1090	825.41 19 MM COPPER SERVICE	322.000 M				
1100	827.304 TRENCH ROCK EXCAVATION	100.000 M3				
1110	827.311 UNSUITABLE SOIL EXCAVATION, REMOVE AND REFILL- BELOW GRADE	1.000 M3				
1120	827.33 TRENCH INSULATION	12.000 M				
1130	832.065 TEMPORARY PIPING	LUMP	LUMP			
SECTION 0002 TOTAL						.

SECTION 0003 NEW UTILITY WORK - ATTACHMENT 2

(MUST BID OPTION)

ALT GROUP OP2

1140	801.17 200 MM PVC SANITARY SEWER (SDR-35)	20.000 M				
1150	801.194 450 MM PVC SANITARY SEWER (SDR-35)	40.000 M				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009192.00

PROJECT(S): STP-9192(00)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1160	803.16 1.2 M DIAMETER PRECAST SEWER MANHOLE	2.000 EA				
1170	827.33 TRENCH INSULATION	6.000 M				
	SECTION 0003 TOTAL					
	TOTAL BID ALL SECTIONS					