



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

November 9, 2007
Subject: **Dixfield**
Project No. NH-1001(500)E
Pin No. 010015.00
Amendment No. 3

Dear Sir/Ms:

Please make the following changes to the Bid Documents.

In the Bid Book, REMOVE the existing: "Schedule of Items" dated 070926 nine pages total and REPLACE with the attached updated: "Schedule of Items" dated 071107 nine pages total.

In the Plan Sheets, ADD the placement of 1200mm X 19.5m RCP Class III pipe at the following Station locations:

Station 4+500 – 9.9m LT, elevation 142.4 to 9.6 m RT, elevation 142.0.

Station 4+560 – 9.8m LT, elevation 142.2 to 9.7 m RT, elevation 142.1.

Make these changes in pen and ink.

Apply the following notes to the 1200mm X 19.5m RCP Class III pipe only:

- 1) These pipes are meant to be dry.
- 2) Do not put highway drainage into these pipes.
- 3) Pipes should be as perpendicular to road as possible.
- 4) No inlet or outlet protection is needed.
- 5) Minor grading at inlets and outlets may be necessary.
- 6) No work is to take place in the mapped vernal pool.
- 7) An exclusion zone will be set up around the vernal pool.
- 8) Inlets and outlets need to be level with surrounding ground. No hanging ends will be allowed.
- 9) A representative from the Departments Environmental Office must be present during installation.

Make these changes in pen and ink.



PRINTED ON RECYCLED PAPER

Consider these changes and information prior to submitting your bid on November 14, 2007.

Sincerely,

A handwritten signature in black ink, appearing to read "Scott Bickford". The signature is stylized and includes a small "Foy" written at the end.

Scott Bickford
Contracts & Specifications Engineer

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010015.00

PROJECT(S): NH-1001(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 MAIN ITEMS						
0010	201.11 CLEARING	3.400 HA				
0020	201.23 REMOVING SINGLE TREE TOP ONLY	7.000 EA				
0030	201.24 REMOVING STUMP	7.000 EA				
0040	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0050	203.20 COMMON EXCAVATION	52000.000 M3				
0060	203.21 ROCK EXCAVATION	1350.000 M3				
0070	203.2318 DISPOSAL OF SPECIAL WASTE	50.000 MG				
0080	203.242 DIRTY BORROW	2200.000 M3				
0090	203.25 GRANULAR BORROW	860.000 M3				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010015.00

PROJECT(S): NH-1001(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	50.000 M3				
0110	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	100.000 M3				
0120	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1200.000 M3				
0130	403.208 HOT MIX ASPHALT 12.5 MM, SURFACE	3800.000 MG				
0140	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	240.000 MG				
0150	409.15 BITUMINOUS TACK COAT APPLIED	7700.000 L				
0160	509.12 STEEL STRUCTURAL PLATE PIPE ARCH:	LUMP	LUMP			
0170	510.10 SPECIAL DETOUR _____ (M) ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 4.2 M RDW. WIDTH	LUMP	LUMP			
0180	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			
0190	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010015.00

PROJECT(S): NH-1001(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	527.3031 ENERGY ABSORBING SYSTEM (ET - PLUS)	2.000 EA				
0210	603.159 300 MM CULVERT PIPE OPTION III	27.000 M				
0220	603.16 375 MM CULVERT PIPE OPTION I	63.000 M				
0230	603.17 450 MM CULVERT PIPE OPTION I	56.000 M				
0240	603.175 450 MM RCP CLASS III	20.000 M				
0250	603.179 450 MM CULVERT PIPE OPTION III	39.000 M				
0260	603.19 600 MM CULVERT PIPE OPTION I	67.000 M				
0270	603.195 600 MM RCP CLASS III	135.000 M				
0280	603.21 900 MM CULVERT PIPE OPTION I	14.000 M				
0290	603.215 900 MM REINFORCED CONCRETE PIPE CLASS III	24.000 M				
0300	603.225 1050 MM REINFORCED CONCRETE PIPE CLASS III	70.000 M				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010015.00

PROJECT(S): NH-1001(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0310	603.235 1200 MM REINFORCED CONCRETE PIPE CLASS III	39.000 M				
0320	604.092 CATCH BASIN TYPE B1-C	5.000 EA				
0330	605.09 150 MM UNDERDRAIN TYPE B	270.000 M				
0340	605.11 300 MM UNDERDRAIN TYPE C	135.000 M				
0350	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	970.000 M				
0360	606.232 GUARDRAIL TYPE 3C - OVER 4.5 M RADIUS	55.000 M				
0370	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA				
0380	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	22.000 EA				
0390	606.356 UNDERDRAIN DELINEATOR POST	3.000 EA				
0400	606.47 SINGLE WOOD POST	6.000 EA				
0410	606.78 LOW VOLUME GUARDRAIL END - TYPE 3	2.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010015.00

PROJECT(S): NH-1001(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0420	606.79 GUARDRAIL 350 FLARED TERMINAL	9.000 EA				
0430	607.17 CHAIN LINK FENCE - 1.8 METER	88.000 M				
0440	607.32 BRACING ASSEMBLY TYPE I - METAL POSTS	2.000 EA				
0450	607.33 BRACING ASSEMBLY TYPE II - METAL POSTS	1.000 EA				
0460	609.31 CURB TYPE 3	440.000 M				
0470	610.08 PLAIN RIPRAP	400.000 M3				
0480	610.16 HEAVY RIPRAP	500.000 M3				
0490	610.18 STONE DITCH PROTECTION	55.000 M3				
0500	610.210 STREAM CHANNEL ROCKS	50.000 M3				
0510	610.212 STREAM CHANNEL SAND	100.000 M3				
0520	613.319 EROSION CONTROL BLANKET	2800.000 M2				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010015.00

PROJECT(S): NH-1001(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	615.07 LOAM	110.000 M3				
0540	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	270.000 UN				
0550	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	180.000 UN				
0560	619.1201 MULCH - PLAN QUANTITY	450.000 UN				
0570	619.1301 BARK MULCH	30.000 M3				
0580	620.54 STABILIZATION GEOTEXTILE	1450.000 M2				
0590	620.58 EROSION CONTROL GEOTEXTILE	2200.000 M2				
0600	621.396 DWARF EVERGREENS (450 MM - 600 MM) GROUP B	250.000 EA				
0610	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	9100.000 M				
0620	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0630	629.05 HAND LABOR, STRAIGHT TIME	100.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010015.00

PROJECT(S): NH-1001(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0640	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	25.000 HR				
0650	631.11 AIR TOOL (INCLUDING OPERATOR)	25.000 HR				
0660	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	50.000 HR				
0670	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	25.000 HR				
0680	631.22 FRONT END LOADER (INCLUDING OPERATOR)	25.000 HR				
0690	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			
0700	652.312 TYPE III BARRICADE	4.000 EA				
0710	652.33 DRUM	100.000 EA				
0720	652.34 CONE	110.000 EA				
0730	652.35 CONSTRUCTION SIGNS	70.000 M2				
0740	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	390.000 CD				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010015.00

PROJECT(S): NH-1001(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0750	652.38 FLAGGER	7500.000 HR				
0760	652.41 PORTABLE - CHANGEABLE MESSAGE SIGN	2.000 EA				
0770	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0780	659.10 MOBILIZATION	LUMP	LUMP			
0790	660.21 ON-THE-JOB TRAINING (BID)	2000.000 HR				
SECTION 0001 TOTAL						.

SECTION 0002 ALTERNATE PAVEMENT 1
ALT GROUP AP1

0800	304.09 AGGREGATE BASE COURSE - CRUSHED	28800.000 M3				
0810	403.207 HOT MIX ASPHALT 19.0 MM NOMINAL MAX SIZE	3950.000 MG				
0820	403.213 HOT MIX ASPHALT 12.5 MM, BASE	4750.000 MG				
SECTION 0002 TOTAL						.

SECTION 0003 ALTERNATE PAVEMENT 2
ALT GROUP AP2

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010015.00

PROJECT(S): NH-1001(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0830	304.09 AGGREGATE BASE COURSE - CRUSHED	27700.000 M3				
0840	310.24 PLANT MIX RECYCLED ASPHALT PAVEMENT - 100 MM DEPTH	23500.000 M2				
0850	403.207 HOT MIX ASPHALT 19.0 MM NOMINAL MAX SIZE	5500.000 MG				
	SECTION 0003 TOTAL					
	TOTAL BID W/CHOSEN ALT.					