



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE  
04333-0016

JOHN ELIAS BALDACCI  
GOVERNOR

DAVID A. COLE  
COMMISSIONER

May 8, 2008  
Subject: **Harpwell**  
Project No. AC-BH-A109 (000)X  
Pin No. 011090.00  
**Amendment No. 4**

Dear Sir/Ms:

The following questions have been received:

**Question:** Reference Amendments #2 & #3: How long does the contractor supplied Mabey or Acrow bridge need to be? Can a Mabey or Acrow bridge be furnished for the long spans at and adjacent to the navigation channel with conventional bridging for flanking spans?

**Response:** A minimum of 500 feet in length and 24 feet curb to curb shall be required/supplied. The flanking spans can be contractor supplied material. The flanking spans are still to be 20 feet curb to curb with a transition to 24 feet.

**Question:** Reference Glue-Lam. Timber Rail: The specs are asking for ACQ treatment. The suppliers are telling us they can't glue ACQ treated lumber. Can the spec be revised to include CCA treatment?

**Response:** We will be investigating the change from ACQ to CCA; another addendum will be issued based on the findings.

Consider this information prior to submitting your bid on **May 14, 2008**.

Sincerely,

Scott Bickford  
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER