



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

May 22, 2008
Subject: **Auburn**
Project No. STP-1159(800)X
Pin No. 011598.00
Amendment No.2

Dear Sir/Ms:

Make the following changes to the Bid Documents:

In the Bid Book, **REMOVE** the "SCHEDULE OF ITEMS" (pages 3 through 8 in the Bid Book dated 080424) and **REPLACE** with the attached new "SCHEDULE OF ITEMS" (6 pages dated 080522)

In the Bid Book, **ADD** the attached "SPECIAL PROVISIONS, SECTION 621, LANDSCAPE, (Plant Species Specification and Quantities List) after page 81 (SPECIAL PROVISION, SECTION 608).

In the Plans, PLAN Sheet 6 of 38, under "GENERAL NOTES" **DELETE**, in it's entirety, Note 6. Make this change in pen and ink.

The following questions have been received:

Question: Schedule of Items, Item No. 621.202, no species is specified? What species would you like?

Response: See Special Provision 621 added in this amendment.

Question: General note #6 calls for Green Acrylic Latex on all paved islands. I am unable to locate any paved islands on the plans. Please clarify the location of the paved islands. If Latex is used, how will it be paid for?

Response: See the above pen and ink change concerning the Green Acrylic Latex. The islands referenced in the notes are labeled on the Plan Sheets as Raised Concrete. The planned treatment is stamped, colored concrete, Item 502.345. See the special provision for this item.

Question: Please clarify the locations and limits for the various sidewalk items, they are not called out in the Plans.



PRINTED ON RECYCLED PAPER

Response: Sidewalks from Station 12+46 to 21+45, left and right, will be Reinforced Concrete Sidewalk, Item 608.08 and Structural Concrete, Colored Pavement, Item 502.345. See the Typical Section for details.

The sidewalk section at approx. Station 21+75 Lt, Station 4+10 to 5+00 Lt, and Station 6+10 to 25+10 Lt, will be Brick, Item 608.17. See Amendment #1 for details.

Existing brick at remaining locations will be left in place. If directed by the Resident, Item 608.10, Brick Sidewalk (Remove and Rebuild) will be used. See Amendment #1 for details.

All pedestrian ramps will be rebuilt, Reinforced Concrete Sidewalk, Item 608.08. See General Note 37.

The sidewalk quantities in the schedule of items are correct.

Question: Please verify the quantity of 8" PVC. After review of the Plans, I am unable to come up with the quantity listed in the Schedule of Items.

Response: The existing catch basin at 16+50 Lt may be eliminated, if directed by the Resident. If not, Catch Basin F5-C and 8" PVC may be used as directed to connect to the basin at 18+50 Lt

Question: There is no Special Provision for pavement removal. How is it to be removed and what is included in that Pay Item?

Response: Item 202.202, Removing Pavement Surface has been changed to Item 202.20 Removing Bituminous Concrete Pavement. See the Standard Specifications. The intent is to remove all of the existing pavement, shape the existing material, and placing aggregate surface course. See General Note 18 regarding cobblestones.

Consider these changes and information prior to submitting your bid on **May 28, 2008**.

Sincerely,

Handwritten signature of Scott Bickford in black ink, with the initials 'S.B.' and 'FOR' visible.

Scott Bickford
Contracts & Specifications Engineer

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011598.00

PROJECT(S): STP-1159(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 PROJECT ITEMS

0010	201.23 REMOVING SINGLE TREE TOP ONLY	1.000 EA				
0020	201.24 REMOVING STUMP	1.000 EA				
0030	202.20 REMOVING BITUMINOUS CONCRETE PAVEMENT	8743.000 SY				
0040	203.20 COMMON EXCAVATION	390.000 CY				
0050	203.25 GRANULAR BORROW	20.000 CY				
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	170.000 CY				
0070	403.1021 TEXTURED ASPHALT PAVEMENT	300.000 SY				
0080	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	696.000 T				
0090	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	37.000 T				
0100	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	1624.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011598.00

PROJECT(S): STP-1159(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	409.15 BITUMINOUS TACK COAT - APPLIED	450.000 G				
0120	411.09 UNTREATED AGGREGATE SURFACE COURSE	753.000 CY				
0130	502.341 STRUCTURAL CONCRETE ROADWAY MEDIAN	5.000 CY				
0140	502.345 STRUCTURAL CONCRETE - COLORED PAVEMENT	24.000 CY				
0150	603.1311 8 " PVC PIPE	225.000 LF				
0160	603.159 12 INCH CULVERT PIPE OPTION III	300.000 LF				
0170	604.15 MANHOLE	2.000 EA				
0180	604.16 ALTERING CATCH BASIN TO MANHOLES	4.000 EA				
0190	604.167 ALTER CATCH BASIN GRATE TO CASCADE	10.000 EA				
0200	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	2.000 EA				
0210	604.2403 SPECIAL BASIN	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011598.00

PROJECT(S): STP-1159(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	604.2412 BEHIND CURB INLET	1.000 EA				
0230	604.247 CATCH BASIN TYPE F5-C	1.000 EA				
0240	604.252 CATCH BASIN TYPE A5-C	2.000 EA				
0250	605.09 6 INCH UNDERDRAIN TYPE B	50.000 LF				
0260	608.08 REINFORCED CONCRETE SIDEWALK	1200.000 SY				
0270	608.10 BRICK SIDEWALK, REMOVE AND REBUILD	23.000 SY				
0280	608.17 BRICK SIDEWALK WITH CONCRETE BASE	225.000 SY				
0290	608.26 CURB RAMP DETECTABLE WARNING FIELD	216.000 SF				
0300	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	55.000 LF				
0310	609.234 TERMINAL CURB TYPE 1 - 4 FOOT	8.000 EA				
0320	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	6.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011598.00

PROJECT(S): STP-1159(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	609.34 CURB TYPE 5	245.000 LF				
0340	609.35 CURB TYPE 5 - CIRCULAR	75.000 LF				
0350	609.38 RESET CURB TYPE 1	1291.000 LF				
0360	615.07 LOAM	65.000 CY				
0370	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	5.200 UN				
0380	619.1201 MULCH - PLAN QUANTITY	5.200 UN				
0390	621.202 MEDIUM DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP B	12.000 EA				
0400	621.80 ESTABLISHMENT PERIOD	LUMP	LUMP			
0410	626.033 POLYVINYL CONDUIT	3600.000 LF				
0420	626.11 PRECAST CONCRETE JUNCTION BOX	4.000 EA				
0430	626.22 NON-METALLIC CONDUIT	100.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011598.00

PROJECT(S): STP-1159(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	626.31 18 INCH FOUNDATION	25.000 EA				
0450	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	5990.000 LF				
0460	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	1200.000 SF				
0470	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0480	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0490	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0500	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	3.000 HR				
0510	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	3.000 HR				
0520	634.16 HIGHWAY LIGHTING	LUMP	LUMP			
0530	634.2041 LUMINAIRES	24.000 EA				
0540	634.206 LIGHT STANDARD FOR POST TOP LUMINAIRE	24.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011598.00

PROJECT(S): STP-1159(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	634.208 REMOVE AND RESET LIGHT STANDARDS	1.000 EA				
0560	634.315 #8 AWG COPPER WIRE	2400.000 LF				
0570	652.31 TYPE I BARRICADE	5.000 EA				
0580	652.312 TYPE III BARRICADE	3.000 EA				
0590	652.33 DRUM	25.000 EA				
0600	652.34 CONE	75.000 EA				
0610	652.35 CONSTRUCTION SIGNS	620.000 SF				
0620	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0630	652.38 FLAGGER	3500.000 HR				
0640	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

SPECIAL PROVISIONS
 SECTION 621
 LANDSCAPE
 (Plant Species Specification and Quantities List)

The following list of items provides the estimated quantities for use on this project. The scientific name of the plant material is provided along with the common name in parenthesis.

The contractor shall follow MDOT Standard Specifications Rev. December, 2002 for landscape materials and installation procedures (sec 621).

The MDOT Landscape Architect or his designee will be available to inspect plant materials and stake the location of plant materials at the time of planting.

The Landscape sub-contractor shall be required to excavate a planting pit to the full planting depth of the plant materials measuring minimum 4' - 0" x 6' - 0" and replace with an amended topsoil planting mix to match finished grades. Excavation and backfill of planting pit will be incidental to tree planting. Note this will require coordination of tree locations with existing utilities, and coordination of schedule of seeding of esplanade with Method No.1 Seeding mix.

In accordance with Section 104.5.9, a separate Performance Bond will not be required for the Landscape portion of this contract. A Maintenance Bond for a Two-Year Establishment period in the full value of the planting contract shall be included in this project.

PLANT MATERIALS

ITEM NO	Description	Unit	Quantity	Total
621.202	Small Deciduous Trees Group A 2" – 2 ½" cal. B&B	Ea.		12
	Syringa reticulate 'Ivory Silk' ('Ivory Silk' Japanese Tree Lilac)			
621.80	Establishment Period- Two Year	LS	1	1

* * *