



JOHN ELIAS BALDACCI
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

DAVID A. COLE
COMMISSIONER

January 14, 2008
Subject: Cumberland Bridge Replacement
Project No. BR-1267(900)X
Pin No's 012679.00
Amendment No. 3

Dear Sir/Ms:

Please make the following change to the Bid Documents.

In the Bid Book, Remove the "schedule of items" dated **080109** (four pages total) and replace with the updated "schedule of items" dated **080114** (four pages total).

The following question has been received.

Questions: With the short duration of this project, the long lead time to setup utilities (esp... DSL) and in the interest of saving money on the project would the Dept. consider removing the 639.10 Office Trailer item from the schedule of items?

Answer: Item 639.10 Office Trailer has been eliminated from the new schedule of items.

Consider these changes and information prior to submitting your bid on **January 16, 2008.**

Sincerely,


Scott Bickford
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012679.00

PROJECT(S): BR-1267(900)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	1350.000 CY				
0030	203.2318 DISPOSAL OF SPECIAL WASTE	45.000 T				
0040	203.24 COMMON BORROW	60.000 CY				
0050	203.25 GRANULAR BORROW	265.000 CY				
0060	203.33 SPECIAL FILL	45.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1385.000 CY				
0080	403.207 HOT MIX ASPHALT 19.0 MM HMA	203.000 T				
0090	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	268.000 T				
0100	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	15.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012679.00

PROJECT(S): BR-1267(900)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	409.15 BITUMINOUS TACK COAT - APPLIED	42.000 G				
0120	509.411 ALUMINUM STRUCTURAL PLATE BOX CULVERT	LUMP	LUMP			
0130	511.07 COFFERDAM: Downstream	LUMP	LUMP			
0140	511.07 COFFERDAM: Upstream	LUMP	LUMP			
0150	603.16 15 INCH CULVERT PIPE OPTION I	50.000 LF				
0160	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	262.500 LF				
0170	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	32.000 LF				
0180	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0190	606.79 GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0200	610.08 PLAIN RIPRAP	280.000 CY				
0210	610.18 STONE DITCH PROTECTION	72.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012679.00

PROJECT(S): BR-1267(900)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	613.319 EROSION CONTROL BLANKET	100.000 SY				
0230	615.07 LOAM	35.000 CY				
0240	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	5.000 UN				
0250	619.1201 MULCH - PLAN QUANTITY	5.000 UN				
0260	619.1401 EROSION CONTROL MIX	20.000 CY				
0270	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	975.000 LF				
0280	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				
0290	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0300	631.132 SMALL BULLDOZER (INCLUDING OPERATOR)	10.000 HR				
0310	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0320	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012679.00

PROJECT(S): BR-1267(900)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	652.38 FLAGGER	150.000 HR				
0340	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0350	652.41 PORTABLE - CHANGEABLE MESSAGE SIGN	3.000 EA				
0360	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0370	659.10 MOBILIZATION	LUMP	LUMP			
0380	830.10 WATER MAIN BRIDGE CROSSING	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					