



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE  
04333-0016

JOHN ELIAS BALDACCI  
GOVERNOR

DAVID A. COLE  
COMMISSIONER

October 6, 2009  
Subject: **Brooks**  
State Pin No's: 012717.00 & 014309.00  
**Amendment No. 4**

Dear Sir/Ms:

In the Bid Book (pages 3 thru 8): **REMOVE** the "SCHEDULE OF ITEMS" 6 pages dated 090924 (replaced in Bid Amendment #2) and **REPLACE** with the attached new "SCHEDULE OF ITEMS" 6 pages dated 091006.

In the Plans, SHEET NUMBER 5 OF 29, **CHANGE** Note #21 from "...3 inch Untreated Aggregate Surface Course unless otherwise noted in the plans or directed by the Resident." to read as follows "...Untreated Aggregate Surface Course as directed by the Resident." Make this change in pen & ink.

The following questions have been received:

**Question:** Due to the possibility on inconsistent pavement depth, varying existing cross slope and other conditions, - how will the quantity of 304.10 be measured?

**Response:** ASCG will be measured in-place using approved methods.

**Question:** Note 21 calls for 3" of untreated aggregate to be used for grading driveways – as there is no 411.10 item in the bid item, how will this item be paid for?

**Response:** See new Schedule of Items.

**Question:** Would precast footers for the strut be acceptable?

**Response:** Please refer to Special Provision 534 – section 534.20 & 534.30. The Department will review the stamped design. Precast footers are not prohibited.

Consider these changes information prior to submitting your bid on October 7, 2009.

Sincerely,

Scott Bickford  
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012717.00

PROJECT(S): 012717.00

014309.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.23 REMOVING SINGLE TREE TOP ONLY	4.000 EA				
0020	201.24 REMOVING STUMP	4.000 EA				
0030	202.20 REMOVING BITUMINOUS CONCRETE PAVEMENT	4430.000 SY				
0040	203.20 COMMON EXCAVATION	210.000 CY				
0050	203.21 ROCK EXCAVATION	20.000 CY				
0060	203.2312 HEALTH AND SAFETY PLAN	LUMP	LUMP			
0070	203.2333 DISPOSAL OF SPECIAL EXCAVATION	800.000 T				
0080	204.41 REHABILITATION OF EXISTING SHOULDERS, PLAN QUANTITY	1529.000 SY				
0090	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	20.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012717.00

PROJECT(S): 012717.00  
014309.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	30.000 CY				
0110	211.21 INSLOPE REHABILITATION	1150.000 LF				
0120	211.30 DITCH EXCAVATION	700.000 LF				
0130	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	2300.000 CY				
0140	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	510.000 T				
0150	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	200.000 T				
0160	403.213 HOT MIX ASPHALT 12.5 MM BASE	860.000 T				
0170	409.15 BITUMINOUS TACK COAT - APPLIED	160.000 G				
0180	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	50.000 CY				
0190	507.0841 STEEL PIPE HAND RAILING	LUMP	LUMP			
0200	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012717.00

PROJECT(S): 012717.00

014309.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			
0220	603.04 4" PVC DRAIN SERVICE	10.000 LF				
0230	603.16 15 INCH CULVERT PIPE OPTION I	237.000 LF				
0240	603.17 18 INCH CULVERT PIPE OPTION I	15.000 LF				
0250	603.179 18 INCH CULVERT PIPE OPTION III	40.000 LF				
0260	603.199 24 INCH CULVERT PIPE OPTION III	270.000 LF				
0270	603.21 36 INCH CULVERT PIPE OPTION I	40.000 LF				
0280	603.42 30 INCH REINFORCED CONCRETE PIPE CLASS IV	32.000 LF				
0290	604.092 CATCH BASIN TYPE B1-C	5.000 EA				
0300	604.097 72 INCH CATCH BASIN TYPE B1-C	2.000 EA				
0310	605.09 6 INCH UNDERDRAIN TYPE B	514.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012717.00

PROJECT(S): 012717.00

014309.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	605.10 6 INCH UNDERDRAIN OUTLET	20.000 LF				
0330	605.13 18 INCH UNDERDRAIN TYPE C	470.000 LF				
0340	606.356 UNDERDRAIN DELINEATOR POST	2.000 EA				
0350	606.47 SINGLE WOOD POST	2.000 EA				
0360	609.31 CURB TYPE 3	760.000 LF				
0370	610.08 PLAIN RIPRAP	10.000 CY				
0380	613.319 EROSION CONTROL BLANKET	240.000 SY				
0390	615.07 LOAM	30.000 CY				
0400	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	30.000 UN				
0410	619.1201 MULCH - PLAN QUANTITY	30.000 UN				
0420	620.56 DRAINAGE GEOTEXTILE	30.000 SY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012717.00

PROJECT(S): 012717.00  
014309.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0440	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0450	631.111 TRACTOR MOUNTED HYDRAULIC HAMMER	4.000 HR				
0460	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0470	631.13 BULLDOZER (INCLUDING OPERATOR)	5.000 HR				
0480	631.14 GRADER (INCLUDING OPERATOR)	5.000 HR				
0490	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0500	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR				
0510	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	5.000 HR				
0520	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	4.000 HR				
0530	639.19 FIELD OFFICE TYPE B	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012717.00

PROJECT(S): 012717.00

014309.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			
0550	652.33 DRUM	20.000 EA				
0560	652.34 CONE	50.000 EA				
0570	652.35 CONSTRUCTION SIGNS	30.000 SF				
0580	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	68.000 CD				
0590	652.38 FLAGGER	2000.000 HR				
0600	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0610	659.10 MOBILIZATION	LUMP	LUMP			
	TOTAL BID					