



STATE OF MAINE
 DEPARTMENT OF TRANSPORTATION
 16 STATE HOUSE STATION
 AUGUSTA, MAINE
 04333-0016

JOHN ELIAS BALDACCI
 GOVERNOR

DAVID A. COLE
 COMMISSIONER

November 5, 2010
 Subject: **Jay Wilton**
 State Pin No: 012774.00
Amendment No. 1

Dear Sir/Ms:

Make the following changes to the bid Document:

In the Bid Book (pages 4 thru 9), **REMOVE** the “SCHEDULE OF ITEMS”, 6 pages dated 101022 and **REPLACE** with the attached new “SCHEDULE OF ITEMS”, 6 pages dated 101105.

In the Bid Book, after page 73, **ADD** the attached “SPECIAL PROVISION, SECTION 502, STRUCTURAL CONCRETE, (QC/QA Acceptance Methods), 1 page dated November 5, 2010.

In the Bid Book, before page 74, **ADD** the attached “SPECIAL PROVISION, SECTION 502, STRUCTURAL CONCRETE BOX CULVERT REPAIR”, 1 page dated November 5, 2010.

In the Plans, SHEET NUMBER 3 OF 147, make the following **CHANGES** in pen and ink;

1. **CHANGE** the Quantity for Item 403.208 – HOT MIX ASPHALT 12.5 MM HMA SURFACE, from “5511 T” to read “**3675 T**”.
2. **DELETE** Item “**534.71 – PRECAST CONCRETE BOX CULVERT – 1 – CY**”
3. **ADD** Item “**502.302 – STRUCTURAL CONCRETE BOX CULVERT, REPAIR – 1-LS**”.

In the Plans, SHEET NUMBER 6 OF 147, to the right of “ITEM 201.11 – CLEARING”, **ADD** “ITEM 607.24 – REMOVE AND RESET FENCE” as listed below in pen and ink;

“607.24 REMOVE AND RESET FENCE

Station	Station	Side	Length (Ft)	Comment
21+50	23+50	RT	200.0	Barbed Wire
26+50	29+00	RT	250.0	Barbed Wire
41+00	49+00	LT	800.0	Barbed Wire
44+25	44+75	RT	50.0	Barbed Wire
77+50	79+75	LT	225.0	Electric
95+75	97+00	LT	125.0	Post and Rail

Total = 1650.0LF”



PRINTED ON RECYCLED PAPER

The following questions have been received:

Question: Item 403.207 – 3” – Est. Tonnage 5520 T

Item 403.208 – 2” – Est. Tonnage – 5511 T

Unless additional areas of surface are to be done, 5511 T seems too high?

Response: The Quantity for Item No. 403.208 Hot Mix Asphalt, 12.5 mm HMA Surface shall be 3675 T. Please see the attached new Schedule Of Items.

Question: Is pavement removal incidental to item 203.20? Who owns the removed pavement?

Response: Pavement removal that is not covered by a specific pavement removal item is to be paid under Item 203.20 Common Excavation. The removed pavement is the property of the Contractor.

Question: Item 607.24 – Remove and Reset Fence – 1650lf, what kind of fence, what kind of post and where is it located?

Response: Please see the above pen and ink change.

Question: Do you have details for the box culvert?

Response: Please see the above changes.

Consider these changes and information prior to submitting your bid on November 17, 2010.

Sincerely,

A handwritten signature in black ink that reads "Scott Bickford FOR". The signature is written in a cursive style.

Scott Bickford
Contracts & Specifications Engineer

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012774.00

PROJECT(S): STP-1277(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.11 CLEARING	1.530 AC				
0020	201.23 REMOVING SINGLE TREE TOP ONLY	28.000 EA				
0030	201.24 REMOVING STUMP	36.000 EA				
0040	203.20 COMMON EXCAVATION	19830.000 CY				
0050	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	50.000 CY				
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	19234.000 CY				
0070	403.207 HOT MIX ASPHALT 19.0 MM HMA	5520.000 T				
0080	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	3675.000 T				
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	300.000 T				
0100	409.15 BITUMINOUS TACK COAT - APPLIED	910.000 G				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012774.00

PROJECT(S): STP-1277(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	10.000 CY				
0120	502.302 STRUCTURAL CONCRETE BOX CULVERT, REPAIR	LUMP	LUMP			
0130	603.16 15 INCH CULVERT PIPE OPTION I	790.000 LF				
0140	603.17 18 INCH CULVERT PIPE OPTION I	190.000 LF				
0150	603.179 18 INCH CULVERT PIPE OPTION III	400.000 LF				
0160	603.19 24 INCH CULVERT PIPE OPTION I	20.000 LF				
0170	603.199 24 INCH CULVERT PIPE OPTION III	160.000 LF				
0180	603.219 36 INCH CULVERT PIPE OPTION III	110.000 LF				
0190	603.239 48 INCH CULVERT PIPE OPTION III	22.000 LF				
0200	604.092 CATCH BASIN TYPE B1-C	12.000 EA				
0210	604.096 60 INCH CATCH BASIN TYPE B1-C	2.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012774.00

PROJECT(S): STP-1277(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	604.244 CATCH BASIN TYPE F4	6.000 EA				
0230	604.245 CATCH BASIN TYPE F4-C	1.000 EA				
0240	605.09 6 INCH UNDERDRAIN TYPE B	1320.000 LF				
0250	605.10 6 INCH UNDERDRAIN OUTLET	60.000 LF				
0260	605.11 12 INCH UNDERDRAIN TYPE C	705.000 LF				
0270	605.12 15 INCH UNDERDRAIN TYPE C	545.000 LF				
0280	605.13 18 INCH UNDERDRAIN TYPE C	660.000 LF				
0290	605.15 24 INCH UNDERDRAIN TYPE C	621.000 LF				
0300	605.17 30 INCH UNDERDRAIN TYPE C	350.000 LF				
0310	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	213.000 LF				
0320	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012774.00

PROJECT(S): STP-1277(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	606.356 UNDERDRAIN DELINEATOR POST	3.000 EA				
0340	606.47 SINGLE WOOD POST	23.000 EA				
0350	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0360	607.24 REMOVE AND RESET FENCE	1650.000 LF				
0370	608.08 REINFORCED CONCRETE SIDEWALK	113.000 SY				
0380	609.31 CURB TYPE 3	4150.000 LF				
0390	610.08 PLAIN RIPRAP	180.000 CY				
0400	610.18 STONE DITCH PROTECTION	680.000 CY				
0410	613.319 EROSION CONTROL BLANKET	6690.000 SY				
0420	615.07 LOAM	1778.000 CY				
0430	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	90.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012774.00

PROJECT(S): STP-1277(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	289.000 UN				
0450	619.1201 MULCH - PLAN QUANTITY	378.000 UN				
0460	620.58 EROSION CONTROL GEOTEXTILE	2380.000 SY				
0470	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	29205.000 LF				
0480	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0490	629.05 HAND LABOR, STRAIGHT TIME	30.000 HR				
0500	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0510	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR				
0520	639.18 FIELD OFFICE TYPE A	1.000 EA				
0530	643.60 FLASHING BEACON AT:	LUMP	LUMP			
0540	652.33 DRUM	10.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012774.00

PROJECT(S): STP-1277(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	652.34 CONE	100.000 EA				
0560	652.35 CONSTRUCTION SIGNS	1060.000 SF				
0570	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	280.000 CD				
0580	652.38 FLAGGER	10000.000 HR				
0590	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0600	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

SPECIAL PROVISION
SECTION 502
STRUCTURAL CONCRETE
(QC/QA Acceptance Methods)

CLASS OF CONCRETE	ITEM NUMBER	DESCRIPTION	P	METHOD
A	502.302	Struct.Concrete Box Culvert Repair	-	C

Jay - Wilton
12774.00
November 5, 2010

SPECIAL PROVISION
SECTION 502
STRUCTURAL CONCRETE BOX CULVERT REPAIR

Description. The Contractor shall remove existing deteriorated concrete and place new structural concrete as shown on the design drawings or as directed by the Construction Manager.

Materials. Concrete shall meet the requirements of Special Provision, Section 502 (Method C).

Method of Measurement. The quantity of Structural Concrete Box Culvert Repair will be measured by the Lump Sum.

Basis of Payment. Payment will be for the accepted quantity of Structural Concrete Box Culvert Repair at the Contract unit price each, which price shall be full compensation for all labor, equipment, materials, and incidentals to complete the specified Work, including concrete removal, structural excavation, reinforcing steel, concrete, silica fume, backfilling, and protective coating.

Pay Item	Description	Pay Unit
502.302	Structural Concrete Box Culvert Repair	Lump Sum