



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

September 8, 2009
Subject: **Sidney Weigh Station**
Federal Project No. IM—95-1314(200)E
State Pin No.013142.00
Amendment No. 2

DAVID A. COLE
COMMISSIONER

Dear Sir/Ms:

Make the following change to the Bid Document:

In the Bid Book, pages 4 through 9, **REMOVE** the “SCHEDULE OF ITEMS” 6 pages dated 090814 and **REPLACE** with the attached new “SCHEDULE OF ITEMS” 6 pages dated 090908.

The following questions have been received:

Question: How far should we figure to haul the granite curbing for stacking?

Response: Approximately 11 miles.

Question: There are several inconsistencies between the door hardware specification and what is called for on plan sheet 24. Also, the door for the pump house is not included in the door schedule, so I would like to confirm the hardware requirements for that door:

- Are electric strikes required?
- Is a card reader system required?
- Are mortise locks required?
- Are closers required on both doors?
- Are kick plates required on both sides of both doors?
- What is the correct function for each lockset?


Response: Are electric strikes required? No
Is a card reader system required? No
Are mortise locks required? Yes
Are closers required on both doors? Yes
Are kick plates required on both sides of both doors? Yes
What is the correct function for each lockset? The Pump house door should be easily secured by a key and lock.

Consider this change and information prior to submitting your bid on September 9, 2009.



PRINTED ON RECYCLED PAPER

Sincerely,

A handwritten signature in dark ink, appearing to read "Scott Bickford". The signature is written in a cursive style with a large initial "S" and a distinct "B".

Scott Bickford
Contracts & Specifications Engineer

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013142.00

PROJECT(S): IM-95-1314(200)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.23 REMOVING SINGLE TREE TOP ONLY	11.000 EA				
0020	201.24 REMOVING STUMP	12.000 EA				
0030	202.08 REMOVING BUILDING NO.:	LUMP	LUMP			
0040	202.203 PAVEMENT BUTT JOINTS	55.000 SY				
0050	203.20 COMMON EXCAVATION	1550.000 CY				
0060	203.21 ROCK EXCAVATION	275.000 CY				
0070	203.24 COMMON BORROW	270.000 CY				
0080	203.242 DIRTY BORROW	230.000 CY				
0090	203.25 GRANULAR BORROW	20.000 CY				
0100	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	2825.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013142.00

PROJECT(S): IM-95-1314(200)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.207 HOT MIX ASPHALT 19.0 MM HMA	765.000 T				
0120	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	13.000 T				
0130	403.210 HOT MIX ASPHALT 9.5 MM HMA	760.000 T				
0140	403.211 HOT MIX ASPHALT (SHIMMING)	45.000 T				
0150	403.213 HOT MIX ASPHALT 12.5 MM BASE	265.000 T				
0160	409.15 BITUMINOUS TACK COAT - APPLIED	580.000 G				
0170	603.191 24 INCH CORRUGATED METAL PIPE	12.000 LF				
0180	604.164 REBUILDING CATCH BASIN	1.000 EA				
0190	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	1.000 EA				
0200	605.09 6 INCH UNDERDRAIN TYPE B	267.000 LF				
0210	607.17 CHAIN LINK FENCE - 6 FOOT	60.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013142.00

PROJECT(S): IM-95-1314(200)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	607.49 DRIVE GATEWAY 40 FOOT METAL	1.000 EA				
0230	607.491 DRIVE GATEWAY - 36' METAL	1.000 EA				
0240	609.441 CURBING REMOVED AND STACKED	186.000 LF				
0250	610.08 PLAIN RIPRAP	3.000 CY				
0260	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	45.000 UN				
0270	619.12 MULCH	45.000 UN				
0280	626.11 PRECAST CONCRETE JUNCTION BOX	9.000 EA				
0290	626.23 PREWIRED CONDUIT SECONDARY WIRING	3335.000 LF				
0300	626.231 SECONDARY WIRING - INSPECTION BLD. (2"C-(3)#3)	420.000 LF				
0310	626.232 SECONDARY WIRING - PUMP EQUIP. BLD. (2"C-(3)#10)	400.000 LF				
0320	626.32 24 INCH FOUNDATION	24.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013142.00

PROJECT(S): IM-95-1314(200)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0340	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0350	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR				
0360	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR				
0370	634.16 HIGHWAY LIGHTING	LUMP	LUMP			
0380	634.166 TELEPHONE SERVICE	LUMP	LUMP			
0390	634.167 HEAT TRACING SYSTEM	LUMP	LUMP			
0400	634.168 PUMP EQUIPMENT & WIRING	LUMP	LUMP			
0410	634.2041 LUMINAIRES	22.000 EA				
0420	634.206 LIGHT STANDARD FOR POST TOP LUMINAIRE	22.000 EA				
0430	634.2071 REMOVE EXISTING HIGH-MAST POLE & LUMINAIRES	10.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013142.00

PROJECT(S): IM-95-1314(200)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	645.113 REINSTALL GUIDE SIGN	1.000 EA				
0450	652.312 TYPE III BARRICADE	4.000 EA				
0460	652.33 DRUM	30.000 EA				
0470	652.34 CONE	100.000 EA				
0480	652.35 CONSTRUCTION SIGNS	700.000 SF				
0490	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0500	652.38 FLAGGER	500.000 HR				
0510	659.10 MOBILIZATION	LUMP	LUMP			
0520	DIV. 15 MECHANICAL	LUMP	LUMP			
0530	DIV. 16 ELECTRICAL	LUMP	LUMP			
0540	DIV. 3 CONCRETE	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013142.00

PROJECT(S): IM-95-1314(200)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	DIV. 5 METALS	LUMP	LUMP			
0560	DIV. 6 WOOD & PLASTICS	LUMP	LUMP			
0570	DIV. 7 THERMAL & MOISTURE PROTECTION	LUMP	LUMP			
0580	DIV. 8 DOORS & WINDOWS	LUMP	LUMP			
0590	DIV. 9 FINISHES	LUMP	LUMP			
	TOTAL BID					