



STATE OF MAINE  
 DEPARTMENT OF TRANSPORTATION  
 16 STATE HOUSE STATION  
 AUGUSTA, MAINE  
 04333-0016

JOHN ELIAS BALDACCI  
 GOVERNOR

DAVID A. COLE  
 COMMISSIONER

July 13, 2009  
 Subject: **Lisbon**  
 Federal Project No: BR-A510(000)X  
 State Pin No: 015100.00  
**Amendment No. 1**

Dear Sir/Ms:

Make the following changes to the Bid Documents:

In the Bid Book (pages 4 through 9), **REMOVE** the "SCHEDULE OF ITEMS", 6 pages dated 090619 and **REPLACE** with the attached new "SCHEDULE OF ITEMS", 6 pages dated 090713.

In the Bid Book, page 38, **REMOVE** "SPECIAL PROVISION, SECTION 107, PROSECUTION AND PROGRESS, (Contract Time)", 1 page dated 6-15-09 and **REPLACE** with the attached new "SPECIAL PROVISION, SECTION 107, PROSECUTION AND PROGRESS, (Contract Time)", 1 page dated 7-10-09.

In the Bid Book, page 63, **REMOVE** "SPECIAL PROVISION, SECTION 502, STRUCTURAL CONCRETE, (QC/QA Acceptance Methods)" 1 page dated June 17, 2009 and **REPLACE** with the attached new "SPECIAL PROVISION, SECTION 502, STRUCTURAL CONCRETE, (QC/QA Acceptance Methods)" 1 page dated July 10.

In the Plans, SHEET NUMBER 2, **ADD** the following to the "ESTIMATED QUANTITIES" in pen and ink:

502.49	Structural Concrete Curbs	10	CY
631.172	Truck – Large	20	HR

The following questions have been received:

**Question:** With such an aggressive completion date, what durations will the State commit to for award and review times of submittals?

**Response:** We anticipate sending out the Intent to Award Memo within a week of bid opening.

**Question:** How are the concrete curbs paid?

**Response:** Please see the new attached Schedule of items.



PRINTED ON RECYCLED PAPER

**Question:** In the Schedule of Items, the following items appear to be missing;

409.15 – Tack  
502.49 – Curbs

**Response:** Item 409.15, Tack, is incidental to the pavement pay items, See Special Provision 403 on page 62 of the Bid Book. Item 502.49 has been added to the Schedule of Items in this amendment.

Consider these changes and information prior to submitting your bid on July 15, 2009.

Sincerely,

A handwritten signature in black ink, appearing to read "Scott Bickford". The signature is stylized and cursive.

Scott Bickford  
Contracts & Specifications Engineer

SCHEDULE OF ITEMS

CONTRACT ID: 015100.00

PROJECT(S): 015100.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	600.000 CY				
0030	203.24 COMMON BORROW	570.000 CY				
0040	203.25 GRANULAR BORROW	270.000 CY				
0050	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	310.000 CY				
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1050.000 CY				
0070	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	140.000 T				
0080	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	13.000 T				
0090	403.213 HOT MIX ASPHALT 12.5 MM BASE	95.000 T				
0100	501.231 DYNAMIC LOADING TEST	2.000 EA				

SCHEDULE OF ITEMS

CONTRACT ID: 015100.00

PROJECT(S): 015100.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	501.48 STEEL H-BEAM PILES 74 LBS/FT, DELIVERED	270.000 LF				
0120	501.481 STEEL H-BEAM PILES 74 LBS/FT, IN PLACE	220.000 LF				
0130	501.90 PILE TIPS	6.000 EA				
0140	501.91 PILE SPLICES	3.000 EA				
0150	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0160	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0170	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP			
0180	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0190	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	9000.000 LB				
0200	503.13 REINFORCING STEEL, PLACING	9000.000 LB				

SCHEDULE OF ITEMS

CONTRACT ID: 015100.00

PROJECT(S): 015100.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	503.14 EPOXY COATED REINFORCING STEEL, FABRICATED AND DELIVERED	29300.000 LB				
0220	503.15 EPOXY COATED REINFORCING STEEL PLACING	29300.000 LB				
0230	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0240	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0250	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			
0260	511.07 COFFERDAM: ABUTMENT #1	LUMP	LUMP			
0270	511.07 COFFERDAM: ABUTMENT #2	LUMP	LUMP			
0280	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0290	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0300	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0310	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				

SCHEDULE OF ITEMS

CONTRACT ID: 015100.00

PROJECT(S): 015100.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	603.17 18 INCH CULVERT PIPE OPTION I	20.000 LF				
0330	603.179 18 INCH CULVERT PIPE OPTION III	80.000 LF				
0340	603.19 24 INCH CULVERT PIPE OPTION I	28.000 LF				
0350	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0360	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	112.500 LF				
0370	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	6.000 EA				
0380	606.78 LOW VOLUME GUARDRAIL ENDS - TYPE 3	4.000 EA				
0390	610.08 PLAIN RIPRAP	630.000 CY				
0400	610.18 STONE DITCH PROTECTION	75.000 CY				
0410	613.319 EROSION CONTROL BLANKET	125.000 SY				
0420	615.0701 LOAM - PLAN QUANTITY	50.000 CY				

SCHEDULE OF ITEMS

CONTRACT ID: 015100.00

PROJECT(S): 015100.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	9.000 UN				
0440	619.1201 MULCH - PLAN QUANTITY	9.000 UN				
0450	619.1401 EROSION CONTROL MIX	100.000 CY				
0460	620.58 NONWOVEN GEOTEXTILE	750.000 SY				
0470	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	1575.000 LF				
0480	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0490	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0500	631.131 SMALL BULLDOZER-GRADER (INCLUDING OPERATOR)	10.000 HR				
0510	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR )	10.000 HR				
0520	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0530	637.071 DUST CONTROL	LUMP	LUMP			

SCHEDULE OF ITEMS

CONTRACT ID: 015100.00

PROJECT(S): 015100.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	639.19 FIELD OFFICE TYPE B	1.000 EA				
0550	652.312 TYPE III BARRICADE	4.000 EA				
0560	652.33 DRUM	10.000 EA				
0570	652.34 CONE	10.000 EA				
0580	652.35 CONSTRUCTION SIGNS	600.000 SF				
0590	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0600	652.38 FLAGGER	40.000 HR				
0610	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0620	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

SPECIAL PROVISION  
SECTION 107  
PROSECUTION AND PROGRESS  
(Contract Time)

The road shall be closed and traffic detoured around the site in accordance with the signs and details shown on the plans.

Once the contractor closes the road, work shall be performed in a continuous manner by the contractor.

The Contractor shall conduct his operation in such a manner that the bridge will be paved and be completed and open to two lanes of traffic on or before **NOVEMBER 15, 2009**.

Supplemental Liquidated damages of \$500 a day shall be assessed to the contractor for any day that the bridge is not open to two lanes of vehicular traffic after **November 15<sup>th</sup>, 2009**

The Specified contract completion date is May 15<sup>th</sup>, 2010.

SPECIAL PROVISION  
SECTION 502  
STRUCTURAL CONCRETE  
(QC/QA Acceptance Methods)

CLASS OF CONCRETE	ITEM NUMBER	DESCRIPTION	P	METHOD
A	502.219	Structural Concrete, Abutments and Retaining Walls	\$400	A
A	502.26	Structural Concrete Roadway and Sidewalk Slabs on Steel	\$400	A
LP	526.34	Perm. Concrete Transition Barrier		C
LP	502.49	Structural Concrete Curbs and Sidewalks		C

P values listed above reflect the price per cubic yard (CY) for all pay adjustment purposes.