



STATE OF MAINE
 DEPARTMENT OF TRANSPORTATION
 16 STATE HOUSE STATION
 AUGUSTA, MAINE
 04333-0016

JOHN ELIAS BALDACCI
 GOVERNOR

DAVID A. COLE
 COMMISSIONER

December 28, 2009
 Subject: **Swanville**
 Federal Project No: BR-1561(700)X
 State Project No. 015617.00
Amendment No. 2

Dear Sir/Ms:

Make the following changes to the Bid Documents:

In the Bid Book (pages 4 through 8), **REMOVE** the “SCHEDULE OF ITEMS, 5 pages dated 091214 and **REPLACE** it with the attached new “SCHEDULE OF ITEMS, 5 pages dated 091228.

In the Bid Book (page 29), SPECIAL PROVISIONS, SECTION 104, Utilities, under the paragraph titled TOWN OF SWANVILLE, **REMOVE** the following sentence in its entirety; “**The excavation of the trench is incidental to Item 203.20, Common Excavation.**” Make this change in pen and ink.

In the Plans, SHEET NUMBER 2 OF 12, make the following **CHANGES** in pen and ink:

- 1) **ADD ITEM 615.07 Loam, 20 CY**
- 2) Under Item 652.35, **CHANGE** the quantity from 250 SF to read **450** SF
- 3) **REMOVE** Note 18 in its entirety.

In the Plans, SHEET NUMBER 11 OF 12, **CHANGE** note 1. to read as follows:

“1. In addition to these signs, the contractor shall install (~~4~~, 2 at each end of bridge), type III barricades in a position to close off the project.”

Make this change in pen and ink.

The following questions have been received:

Question: Due to the Holidays, can the bid date be moved to 1/13/10?

Response: The Bid Opening date was changed in Amendment #1.

Question: Page 29 of the Bid Book states excavation of the trench for the dry hydrant is under common excavation but Special Provision 834.322 states that payment is Lump Sum. Please Clarify?



PRINTED ON RECYCLED PAPER

Response: All excavation will be paid under Item 834.322. (Please see changes in this amendment)

Question: Special Provision 403 calls for method “B” HMA. Can the spec. be changed to method “D” for all HMA due to the small quantity and short run of pavement?

Response: The Department would like to keep method “B”.

Question: Is the excavation of FairPoint’s existing conduit (to expose it to be moved) the Contractor’s responsibility?

Response: No, it is FairPoint’s responsibility.

Question: Is this a stimulus project?

Response: No

Question: How is the removal of the existing bridge/culvert to be paid for?

Response: It is included in the Precast Item since it is a minor structure. See 206.049 of the Standard Specifications.

Question: The basis of payment for 534.71 states that the excavation and backfill for the Box Culvert will be paid for under the provided contract items. Is this correct?

Response: All payment is included in the Precast Box Item.

Question: Are the detour signs shown on Plan Sheet 11 of 12 included in the quantity for Item 652.35, “Construction Signs”?

Response: No, the square footage is incorrect and has been changed in this amendment to 450 sf.

Question: Note 1 on Sheet 11 of 12 states that there are 8 type III Barricades required, but only 4 are listed in the Schedule of Values. Please clarify.

Response: 4 type III barricades are correct; please see changes in this Amendment.

Question: Is it possible to get a detail/drawing that shows the existing structure better?

Response: No existing plans are available.

Question: On sheet 2 of 12, General note 10 directs the Contractor to place loam on new or reconstructed side slopes or as directed by the Resident, but there is no pay item for loam in the Schedule of Values. How will this material be paid for?

Response: Loam (Item 615.07) has been added to the new Schedule of Items included in this amendment.

Consider these changes and information prior to submitting your bid on **January 13, 2010.**

Sincerely,

A handwritten signature in dark ink, appearing to read "Scott Bickford", with a long horizontal flourish extending to the right.

For Scott Bickford
Contracts & Specifications Engineer

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015617.00

PROJECT(S): BR-1561(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	203.20 COMMON EXCAVATION	320.000 CY				
0020	203.24 COMMON BORROW	5.000 CY				
0030	203.25 GRANULAR BORROW	224.000 CY				
0040	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	205.000 CY				
0050	403.207 HOT MIX ASPHALT 19.0 MM HMA	25.000 T				
0060	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	47.000 T				
0070	409.15 BITUMINOUS TACK COAT - APPLIED	11.000 G				
0080	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			
0090	511.07 COFFERDAM: CULVERT NO.1	LUMP	LUMP			
0100	511.07 COFFERDAM: CULVERT NO.2	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015617.00

PROJECT(S): BR-1561(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0120	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			
0130	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	75.000 LF				
0140	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	50.000 LF				
0150	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA				
0160	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0170	606.79 GUARDRAIL 350 FLARED TERMINAL	2.000 EA				
0180	610.08 PLAIN RIPRAP	144.000 CY				
0190	613.319 EROSION CONTROL BLANKET	15.000 SY				
0200	615.07 LOAM	20.000 CY				
0210	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	1.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015617.00

PROJECT(S): BR-1561(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	619.1201 MULCH - PLAN QUANTITY	1.000 UN				
0230	620.54 STABILIZATION GEOTEXTILE	430.000 SY				
0240	620.58 EROSION CONTROL GEOTEXTILE	55.000 SY				
0250	620.65 REINFORCEMENT GEOGRID	195.000 SY				
0260	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	210.000 LF				
0270	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0280	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	10.000 HR				
0290	631.11 AIR TOOL (INCLUDING OPERATOR)	10.000 HR				
0300	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0310	631.132 SMALL BULLDOZER (INCLUDING OPERATOR)	10.000 HR				
0320	631.14 GRADER (INCLUDING OPERATOR)	10.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015617.00

PROJECT(S): BR-1561(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	10.000 HR				
0340	639.19 FIELD OFFICE TYPE B	1.000 EA				
0350	652.312 TYPE III BARRICADE	4.000 EA				
0360	652.33 DRUM	10.000 EA				
0370	652.34 CONE	20.000 EA				
0380	652.35 CONSTRUCTION SIGNS	450.000 SF				
0390	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	60.000 CD				
0400	652.38 FLAGGER	50.000 HR				
0410	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0420	659.10 MOBILIZATION	LUMP	LUMP			
0430	834.322 DRY HYDRANT - INSTALL ONLY	LUMP	LUMP			
	SECTION 0001 TOTAL					.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015617.00

PROJECT(S): BR-1561(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0002 OPTION NO.1 TEMPORARY PEDESTRIAN BRIDGE						
0440	510.11 SPECIAL DETOUR, PEDESTRIAN TRAFFIC ONLY	LUMP	LUMP			
	SECTION 0002 TOTAL					
	TOTAL BID					