



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

October 4, 2010
Subject: **Carmel**
Federal Project No: BR-1562(200)X
State Pin No: 015622.00
Amendment No. 3

Dear Sir/Ms:

Make the following change to the Bid Document:

In the Bid Book (pages 4 thru 10), **REMOVE** the "SCHEDULE OF ITEMS" (replaced in Amendment #2), 8 pages dated 101004 and **REPLACE** with the attached new "SCHEDULE OF ITEMS", 8 pages dated 101004.

Consider this change prior to submitting your bid on October 6, 2010.

Sincerely,

A handwritten signature in black ink, appearing to read 'Scott Bickford'.

Scott Bickford
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

SCHEDULE OF ITEMS

CONTRACT ID: 015622.00

PROJECT(S): BR-1562(200)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.11 REMOVING PORTLAND CEMENT CONCRETE PAVEMENT	1620.000 SY				
0020	202.15 REMOVING MANHOLE OR CATCH BASIN	1.000 EA				
0030	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0040	202.202 REMOVING PAVEMENT SURFACE	900.000 SY				
0050	203.20 COMMON EXCAVATION	3400.000 CY				
0060	203.2318 DISPOSAL OF SPECIAL WASTE	100.000 T				
0070	203.24 COMMON BORROW	10155.000 CY				
0080	203.25 GRANULAR BORROW	2625.000 CY				
0090	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	5.000 CY				
0100	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	1165.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015622.00

PROJECT(S): BR-1562(200)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	3150.000 CY				
0120	403.207 HOT MIX ASPHALT 19.0 MM HMA	1020.000 T				
0130	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	435.000 T				
0140	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	40.000 T				
0150	403.213 HOT MIX ASPHALT 12.5 MM BASE	375.000 T				
0160	409.15 BITUMINOUS TACK COAT - APPLIED	55.000 G				
0170	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0180	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0190	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP	LUMP			
0200	502.56 CONCRETE FILL	140.000 CY				
0210	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	105755.000 LB				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015622.00

PROJECT(S): BR-1562(200)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	503.13 REINFORCING STEEL, PLACING	105755.000 LB				
0230	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP	LUMP			
0240	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0250	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 34'	LUMP	LUMP			
0260	512.081 FRENCH DRAINS	LUMP	LUMP			
0270	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0280	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	96.000 SY				
0290	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0300	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0310	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015622.00

PROJECT(S): BR-1562(200)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	535.60 PRESTRESSED STRUCTURAL CONCRETE SLAB	LUMP	LUMP			
0330	603.169 15 INCH CULVERT PIPE OPTION III	20.000 LF				
0340	603.179 18 INCH CULVERT PIPE OPTION III	420.000 LF				
0350	604.092 CATCH BASIN TYPE B1-C	1.000 EA				
0360	604.15 MANHOLE	1.000 EA				
0370	604.246 CATCH BASIN TYPE F5	1.000 EA				
0380	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0390	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	1200.000 LF				
0400	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	25.000 LF				
0410	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA				
0420	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015622.00

PROJECT(S): BR-1562(200)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	606.369 GUARDRAIL REMOVED AND STACKED	1240.000 LF				
0440	606.79 GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0450	607.15 DRIVE GATEWAY 16 FOOT - METAL	1.000 EA				
0460	607.19 CHAIN LINK FENCE - 8 FOOT	32.000 LF				
0470	609.31 CURB TYPE 3	135.000 LF				
0480	610.08 PLAIN RIPRAP	2.000 CY				
0490	613.319 EROSION CONTROL BLANKET	40.000 SY				
0500	615.0701 LOAM - PLAN QUANTITY	645.000 CY				
0510	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	2.000 UN				
0520	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	15.000 UN				
0530	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	88.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015622.00

PROJECT(S): BR-1562(200)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	619.1201 MULCH - PLAN QUANTITY	103.000 UN				
0550	619.1401 EROSION CONTROL MIX	1290.000 CY				
0560	621.044 EVERGREEN TREES (6 FOOT - 8 FOOT) GROUP B	3.000 EA				
0570	621.047 EVERGREEN TREES (8 FOOT - 9 FOOT) GROUP B	2.000 EA				
0580	621.273 LARGE DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP A	5.000 EA				
0590	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	3750.000 LF				
0600	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0610	629.05 HAND LABOR, STRAIGHT TIME	120.000 HR				
0620	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR				
0630	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	40.000 HR				
0640	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	80.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015622.00

PROJECT(S): BR-1562(200)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0650	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	20.000 HR				
0660	639.18 FIELD OFFICE TYPE A	1.000 EA				
0670	652.31 TYPE I BARRICADE	8.000 EA				
0680	652.312 TYPE III BARRICADE	8.000 EA				
0690	652.33 DRUM	50.000 EA				
0700	652.34 CONE	100.000 EA				
0710	652.35 CONSTRUCTION SIGNS	244.000 SF				
0720	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	150.000 CD				
0730	652.38 FLAGGER	240.000 HR				
0740	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0750	659.10 MOBILIZATION	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015622.00

PROJECT(S): BR-1562(200)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0760	660.21 ON-THE-JOB TRAINING (BID)	1000.000 HR				
	SECTION 0001 TOTAL					
	TOTAL BID					