



JOHN ELIAS BALDACCI
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

DAVID A. COLE
COMMISSIONER

June 8, 2009
Subject: **Bangor**
Federal Project No: STP-1585(300)S
State Pin No: 015853.00
Amendment No. 2

Dear Sir/Ms:

Make the following changes to the Bid Documents:

In the Bid Book (pages 5 through 8), **REMOVE** the "SCHEDULE OF ITEMS" (replaced in amendment #1), 5 pages dated 090605 and **REPLACE** with the attached new "SCHEDULE OF ITEMS" 4 pages dated 090608.

In the Plans, Drawing Number D2, **ADD** the following note under "TYPICAL TYPE 1 GRANITE CURB DETAIL" in pen and ink; "**The Concrete fill item has been deleted. Concrete fill shall be incidental to item 609.38 Reset Curb type I.**"

The following questions have been received:

Question: Can you tell us where the 60" Dia. Catch Basins are located and are there any details in relation to them? And the alt. and adj. CB items?

Response: Item 604.076 has been deleted as the developer has pulled these and substituted 6" UD in addendum 1. See the above Schedule of Items change.

Question: On the Haskell Road plans there appear to be raised concrete median islands but there is no bid item – are these part of the work and will MDOT add an item?

Response: Item 502.3412 Structural Concrete, Raised Island has been added and Item 502.56, Concrete Fill, has been deleted. See the above Schedule of Items change.

Question: Is the concrete fill item to be used in conjunction with the reset granite curb?



PRINTED ON RECYCLED PAPER

Response: The Concrete fill item has been deleted. Concrete fill shall be incidental to item 609.38 Reset Curb type I. See the above pen and ink change

Question: There are quite a few signs to be removed and reset on the Haskell Road plans. Is this by others or will MDOT add a bid item?

Response: Signs shall be removed and reset by the contractor and paid for under the appropriate equipment rental items.

Consider these changes and information prior to submitting your bid on June 10, 2009.

Sincerely,

A handwritten signature in black ink, appearing to read "Scott Bickford". The signature is written in a cursive style with a large initial "S".

Scott Bickford
Contracts & Specifications Engineer

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015853.00

PROJECT(S): STP-1585(300)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 HIGHWAY ITEMS						
0010	202.203 PAVEMENT BUTT JOINTS	1075.000 SY				
0020	203.20 COMMON EXCAVATION	790.000 CY				
0030	304.08 AGGREGATE BASE COURSE - SCREENED	155.000 CY				
0040	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	455.000 CY				
0050	403.207 HOT MIX ASPHALT 19.0 MM HMA	140.000 T				
0060	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	20.000 T				
0070	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	20.000 T				
0080	403.210 HOT MIX ASPHALT 9.5 MM HMA	1350.000 T				
0090	403.212 HOT MIX ASPHALT 4.75 MM	2000.000 T				
0100	409.15 BITUMINOUS TACK COAT - APPLIED	2300.000 G				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015853.00

PROJECT(S): STP-1585(300)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	502.3412 STRUCTURAL CONCRETE, RAISED ISLAND	22.000 CY				
0120	604.161 ALTERING CATCH BASIN	1.000 EA				
0130	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	1.000 EA				
0140	605.09 6 INCH UNDERDRAIN TYPE B	656.000 LF				
0150	606.21 GUARDRAIL TYPE 3B - 15 FOOT RADIUS AND LESS	25.000 LF				
0160	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	137.500 LF				
0170	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	25.000 LF				
0180	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	7.000 EA				
0190	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0200	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0210	609.31 CURB TYPE 3	1110.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015853.00

PROJECT(S): STP-1585(300)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	609.38 RESET CURB TYPE 1	700.000 LF				
0230	615.07 LOAM	50.000 CY				
0240	618.13 SEEDING METHOD NUMBER 1	5.000 UN				
0250	619.12 MULCH	5.000 UN				
0260	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	50126.000 LF				
0270	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	2600.000 SF				
0280	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0290	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0300	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0310	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0320	643.71 TRAFFIC SIGNAL MODIFICATION	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015853.00

PROJECT(S): STP-1585(300)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	652.33 DRUM	10.000 EA				
0340	652.34 CONE	40.000 EA				
0350	652.35 CONSTRUCTION SIGNS	714.000 SF				
0360	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	46.000 CD				
0370	652.38 FLAGGER	1510.000 HR				
0380	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA				
0390	659.10 MOBILIZATION	LUMP	LUMP			
	TOTAL BID					