



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE  
04333-0016

JOHN ELIAS BALDACCI  
GOVERNOR

DAVID A. COLE  
COMMISSIONER

May 17, 2010  
Subject: **Emden**  
State Pin No: 016699.00  
**Amendment No. 1**

Dear Sir/Ms:

Make the following changes to the Bid Documents:

In the Bid Book (pages 4 thru 8), **REMOVE** the "SCHEDULE OF ITEMS" 5 pages dated 100426 and **REPLACE** with the attached new "SCHEDULE OF ITEMS" 5 pages dated 100514.

In the Plans, Sheet Number 2 of 22, "ESTIMATED QUANTITIES", make the following **CHANGES** in pen and ink:

**REMOVE** Item 652.39 – WORK ZONE TRAFFIC CONTROL – 1 – LS

**ADD** Item **652.361 – MAINTENANCE OF TRAFFIC CONTROL DEVICES (140 CD) - 1 - LS**

The following question has been received:

**Question:** Who is the manufacturer and what is the heaviest section of the state provided precast concrete box culvert?

**Response:** The precaster is Oldcastle in Auburn. The heaviest piece is 25 tons.

Consider this change and information prior to submitting your bid on May 19, 2010.

Sincerely,

*FOR*

Scott Bickford  
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016699.00

PROJECT(S): 016699.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	3090.000 CY				
0030	203.2318 DISPOSAL OF SPECIAL WASTE	120.000 T				
0040	203.24 COMMON BORROW	5.000 CY				
0050	203.25 GRANULAR BORROW	600.000 CY				
0060	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	10.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1890.000 CY				
0080	403.207 HOT MIX ASPHALT 19.0 MM HMA	630.000 T				
0090	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	315.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016699.00

PROJECT(S): 016699.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	5.000 T				
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	315.000 T				
0120	409.15 BITUMINOUS TACK COAT - APPLIED	225.000 G				
0130	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0140	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			
0150	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			
0160	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	60.000 LF				
0170	534.7101 PRECAST CONCRETE BOX CULVERT - STATE SUPPLIED	LUMP	LUMP			
0180	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	600.000 LF				
0190	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0200	606.369 GUARDRAIL REMOVED AND STACKED	200.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016699.00

PROJECT(S): 016699.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0220	610.08 PLAIN RIPRAP	375.000 CY				
0230	610.18 STONE DITCH PROTECTION	100.000 CY				
0240	613.319 EROSION CONTROL BLANKET	205.000 SY				
0250	615.07 LOAM	6.000 CY				
0260	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	1.000 UN				
0270	619.1401 EROSION CONTROL MIX	170.000 CY				
0280	620.58 EROSION CONTROL GEOTEXTILE	580.000 SY				
0290	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2100.000 LF				
0300	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0310	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016699.00

PROJECT(S): 016699.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	631.13 BULLDOZER (INCLUDING OPERATOR)	20.000 HR				
0330	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0340	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR )	20.000 HR				
0350	631.16 ROLLER, PAVEMENT (INCLUDING OPERATOR)	20.000 HR				
0360	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0370	639.18 FIELD OFFICE TYPE A	1.000 EA				
0380	652.312 TYPE III BARRICADE	6.000 EA				
0390	652.33 DRUM	12.000 EA				
0400	652.34 CONE	24.000 EA				
0410	652.35 CONSTRUCTION SIGNS	607.000 SF				
0420	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016699.00

PROJECT(S): 016699.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	652.38 FLAGGER	100.000 HR				
0440	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0450	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					