



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Paul R. LePage  
GOVERNOR

David Bernhardt  
COMMISSIONER

March 17, 2011  
Subject: **Denmark**  
State PIN: 017529.00  
**Amendment No. 2**

Dear Sir/Ms:

Make the following changes to the Bid Documents:

In the Bid Book (pages 3 thru 6) **REMOVE** the "SCHEDULE OF ITEMS" 4 pages dated 110224 and **REPLACE** with the attached new "SCHEDULE OF ITEMS" 4 pages dated 110309.

In the Plans, SHEET NUMBER 5 OF 11, "ESTIMATED QUANTITIES" **CHANGE** Item "534.7102 – PRECAST STRUCTURAL CONCRETE – 1 – LS" to read as follows: "**534.71 – PRECAST CONCRETE BOX CULVERT – 1 – LS**". Make this change in pen and ink.

The following question has been received:

**Question:** Will MDOT supply rebar detail for the retaining wall?

**Response:** No please refer to Special Provision 534;  
534.10 Description The Contractor shall design, manufacture, furnish, and install elements, precast structural concrete structures, arches, or box culverts and associated wings, headwalls, and appurtenances, in accordance with the contract documents."

Consider this change and information prior to submitting your bid on March 23, 2011.

Sincerely,

Scott Bickford  
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017529.00

PROJECT(S): 017529.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.23 REMOVING SINGLE TREE TOP ONLY	4.000 EA				
0020	201.24 REMOVING STUMP	4.000 EA				
0030	203.2001 COMMON EXCAVATION - PLAN QUANTITY	321.000 CY				
0040	203.25 GRANULAR BORROW	100.000 CY				
0050	304.104 AGGREGATE SUBBASE COURSE (PLAN QUANTITY)	251.000 CY				
0060	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	70.000 T				
0070	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	10.000 T				
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	150.000 T				
0090	409.15 BITUMINOUS TACK COAT - APPLIED	30.000 G				
0100	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017529.00

PROJECT(S): 017529.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			
0120	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	140.000 LF				
0130	526.40 RESETTING TEMPORARY CONCRETE BARRIER TYPE I	140.000 LF				
0140	527.303 ENERGY ABSORBING SYSTEM (ET-PLUS)	2.000 EA				
0150	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			
0160	603.19 24 INCH CULVERT PIPE OPTION I	38.000 LF				
0170	606.24 GUARDRAIL TYPE 3D - SINGLE RAIL	125.000 LF				
0180	606.242 GUARDRAIL TYPE 3D - OVER 15 FOOT RADIUS	50.000 LF				
0190	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA				
0200	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	4.000 EA				
0210	610.08 PLAIN RIPRAP	40.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017529.00

PROJECT(S): 017529.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	610.21 RIVER STONES	5.000 CY				
0230	610.211 STREAM CHANNEL GRAVEL	10.000 CY				
0240	615.07 LOAM	20.000 CY				
0250	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	3.000 UN				
0260	619.1201 MULCH - PLAN QUANTITY	3.000 UN				
0270	620.58 EROSION CONTROL GEOTEXTILE	70.000 SY				
0280	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	750.000 LF				
0290	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0300	629.05 HAND LABOR, STRAIGHT TIME	25.000 HR				
0310	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0320	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017529.00

PROJECT(S): 017529.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	631.22 FRONT END LOADER (INCLUDING OPERATOR)	10.000 HR				
0340	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			
0350	652.33 DRUM	30.000 EA				
0360	652.34 CONE	30.000 EA				
0370	652.35 CONSTRUCTION SIGNS	390.000 SF				
0380	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	47.000 CD				
0390	652.38 FLAGGER	100.000 HR				
0400	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0410	659.10 MOBILIZATION	LUMP	LUMP			
	TOTAL BID					