



Paul R. LePage
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

David Bernhardt
COMMISSIONER

March 31, 2011
Subject: **Kenduskeag**
Federal Project No: BR-1757(600)X
State PIN: 017576.00
Amendment No. 1

Dear Sir/Ms:

Make the following changes to the Bid Documents:

In the Bid Book (pages 4 thru 11) **REMOVE** the "SCHEDULE OF ITEMS" 8 pages dated 110308 and **REPLACE** with the attached new "SCHEDULE OF ITEMS" 8 pages dated 110330.

In the Plans, Sheet number 2 of 28, "ESTIMATED QUANTITIES", **DELETE** in its entirety "ITEM 502.56 – CONCRETE FILL – 60 – CY". Make this change in pen and ink.

The following questions have been received:

Question: Where on the project does the MDOT expect to use item 502.26, Concrete Fill? We find no references in the plans or specs for this item.

Response: Item No. 502.56, Concrete Fill, has been eliminated; please see the attached new Schedule of Items.

Question: The in water work from December 1 – March 30 to facilitate bridge removal for this season has passed. Will the in water work window be extended to allow the temporary pile bents prior to July 15th?

Response: No, the in water work window will not be extended to allow the temporary pile bents prior to July 15th. Please see paragraph 3 on page 36 of the contract book for information about possible work window extensions.



PRINTED ON RECYCLED PAPER

Consider these changes and information prior to submitting your bid on April 6, 2011.

Sincerely,

A handwritten signature in black ink, appearing to read "Scott Bickford". The signature is fluid and cursive, with a prominent "S" and "B".

Scott Bickford
Contracts & Specifications Engineer

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017576.00

PROJECT(S): BR-1757(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	570.000 CY				
0030	203.24 COMMON BORROW	5.000 CY				
0040	203.25 GRANULAR BORROW	1230.000 CY				
0050	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	1720.000 CY				
0060	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	150.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	665.000 CY				
0080	403.102 HOT MIX ASPHALT PAVEMENT - SPECIAL AREAS	5.000 T				
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	25.000 T				
0100	403.210 HOT MIX ASPHALT 9.5 MM	263.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017576.00

PROJECT(S): BR-1757(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	194.000 T				
0120	409.15 BITUMINOUS TACK COAT - APPLIED	27.000 G				
0130	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0140	502.22 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS (PLACED UNDER WATER)	610.000 CY				
0150	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP			
0160	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0170	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP	LUMP			
0180	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	82200.000 LB				
0190	503.13 REINFORCING STEEL, PLACING	82200.000 LB				
0200	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017576.00

PROJECT(S): BR-1757(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0220	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0230	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			
0240	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP	LUMP			
0250	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0260	511.07 COFFERDAM: ABUTMENT NO. 2	LUMP	LUMP			
0270	511.07 COFFERDAM: ABUTMENT NO.1	LUMP	LUMP			
0280	512.081 FRENCH DRAINS	LUMP	LUMP			
0290	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0300	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	275.000 SY				
0310	520.21 EXPANSION DEVICE - GLAND SEAL	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017576.00

PROJECT(S): BR-1757(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	523.52 BEARING INSTALLATION	12.000 EA				
0330	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	6.000 EA				
0340	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	6.000 EA				
0350	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	60.000 LF				
0360	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0370	527.303 ENERGY ABSORBING SYSTEM (ET-PLUS)	2.000 EA				
0380	603.179 18 INCH CULVERT PIPE OPTION III	155.000 LF				
0390	604.163 ABANDONING CATCH BASIN	1.000 EA				
0400	604.247 CATCH BASIN TYPE F5-C	2.000 EA				
0410	604.249 CATCH BASIN TYPE F6-C	1.000 EA				
0420	605.09 6 INCH UNDERDRAIN TYPE B	212.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017576.00

PROJECT(S): BR-1757(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0440	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	87.500 LF				
0450	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0460	606.79 GUARDRAIL 350 FLARED TERMINAL	2.000 EA				
0470	608.26 CURB RAMP DETECTABLE WARNING FIELD	23.000 SF				
0480	609.31 CURB TYPE 3	289.000 LF				
0490	610.08 PLAIN RIPRAP	290.000 CY				
0500	610.18 STONE DITCH PROTECTION	10.000 CY				
0510	613.319 EROSION CONTROL BLANKET	25.000 SY				
0520	615.07 LOAM	11.000 CY				
0530	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	1.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017576.00

PROJECT(S): BR-1757(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	2.000 UN				
0550	619.1401 EROSION CONTROL MIX	21.000 CY				
0560	620.58 EROSION CONTROL GEOTEXTILE	385.000 SY				
0570	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1050.000 LF				
0580	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	100.000 SF				
0590	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0600	631.121 HEAVY DUTY ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR				
0610	631.13 BULLDOZER (INCLUDING OPERATOR)	20.000 HR				
0620	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0630	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	20.000 HR				
0640	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	50.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017576.00

PROJECT(S): BR-1757(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0650	637.071 DUST CONTROL	LUMP	LUMP			
0660	639.18 FIELD OFFICE TYPE A	1.000 EA				
0670	652.312 TYPE III BARRICADE	4.000 EA				
0680	652.33 DRUM	12.000 EA				
0690	652.34 CONE	12.000 EA				
0700	652.35 CONSTRUCTION SIGNS	774.000 SF				
0710	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0720	652.38 FLAGGER	50.000 HR				
0730	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0740	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					