



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE  
04333-0016

JOHN ELIAS BALDACCI  
GOVERNOR

DAVID A. COLE  
COMMISSIONER

August 20, 2010  
Subject: **Brewer**  
Federal Project No: STP-1785(300)X  
State Pin No: 017853.00  
**Amendment No. 1**

Dear Sir/Ms:

Because of the fast pace of this project the Department felt that it was necessary to hold an onsite pre-bid conference, Wednesday August 18<sup>th</sup>.

The following items below were discussed:

- The pipe to be replaced is a 48" corrugated metal pipe and a new 48" corrugated pipe needs to be installed.
- All **instream** work needs to be completed by Oct 1<sup>st</sup>. contract completion is Oct 30, 2010.
- There is a 12" lead joint water main located above existing pipe.

There is a gate valve at Park Ave. The Water District will work with the Contractor nights after 10 pm to isolate water by installing an insertion valve or gate valve near Sunset Strip. If the Contractor wishes to isolate water, all of this work will be coordinated between the Contractor and the Brewer Water District.

- There is a 12" storm drain located above existing pipe.
- There is a 24" sewer line roughly 1 foot below pipe.
- Catch Basin on the left will be replaced.
- Catch Basin on the right will be replaced if needed
- New Utility poles have been installed and the lines will be moved before the project starts.
- The City of Brewer will allow a 1 week road closure. The detour has been established, signs will be paid under item 652.35 Construction Signs.
- All Gravel will be incidental to the Pipe installation.

Consider this information prior to submitting your bid on August 25, 2010.

Sincerely,

Scott Bickford

For Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER