



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

November 12, 2004
Subject: Pownal
Project No. BR-1106(100) X
PIN: 11061.00
Bid Amendment No. 3

Dear Sir/Ms.:

Please make the following changes to the Plan Sheets:

On Sheet 13 of 14 entitled "Concrete Collar Details" under the "Structural Plate Pipe Arch Notes"

Note No. 1, delete *All plates shall be 0.175 in thick* and replace with **All plates shall be 0.225 in thick.**

Add the following new Note # 7: The contractor shall assemble the pipe in accordance with the plans and specifications, **Temporary Steel Bolts** may be necessary to properly assemble the aluminum plates. **All Temporary Steel Bolts shall be removed and replaced with Aluminum Bolts after the pipe plates have been assembled. NO Temporary Steel Bolts shall be left in the Structural Plate Pipe Arch after it has been assembled.** This work shall be allowed at the resident's discretion and all costs associated with this work shall be considered incidental to the pipe items.

Make these changes in pen and ink.

Consider these changes prior to submitting your bid on November 17, 2004.

Sincerely,

Scott Bickford

Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER