STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCI
GOVERNOR

DAVID A. COLE
COMMISSIONER

January 29, 2007
Subject: **Waterville**
Pin No. 11492.00
Amendment No. 1

Dear Sir/Ms:

Please make the following change to the Bid Documents:

In the Book, REMOVE the existing: "Special Provision, Section 107, Time, (Bridge Closure, Limitation of Operations, & Supplemental Liquidated Damages)" dated December 14, 2006 one page total and REPLACE with the attached updated: "Special Provision, Section 107, Time, (Bridge Closure, Limitation of Operations, & Supplemental Liquidated Damages)" dated January 29, 2007 one page total.

The following question has been received.

Question: Is the 17 days to replace the water main added to the 35 day road closure for a total of 52 days allowed for the water main to be out of service?

Response: No, but see attached updated "Special Provision, Section 107, Time, (Bridge Closure, Limitation of Operations, & Supplemental Liquidated Damages)" added earlier in this amendment.

Consider this change and information prior to submitting your bid on January 31, 2007.

Sincerely,

Scott Bickford
Contracts & Specifications Engineer

PRINTED ON RECYCLED PAPER
THE MAINE DEPARMENT OF TRANSPORTATION IS AN AFFIRMATIVE ACTION - EQUAL OPPORTUNITY EMPLOYER

SPECIAL PROVISION
SECTION 107
TIME
(Bridge Closure, Limitation of Operations, & Supplemental Liquidated Damages)

The Contractor shall plan and conduct his operations in such a manner that State Route 104 is closed to traffic for a maximum of 35 consecutive days, after which time a minimum of one 12 foot lane of alternating traffic shall be maintained at all times. This closure will be allowed between June 25th, 2007 and September 1st, 2007. All traffic control items necessary to maintain one lane of alternating traffic shall be considered incidental to related contract items.

During the full closure, the Contractor will be required to remove and replace a section of water main owned by the Kennebec Water District to the limits shown on the plans and in accordance with General Provisions Section 890.01 and 830.10. The Contractor shall have a maximum of 21 consecutive days from the time that the water main is disconnected to such time that the new water main is placed back in service.

Should Route 104 remain closed to traffic beyond 35 consecutive days, the closure extend beyond September 1st, 2007, or the water main be out of service beyond 21 consecutive days, the Contractor shall be assessed supplemental liquidated damages at the rate of Five Hundred Dollars ($500.00) per day for each day that the roadway remains closed to traffic or the water main out of service. This assessment of supplemental liquidated damages will be in addition to the liquidated damages specified in Section 107 of the Standard Specifications.

The Contractor shall coordinate the Bridge Closure Notification in accordance with Standard Specification 104.4.10.

Once the Contractor commences work on this project the work shall be continuous through completion unless the work stoppage is allowed by the Resident.