



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

JOHN ELIAS BALDACCII
GOVERNOR

DAVID A. COLE
COMMISSIONER

May 25, 2007
Subject: **Gardiner-Randolph**
Project No. BH-1262(400)X
Pin No. 12624.00
Amendment No. 1

Dear Sir/Ms:

Please make the following changes to the Bid Documents:

In the Bid Book, REMOVE in its entirety the existing: "Schedule of Items" five pages total, dated 070502 and REPLACE with the attached updated: "Schedule of Items" five pages total, dated 070524.

In the Plans, on sheet two of ten titled: "Estimated Quantities" within the Estimated Quantities, on item "202.202 Removing Pavement Surface" DELETE the existing quantity of 465-SY and REPLACE it with the new quantity of 180-SY. Make this change in pen and ink.

On sheet two of ten titled: "Estimated Quantities" within the Estimated Quantities, on item "203.20 Common Excavation" DELETE the existing quantity of 155-CY and REPLACE it with the new quantity of 95-CY. Make this change in pen and ink.

On sheet two of ten titled: "Estimated Quantities" within the Estimated Quantities, on item "304.10 Aggr Subb Course - Gravel" DELETE the existing quantity of 155-CY and REPLACE it with the new quantity of 50-CY. Make this change in pen and ink.

On sheet two of ten titled: "Estimated Quantities" within the Estimated Quantities, on item "518.50 Repair of Upward Fac Surf – to Re Steel" DELETE the existing quantity of 10-SF and REPLACE with the new quantity of 2500-SF. Make this change in pen and ink.

On sheet two of ten titled: "Estimated Quantities" within the Estimated Quantities, on item "518.51 Repair of Upward Fac Surf-Below Re Steel" DELETE the existing quantity of 10-SF and REPLACE with the new quantity of 250-SF. Make this change in pen and ink.



PRINTED ON RECYCLED PAPER

On sheet four of ten titled: "Staging Plan" within "Staging Plan Cross Section, Phase One" and "Phase two" under "Phasing" ADD the following Note five to both: "5) Deck Repair". Make this change in pen and ink.

On sheet six of ten titled: "Abut. #1, Bearing, Sidewalk" on the: "Expansion Pedestal Chart Span #1 Pier #1", on the left of the chart that shows dimension in inches DELETE the text: "Toward Abutment No. 2 Toward Abutment No. 2" and REPLACE with the following: "Toward Abutment No.1 Toward Abutment No. 1". Make this change in pen and ink.

On sheet seven of ten titled: "Abutment #2" on the "Detail A Curtain Plate" to the end of the note that states: " ½" Reduced Base End Welded Stud with Locking Nut and Washer" ADD the following: "spaced at 12" on center"

On sheet seven of ten titled: "Abutment #2" on the "Typical Abutment No. 2 Cross Section" ADD the following note: "Lap and Adhere Trough Seam per Manufacturers Specifications". Place this note at the intersection of the Right and Left Trough

The following questions have been received.

Question: Bid item 202.202 Removing Pavement Surface seems to be called for at the approach for Abutment 1 (plan sheet six) and full depth removal item 203.20 Common Excavation at the approach for Abutment 2 (plan sheet seven), however the quantities for items 202.202, 203.20 and 304.10 seems to include both approaches. Please clarify.

Response: *See quantity changes made earlier in this amendment.*

Question: Is there any reinforcing in the overlay?

Response: *No, there isn't any reinforcing in the concrete wearing surface.*

Question: Please provide dead loads and live loads for item 523.1201.

Response: *The capacity of the bearing is 50 tons.*

Question: Can bearings be reset in two phases?

Response: *Yes, the bearings can be set in two phases.*

Question: Bid item 518.52 @ 10 cy doesn't seem to correspond with the other repair item quantities considering the condition and age of the bridge, please advise.

Response: *We anticipate using this item on the project, but have not assigned locations for the entire quantity.*

Question: Is bid item 502.21 and 502.26 for the joint replacements? I can't find any other location, however specification section 520 "Basis of Payment" calls for both removal and replacement of concrete to be incidental?


Response: *Yes, items 502.21 and 502.26 are for the concrete around the joint replacements. Concrete replacement and removal at abutment #1 is incidental to the 520 Items.*

Question: Item 516.23 is called out for in the 516.21 specs. (latex) if it not required for 403.224 shouldn't it be part of the Alternate No.2?

Response: *The deck shall be prepared for both alternates.*

Consider this information and changes prior to submitting your bid on May 30, 2007.

Sincerely,



Scott Bickford

Contracts & Specifications Engineer

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012624.00

PROJECT(S): BH-1262(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 ITEMS COMMON TO EITHER ALTERNATE						
0010	202.12 REMOVING EXISTING STRUCTURAL CONCRETE	100.000 CY				
0020	202.202 REMOVING PAVEMENT SURFACE	180.000 SY				
0030	202.30 REMOVING EXISTING CONCRETE WEARING SURFACE	LUMP	LUMP			
0040	203.20 COMMON EXCAVATION	95.000 CY				
0050	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	50.000 CY				
0060	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	50.000 T				
0070	409.15 BITUMINOUS TACK COAT APPLIED	50.000 G				
0080	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	3.000 CY				
0090	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP			
0100	502.341 STRUCTURAL CONCRETE ROADWAY MEDIAN	55.000 CY				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 2

SCHEDULE OF ITEMS

DATE: 070524

REVISED:

CONTRACT ID: 012624.00

PROJECT(S): BH-1262(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	4300.000 LB				
0120	503.13 REINFORCING STEEL, PLACING	4300.000 LB				
0130	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0140	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0150	516.23 PREPARATION OF NEW CONCRETE SURFACE	LUMP	LUMP			
0160	518.39 REPAIRING GRANITE CURB BEDDING MORTAR	200.000 LF				
0170	518.50 REPAIR OF UPWARD FACING SURFACES - TO REINFORCING STEEL < 7.9 IN.	2500.000 SF				
0180	518.51 REPAIR OF UPWARD FACING SURFACES - BELOW REINFORCING STEEL < 7.9 IN.	250.000 SF				
0190	518.52 REPAIR OF UPWARD FACING SURFACES > 7.9 IN.	10.000 CY				
0200	520.241 BRIDGE JOINT MODIFICATION TYPE 1	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012624.00

PROJECT(S): BH-1262(400)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	521.23 EXPANSION DEVISE FINGER JOINT	2.000 EA				
0220	521.32 FABRIC TROUGH FOR FINGER JOINT	2.000 EA				
0230	523.1201 RESET STEEL BEARING	10.000 EA				
0240	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0250	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN				
0260	610.08 PLAIN RIPRAP	10.000 CY				
0270	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	6200.000 LF				
0280	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	500.000 SF				
0290	627.77 REMOVING PAVEMENT MARKINGS	3100.000 SF				
0300	627.80 TEMPORARY RAISED PAVEMENT MARKER - MONODIRECTIONAL	20.000 EA				
0310	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 4

SCHEDULE OF ITEMS

DATE: 070524

REVISED:

CONTRACT ID: 012624.00

PROJECT(S): BH-1262(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	10.000 HR				
0330	637.071 DUST CONTROL	LUMP	LUMP			
0340	639.19 FIELD OFFICE TYPE B	1.000 EA				
0350	652.30 FLASHING ARROW BOARD	2.000 EA				
0360	652.31 TYPE I BARRICADE	4.000 EA				
0370	652.312 TYPE III BARRICADE	2.000 EA				
0380	652.33 DRUM	50.000 EA				
0390	652.34 CONE	50.000 EA				
0400	652.35 CONSTRUCTION SIGNS	500.000 SF				
0410	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0420	652.38 FLAGGER	100.000 HR				

SCHEDULE OF ITEMS

CONTRACT ID: 012624.00

PROJECT(S): BH-1262(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	652.41 PORTABLE - CHANGEABLE MESSAGE SIGN	EA 4.000				
0440	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0450	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					.
SECTION 0002 ALTERNATE NO.1 ALT GROUP AS1						
0460	403.324 ROSPHALT 50 HIGH PERFORMANCE RUBBERIZED ASPHALT	T 660.000				
	SECTION 0002 TOTAL					.
SECTION 0003 ALTERNATE NO.2 ALT GROUP AS2						
0470	516.21 LATEX MODIFIED MORTAR OR CONCRETE WEARING SURFACE ON BRIDGE	LUMP	LUMP			
	SECTION 0003 TOTAL					
	TOTAL BID					