

STATE OF MAINE DEPARTMENT OF TRANSPORTATION 16 STATE HOUSE STATION AUGUSTA, MAINE 04333-0016

DAVID A. COLE
COMMISSIONER

November 2, 2004 Subject: Searsport Project No. HP-8188(01)X PIN 8188.01 Bid Amendment No. 2

Dear Sir/Ms.:

Please make the following changes to your bid documents:

Delete page one of the "Schedule of Items" dated 040927 and replace with the attached page one of the "Schedule of Items" dated 041102.

Delete page five of the "Schedule of Items" dated 040927 and replace with the attached page five of the "Schedule of Items" dated 041102.

Delete page seven of the "Schedule of Items" dated 040927 and replace with the attached page seven of the "Schedule of Items" dated 041102.

The Department has received the following Requests for information:

- Q. Should there be an item on the Bid Form for required Base Gravel or is it incidental to another item?
- **R.** Please refer to the new "Schedule of Items" dated 041102.
- Q. Should there be an item on the Bid Form for the Fiber Optic hands free intercom or is it incidental to the security building?
- **R.** The hands free intercom system will be paid for under item 815.301 Security Entrance Building.
- Q. Is the wiring to be part of the conduit bid items throughout the site?
- **R.** Payment for wiring is provided for under item 844.19 Site Lighting and the 607 items for the Chain Link Fence Sliding Gates. All other wiring shall be paid for under item 815.301 Security Entrance Building. Wiring is not included in the conduit bid items, 626.212 and 626.221.



- Q. Are the Accessory Packs for the pipes fittings paid for by the pound or are they incidental?
- R. Accessories are considered incidental and will not be measured for payment.
- Q. What is the thickness of the concrete sidewalks around the security building?
- R. Sidewalks shall be 4" thick. Refer to MDOT Standard detail 608(01).
- Q. Can new water system be installed during the winter months?
- **R.** No, unless can comply with Special Provision Section 104 Coordination/Priority of Work.
- Q. Please provide clarification regarding the Railroad Crossing work. Montreal, Maine and Atlantic (MM&A) has indicated to a subcontractor that MM&A is going to give a price and do the work themselves. If this is true, will MM&A be quoting MDOT or the bidders and when?
- R. MM&A has decided to do all of the track work associated with the crossing. In order to cover this, the contractor will carry an allowance of \$60,000 to be paid under item 648.5203 and will be reimbursed for all actual cost billed by MM&A for the crossing construction, with no mark ups allowed. MM&A's work will include the removal of the existing rail, the furnishing and installation of all track, ties, OTM (other track material), ballast and the prefabricated rubber grade crossing material. The contractor will still be responsible for all the road work leading up to and in the crossing area, to include all sub base and base material, compaction, drainage, pavement, pavement markings, signs and the coordination of work activities with the Railroad and the Terminal Operator to be paid under item 648.5204.

Consider these changes and information prior to submitting your bid on November 3, 2004.

Sincerely,

Scott Bickford

Contracts & Specifications Engineer

PAGE:

DATE: 041102

SCHEDULE OF ITEMS REVISED:

CONTRACT ID: 008188.01 PROJECT(S): HP-8188(01)X

CONTRACTOR : | AND UNITS | DOLLARS | CTS | DOLLARS | CTS 1 SECTION 0001 BID ITEMS |201.12 SELECTIVE 0010|CLEARING AND THINNING - 1 0.500| AC | |201.24 REMOVING STUMP 10.000 0020| |203.21 ROCK EXCAVATION 00301 | CY |203.22 UNCLASSIFIED | 11840.000| 0040 | EXCAVATION |CY | |206.061 STRUCTURAL EARTH | 0060|EXCAVATION - DRAINAGE | 5850.000| |AND MINOR STRUCTURES, | CY |BELOW GRADE |304.08 AGGREGATE BASE | 4570.000 0065|COURSE - SCREENED | CY |304.10 AGGREGATE SUBBASE | | 3540.000| |CY | 0070|COURSE - GRAVEL 1 |403.207 HOT MIX ASPHALT | 0080|19.0 MM HMA | 5345.000| |403.208 HOT MIX ASPHALT | 2005.000| 0090|12.5 MM HMA SURFACE | ΙT |603.159 12 INCH CULVERT | 0100|PIPE OPTION III | 95.000| | | | | | | | | | |

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 008188.01 PROJECT(S): HP-8188(01)X

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY -		UNIT PRICE			BID AMOUNT		
NO	DESCRIPTION		_	DOLLARS	CTS	-	DOLLARS	CT	
0440	637.071 DUST CONTROL	 LUMP		 LUMP 	 		 	 	
0450	639.19 FIELD OFFICE TYPE B 	 1.00 EA	0	 	 		 	 	
	645.251 ROADSIDE GUIDE SIGNS 	 352.00 SF	0	 	 		 	 	
0470	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	 225.00 SF 	0	 	 		 	 	
0480	645.280 WOOD POST 	 24.00 EA	0	 	 		 	 	
	645.289 STEEL H-BEAM POLES 	 3000.00 LB	0	 	 		 	 	
	648.5203 GRADE CROSSING ALLOWANCE 	 LUMP \$60,000.0	0	 - -	LUM	P	 \$60,000.00 	1	
	648.5204 GRADE CROSSING MISCELLANEOUS 	 LUMP		 LUMP 	 		 	 	
	652.312 TYPE III BARRICADE 	 3.00 EA	0	 	 		 	 	
0530	652.33 DRUM 	 25.00 EA	0	 	 		 	 	
0540	652.34 CONE	 75.00 EA	0	 	 		 	 	

SCHEDULE OF ITEMS REVISED:

CONTRACT ID: 008188.01 PROJECT(S): HP-8188(01)X

LINE NO	•	APPROX. QUANTITY - AND UNITS	UNIT PRICE			BID AMOUNT		
			-				DOLLARS	CT
0660	822.362 POLYETHYLENE ENCASEMENT FOR DUCTILE IRON PIPE	 2 LF	2500.000	 		 	 	
0670	822.40 6 INCH COUPLING 	 EA	1.000	 		 	 	
0680	822.41 8 " COUPLING 	 EA	1.000	 		 	 	
0690	822.42 1 " COUPLING 	 EA	2.000	 		 		
	823.30 DUCTILE IRON FITTINGS FOR WATER PIPE 	 1: LB	100.000	 		 	 	
	823.311 12 INCH GATE VALVE WITH BOX 	 EA	13.000	 		 	 	
	823.3251 8 INCH GATE VALVE WITH BOX	 EA	4.000	 		 	 	
0730	823.3253 TAPPING SLEEVE & GATE VALVE WITH BOX - 10 INCH	 EA	1.000	 		 	 	
	823.33 6 INCH GATE VALVE WITH BOX 	 EA	11.000	 		 	 	
0750	824.30 FIRE HYDRANT 	 EA	9.000	 		 	 	
	824.31 REMOVE FIRE HYDRANT	 EA	1.000	 		 	 	