

**ADDENDUM NO. 1 TO
PLANS AND SPECIFICATIONS
PUBLIC BOAT LAUNCH, BACK RIVER
WESTPORT ISLAND, MAINE**

FEBRUARY 23, 2011

The following changes and clarifications have been made to the Specifications:

1. Item 3.2 Pier, Work Included, add:

All railings shall be attached to uprights with #10 x 3" SS deck screws.

2. Item A3.2, 10' X 20' Wooden Float, Work Included, fourth paragraph shall read:

Decking and skirt boards shall be southern yellow pine, grade 1; all other wood shall be southern yellow pine, grade 2 or better. Lumber shall be pressure treated ACQ - 0.6 lbs./cu.ft. for framing and 0.25 lbs./cu. ft. for decking. Float decking shall be installed "heartwood-down."

3. The Contractor shall be responsible for any damage to the boat launch, paved surfaces, and landscaping caused by equipment, materials, storage, and handling, at no cost to the Owner.

**PINE TREE
ENGINEERING**