

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 005136.30

PROJECT(S): STP-5136(30)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.23 REMOVING SINGLE TREE TOP ONLY	1.000 EA				
0020	201.24 REMOVING STUMP	1.000 EA				
0030	202.15 REMOVING MANHOLE OR CATCH BASIN	2.000 EA				
0040	202.202 REMOVING PAVEMENT SURFACE	4850.000 SY				
0050	203.20 COMMON EXCAVATION	2075.000 CY				
0060	203.21 ROCK EXCAVATION	100.000 CY				
0070	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	100.000 CY				
0080	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	100.000 CY				
0090	304.09 AGGREGATE BASE COURSE - CRUSHED (TYPE A)	1290.000 CY				
0100	304.09 AGGREGATE BASE COURSE - CRUSHED (TYPE B)	300.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 005136.30

PROJECT(S): STP-5136(30)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	1370.000 T				
0120	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	175.000 T				
0130	403.211 HOT MIX ASPHALT (SHIMMING)	1000.000 T				
0140	403.213 HOT MIX ASPHALT 12.5 MM BASE	530.000 T				
0150	409.15 BITUMINOUS TACK COAT - APPLIED	720.000 G				
0160	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	35.000 CY				
0170	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	700.000 LF				
0180	602.30 FLOWABLE CONCRETE FILL	10.000 CY				
0190	602.302 LIGHT WEIGHT FOAM CONCRETE FILL	LUMP	LUMP			
0200	603.159 12 INCH CULVERT PIPE OPTION III	46.000 LF				
0210	603.21 36 INCH CULVERT PIPE OPTION I - CORRUGATED METAL	25.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 005136.30

PROJECT(S): STP-5136(30)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	604.071 CATCH BASIN TYPE A1-P	9.000 EA				
0230	604.163 ABANDONING CATCH BASIN	2.000 EA				
0240	604.164 REBUILDING CATCH BASIN	2.000 EA				
0250	604.166 REBUILDING MANHOLE	2.000 EA				
0260	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	12.000 EA				
0270	604.24 CATCH BASIN TYPE F	1.000 EA				
0280	605.08 4" UNDERDRAIN OUTLET PIPE	44.000 LF				
0290	605.09 6 INCH UNDERDRAIN TYPE B	250.000 LF				
0300	605.11 12 INCH UNDERDRAIN TYPE C	1150.000 LF				
0310	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	100.000 LF				
0320	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	75.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 005136.30

PROJECT(S): STP-5136(30)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	81.000 LF				
0340	606.233 GR TP 3C - SGL RAIL, 8' POSTS INSTALL W/POST	975.000 LF				
0350	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA				
0360	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	4.000 EA				
0370	606.356 UNDERDRAIN DELINEATOR POST	1.000 EA				
0380	606.363 GUARDRAIL REMOVE AND DISPOSE	670.000 LF				
0390	606.47 SINGLE WOOD POST	1.000 EA				
0400	606.79 GUARDRAIL 350 FLARED TERMINAL	1.000 EA				
0410	608.26 CURB RAMP DETECTABLE WARNING FIELD	80.000 SF				
0420	609.11 VERTICAL CURB TYPE 1	1210.000 LF				
0430	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	120.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 005136.30

PROJECT(S): STP-5136(30)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	609.231 TERMINAL CURB TYPE I - 12.5 FT. - CIRCULAR	2.000 EA				
0450	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	8.000 EA				
0460	609.2371 TERMINAL CURB TYPE 1- 7 FT - CIRCULAR	12.000 EA				
0470	609.38 RESET CURB TYPE 1	1000.000 LF				
0480	609.40 RESET CURB TYPE 5	40.000 LF				
0490	610.08 PLAIN RIPRAP	16.000 CY				
0500	613.319 EROSION CONTROL BLANKET	100.000 SY				
0510	615.07 LOAM	310.000 CY				
0520	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	18.000 UN				
0530	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	13.000 UN				
0540	619.1201 MULCH - PLAN QUANTITY	31.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 005136.30

PROJECT(S): STP-5136(30)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	620.58 EROSION CONTROL GEOTEXTILE	12.000 SY				
0560	626.22 NON-METALLIC CONDUIT	1100.000 LF				
0570	626.31 18 INCH FOUNDATION	8.000 EA				
0580	626.331 36 INCH FOUNDATION	1.000 EA				
0590	626.35 CONTROLLER CABINET FOUNDATION	2.000 EA				
0600	626.36 REMOVE OR MODIFY CONCRETE FOUNDATION	1.000 EA				
0610	626.37 SPECIAL FOUNDATION	1.000 EA				
0620	627.18 12 " SOLID WHITE PAVEMENT MARKING	290.000 LF				
0630	627.407 REFLECTORIZED PLASTIC WHITE OR YELLOW PAVEMENT MARKING	1870.000 SF				
0640	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	7720.000 LF				
0650	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	570.000 SF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 005136.30

PROJECT(S): STP-5136(30)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT		
			DOLLARS	CTS	DOLLARS	CTS	
0660	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP				
0670	627.77 REMOVING PAVEMENT MARKINGS	50.000 SF					
0680	629.05 HAND LABOR, STRAIGHT TIME	200.000 HR					
0690	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	10.000 HR					
0700	631.11 AIR TOOL (INCLUDING OPERATOR)	10.000 HR					
0710	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR					
0720	631.132 SMALL BULLDOZER (INCLUDING OPERATOR)	10.000 HR					
0730	631.14 GRADER (INCLUDING OPERATOR)	10.000 HR					
0740	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR					
0750	631.22 FRONT END LOADER (INCLUDING OPERATOR)	10.000 HR					
0760	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR					

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 005136.30

PROJECT(S): STP-5136(30)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0770	635.14 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	1610.000 SF				
0780	639.18 FIELD OFFICE TYPE A	1.000 EA				
0790	643.71 TRAFFIC SIGNAL MODIFICATION RIVERSIDE / HOME DEPOT	LUMP	LUMP			
0800	643.71 TRAFFIC SIGNAL MODIFICATION RIVERSIDE / WARREN	LUMP	LUMP			
0810	643.83 VIDEO DETECTION SYSTEM RIVERSIDE / WARREN	LUMP	LUMP			
0820	643.86 TRAFFIC SIGNAL LOOP DETECTORS	2.000 EA				
0830	643.90 INTERCONNECT WIRE BETWEEN WARREN AVE / HOME DEPOT	LUMP	LUMP			
0840	643.90 INTERCONNECT WIRE BETWEEN WIRELESS FROM LARRABEE TO HOME DEPOT	LUMP	LUMP			
0850	643.91 MAST ARM POLE	2.000 EA				
0860	643.92 PEDESTAL POLE	8.000 EA				



SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 005136.30

PROJECT(S): STP-5136(30)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0870	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	10.000 EA				
0880	645.108 DEMOUNT POLE	10.000 EA				
0890	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	10.000 EA				
0900	645.118 REINSTALL POLE	10.000 EA				
0910	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	150.000 SF				
0920	652.33 DRUM	50.000 EA				
0930	652.34 CONE	50.000 EA				
0940	652.35 CONSTRUCTION SIGNS	540.000 SF				
0950	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	180.000 CD				
0960	652.38 FLAGGER	4000.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 005136.30

PROJECT(S): STP-5136(30)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0970	652.381 TRAFFIC OFFICER	2000.000 HR				
0980	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA				
0990	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
1000	659.10 MOBILIZATION	LUMP	LUMP			
1010	660.21 ON-THE-JOB TRAINING (BID)	1000.000 HR				
1020	824.32 REMOVE/RESET HYDRANT	1.000 EA				
	SECTION 0001 TOTAL					
	TOTAL BID					