

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 008869.00

PROJECTS

PFH-8869(00)X

PFH-8869(10)S

COUNTY : OXFORD

CONTRACT ID : 008869.00

GILEAD - BACHELDERS GRANT, HIGHWAY IMPROVEMENTS. WORK INCLUDES HIGHWAY, DRAINAGE AND GUARDRAIL IMPROVEMENTS, SLOPE STABILIZATION AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	10/31/09	\$ 0.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 008869.00

PROJECT(S): PFH-8869(00)X
PFH-8869(10)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.11 CLEARING	0.900 AC				
0020	202.203 PAVEMENT BUTT JOINTS	60.000 SY				
0030	203.20 COMMON EXCAVATION	1900.000 CY				
0040	203.24 COMMON BORROW	1050.000 CY				
0050	203.242 DIRTY BORROW	100.000 CY				
0060	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	15.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	620.000 CY				
0080	403.210 HOT MIX ASPHALT 9.5 MM HMA	250.000 T				
0090	403.211 HOT MIX ASPHALT (SHIMMING)	80.000 T				
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	190.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 008869.00

PROJECT(S): PFH-8869(00)X
PFH-8869(10)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	409.15 BITUMINOUS TACK COAT - APPLIED	165.000 G				
0120	502.248 UNDERWATER GROUT BAGS	3.500 CY				
0130	603.171 18 INCH CORRUGATED METAL PIPE	86.000 LF				
0140	605.09 6 INCH UNDERDRAIN TYPE B	625.000 LF				
0150	605.10 6 INCH UNDERDRAIN OUTLET	50.000 LF				
0160	606.151 GUARDRAIL TYPE 3AA - SINGLE RAIL	500.000 LF				
0170	606.17 GUARDRAIL TYPE 3B - SINGLE RAIL	75.000 LF				
0180	606.172 GUARDRAIL TYPE 3B - SINGLE RAIL, 8' POSTS	25.000 LF				
0190	606.201 GUARDRAIL TYPE 3AA - OVER 15 FOOT RADIUS	100.000 LF				
0200	606.22 GUARDRAIL TYPE 3B - OVER 15 FOOT RADIUS	275.000 LF				
0210	606.261 TERMINAL ENDS - SINGLE RAIL TYPE 3AA	8.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 008869.00

PROJECT(S): PFH-8869(00)X
PFH-8869(10)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	39.000 EA				
0230	606.269 TEMPORARY TERMINAL END SINGLE RAIL GALVANIZED STEEL	2.000 EA				
0240	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	5.000 EA				
0250	606.354 REMOVE & RESET FLEXIBLE GUARDRAIL MARKER	3.000 EA				
0260	606.36 GUARDRAIL REMOVED AND RESET	1350.000 LF				
0270	610.07 STONE FILL	2000.000 CY				
0280	613.319 EROSION CONTROL BLANKET	510.000 SY				
0290	615.07 LOAM	220.000 CY				
0300	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	33.000 UN				
0310	618.146 SEEDING HYDROMULCH GROWTH MEDIUM	23.000 UN				
0320	619.1201 MULCH - PLAN QUANTITY	33.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 008869.00

PROJECT(S): PFH-8869(00)X
PFH-8869(10)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	620.58 NON WOVEN GEOTEXTILE	2900.000 SY				
0340	620.604 GEOCELL CONFINEMENT SYSTEM	23000.000 SF				
0350	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	1980.000 LF				
0360	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0370	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0380	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0390	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR				
0400	652.33 DRUM	30.000 EA				
0410	652.34 CONE	70.000 EA				
0420	652.35 CONSTRUCTION SIGNS	280.000 SF				
0430	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 008869.00

PROJECT(S): PFH-8869(00)X
PFH-8869(10)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	652.38 FLAGGER	1300.000 HR				
0450	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0460	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

