

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 009184.50

PROJECTS

HP-9184(500)E

COUNTY : OXFORD

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 2

CONTRACT ID : 009184.50

HIGHWAY RECONSTRUCTION. WORK INCLUDES GRADING, DRAINAGE,
BASE, HOT MIX ASPHALT, PRECAST CONCRETE BOX CULVERTS,
GUARDRAIL, AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES	

CONTRACT	07/24/10	\$	1875.00
01		INCREMENTAL PERIOD \$	1875.00

FOLLOWING GROUPS ARE ALTERNATES :

GROUP AP1 ALTERNATE PAVEMENT 1
GROUP AP2 ALTERNATE PAVEMENT 2

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

CONTRACT ID: 009184.50

PROJECT(S): HP-9184(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 PROJECT ITEMS

0010	201.11 CLEARING	6.000 HA				
0020	201.23 REMOVING SINGLE TREE TOP ONLY	2.000 EA				
0030	201.24 REMOVING STUMP	2.000 EA				
0040	202.08 REMOVING BUILDING NO.: 1	LUMP	LUMP			
0050	202.15 REMOVING MANHOLE OR CATCH BASIN	1.000 EA				
0060	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0070	203.20 COMMON EXCAVATION	71400.000 M3				
0080	203.21 ROCK EXCAVATION	7550.000 M3				
0090	203.211 PRESPLITTING ROCK	1950.000 M				
0100	203.213 FRACTURING EXISTING SUBGRADE LEDGE	1510.000 M2				

SCHEDULE OF ITEMS

CONTRACT ID: 009184.50

PROJECT(S): HP-9184(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	203.24 COMMON BORROW	15600.000 M3				
0120	203.242 DIRTY BORROW	1700.000 M3				
0130	203.25 GRANULAR BORROW	500.000 M3				
0140	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	50.000 M3				
0150	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	45.000 M3				
0160	211.30 DITCH EXCAVATION	400.000 M				
0170	403.208 HOT MIX ASPHALT 12.5 MM, SURFACE	3520.000 MG				
0180	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	40.000 MG				
0190	403.211 HOT MIX ASPHALT (SHIM)	100.000 MG				
0200	403.213 HOT MIX ASPHALT 12.5 MM, BASE	4020.000 MG				
0210	409.15 BITUMINOUS TACK COAT APPLIED	5500.000 L				

SCHEDULE OF ITEMS

CONTRACT ID: 009184.50

PROJECT(S): HP-9184(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	504.069 CONCRETE PIPE TIES	52.000 EA				
0230	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			
0240	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			
0250	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			
0260	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0270	534.71 PRECAST CONCRETE BOX CULVERT Bog Brook	LUMP	LUMP			
0280	534.71 PRECAST CONCRETE BOX CULVERT STA 6+938.5	LUMP	LUMP			
0290	534.71 PRECAST CONCRETE BOX CULVERT STA 7+270.9	LUMP	LUMP			
0300	534.71 PRECAST CONCRETE BOX CULVERT STA 9+065.8	LUMP	LUMP			
0310	603.15 300 MM CULVERT PIPE OPTION I	4.000 M				
0320	603.16 375 MM CULVERT PIPE OPTION I	30.000 M				

SCHEDULE OF ITEMS

CONTRACT ID: 009184.50

PROJECT(S): HP-9184(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	603.17 450 MM CULVERT PIPE OPTION I	64.000 M				
0340	603.175 450 MM RCP CLASS III	245.000 M				
0350	603.19 600 MM CULVERT PIPE OPTION I	32.000 M				
0360	603.195 600 MM RCP CLASS III	71.000 M				
0370	603.41 600 MM REINFORCED CONCRETE PIPE CLASS IV	44.000 M				
0380	604.092 CATCH BASIN TYPE B1-C	1.000 EA				
0390	605.09 150 MM UNDERDRAIN TYPE B	215.000 M				
0400	605.10 150 MM UNDERDRAIN OUTLET	35.000 M				
0410	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	1950.000 M				
0420	606.232 GUARDRAIL TYPE 3C - OVER 4.5 M RADIUS	50.000 M				
0430	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA				

SCHEDULE OF ITEMS

CONTRACT ID: 009184.50

PROJECT(S): HP-9184(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	30.000 EA				
0450	606.356 UNDERDRAIN DELINEATOR POST	3.000 EA				
0460	606.79 GUARDRAIL 350 FLARED TERMINAL	13.000 EA				
0470	609.31 CURB TYPE 3	700.000 M				
0480	610.08 PLAIN RIPRAP	2050.000 M3				
0490	610.18 STONE DITCH PROTECTION	140.000 M3				
0500	613.319 EROSION CONTROL BLANKET	2400.000 M2				
0510	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	350.000 UN				
0520	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	310.000 UN				
0530	618.145 SPECIAL SEED	80.000 KG				
0540	619.1201 MULCH - PLAN QUANTITY	350.000 UN				

SCHEDULE OF ITEMS

CONTRACT ID: 009184.50

PROJECT(S): HP-9184(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	619.1401 EROSION CONTROL MIX	3050.000 M3				
0560	620.54 STABILIZATION GEOTEXTILE	1000.000 M2				
0570	620.58 EROSION CONTROL GEOTEXTILE	4500.000 M2				
0580	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	9700.000 M				
0590	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0600	629.05 HAND LABOR, STRAIGHT TIME	100.000 HR				
0610	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	50.000 HR				
0620	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	30.000 HR				
0630	631.22 FRONT END LOADER (INCLUDING OPERATOR)	20.000 HR				
0640	635.14 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	160.000 M2				
0650	652.33 DRUM	100.000 EA				

SCHEDULE OF ITEMS

CONTRACT ID: 009184.50

PROJECT(S): HP-9184(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	652.34 CONE	150.000 EA				
0670	652.35 CONSTRUCTION SIGNS	110.000 M2				
0680	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0690	652.38 FLAGGER	12000.000 HR				
0700	652.41 PORTABLE - CHANGEABLE MESSAGE SIGN	2.000 EA				
0710	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0720	659.10 MOBILIZATION	LUMP	LUMP			
0730	660.21 ON-THE-JOB TRAINING (BID)	2000.000 HR				
	SECTION 0001 TOTAL					.

SECTION 0002 ALTERNATE PAVEMENT 1
ALT GROUP AP1

0740	304.09 AGGREGATE BASE COURSE - CRUSHED	12500.000 M3				
------	--	-----------------	--	--	--	--

SCHEDULE OF ITEMS

CONTRACT ID: 009184.50

PROJECT(S): HP-9184(500)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0750	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	18650.000 M3				
0760	403.207 HOT MIX ASPHALT 19.0 MM NOMINAL MAX SIZE	5500.000 MG				
	SECTION 0002 TOTAL					.
SECTION 0003 ALTERNATE PAVEMENT 2 ALT GROUP AP2						
0770	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	20350.000 M3				
0780	304.1311 DENSE-GRADED CRUSHED AGGREGATE BASE	11000.000 M3				
0790	403.207 HOT MIX ASPHALT 19.0 MM NOMINAL MAX SIZE	4850.000 MG				
	SECTION 0003 TOTAL					
	TOTAL BID					

