

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 009184.60

PROJECTS

-----  
NH-9184(600)E

COUNTY : OXFORD

CONTRACT ID : 009184.60

HIGHWAY RECONSTRUCTION

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	11/18/10	\$ 0.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009184.60

PROJECT(S): NH-9184(600)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.11 CLEARING	5.000 HA				
0020	201.23 REMOVING SINGLE TREE TOP ONLY	3.000 EA				
0030	202.08 REMOVING BUILDING NO.:	LUMP	LUMP			
0040	202.2006 RELOCATION OF HOUSE	LUMP	LUMP			
0050	203.20 COMMON EXCAVATION	80000.000 M3				
0060	203.21 ROCK EXCAVATION	7250.000 M3				
0070	203.212 SPECIAL PERIMETER CONTROL BLASTING	1850.000 M				
0080	203.213 FRACTURING EXISTING SUBGRADE LEDGE	1900.000 M2				
0090	203.214 EXPLORATORY DRILLING	25.000 M				
0100	203.242 DIRTY BORROW	1350.000 M3				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009184.60

PROJECT(S): NH-9184(600)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	203.25 GRANULAR BORROW	100.000 M3				
0120	203.35 CRUSHED STONE FILL	10.000 M3				
0130	203.37 REINFORCED BACKFILL	6600.000 M3				
0140	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	25.000 M3				
0150	403.208 HOT MIX ASPHALT 12.5 MM, SURFACE	3600.000 MG				
0160	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	40.000 MG				
0170	403.211 HOT MIX ASPHALT (SHIM)	170.000 MG				
0180	403.213 HOT MIX ASPHALT 12.5 MM, BASE	4300.000 MG				
0190	409.15 BITUMINOUS TACK COAT APPLIED	5800.000 L				
0200	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	110.000 M3				
0210	504.07 CONCRETE PIPE TIES	16.000 GP				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009184.60

PROJECT(S): NH-9184(600)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0230	601.221 GABIONS, PVC COATED AND HAND FILLED	M3 50.000				
0240	603.159 300 MM CULVERT PIPE OPTION III	M 11.000				
0250	603.16 375 MM CULVERT PIPE OPTION I	M 11.000				
0260	603.175 450 MM RCP CLASS III	M 39.000				
0270	603.195 600 MM RCP CLASS III	M 47.000				
0280	603.20 750 MM CULVERT PIPE OPTION I	M 20.000				
0290	603.205 750 MM REINFORCED CONCRETE PIPE CLASS III	M 150.000				
0300	603.215 900 MM REINFORCED CONCRETE PIPE CLASS III	M 66.000				
0310	603.2151 900 MM RCP CLASS IV	M 40.000				
0320	604.092 CATCH BASIN TYPE B1-C	EA 7.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009184.60

PROJECT(S): NH-9184(600)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	604.244 CATCH BASIN TYPE F4	1.000 EA				
0340	605.09 150 MM UNDERDRAIN TYPE B	180.000 M				
0350	605.11 300 MM UNDERDRAIN TYPE C	470.000 M				
0360	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0370	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	1800.000 M				
0380	606.231 GUARDRAIL TYPE 3C - 4.5 M RADIUS AND LESS	16.000 M				
0390	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	4.000 EA				
0400	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	30.000 EA				
0410	606.363 GUARDRAIL REMOVE AND DISPOSE	120.000 M				
0420	606.551 GUARDRAIL TYPE 3-SINGLE RAIL WITH RUB RAIL	120.000 M				
0430	606.79 GUARDRAIL 350 FLARED TERMINAL	11.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009184.60

PROJECT(S): NH-9184(600)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	609.31 CURB TYPE 3	570.000 M				
0450	610.08 PLAIN RIPRAP	3650.000 M3				
0460	610.16 HEAVY RIPRAP	4300.000 M3				
0470	610.18 STONE DITCH PROTECTION	320.000 M3				
0480	613.319 EROSION CONTROL BLANKET	7500.000 M2				
0490	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	250.000 UN				
0500	618.146 SEEDING HYDROMULCH GROWTH MEDIUM	30.000 UN				
0510	619.1201 MULCH - PLAN QUANTITY	250.000 UN				
0520	619.1401 EROSION CONTROL MIX	3450.000 M3				
0530	620.541 REINFORCEMENT GEOTEXTILE	7000.000 M2				
0540	620.542 COMPACTION AID GEOTEXTILE	3000.000 M2				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009184.60

PROJECT(S): NH-9184(600)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	620.59 EROSION CONTROL GEOTEXTILE (SEWN SEAMS)	3100.000 M2				
0560	620.604 GEOCELL CONFINEMENT SYSTEM	910.000 M2				
0570	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0580	627.77 REMOVING PAVEMENT MARKINGS	330.000 M2				
0590	629.05 HAND LABOR, STRAIGHT TIME	100.000 HR				
0600	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	24.000 HR				
0610	631.11 AIR TOOL (INCLUDING OPERATOR)	24.000 HR				
0620	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	24.000 HR				
0630	631.13 BULLDOZER (INCLUDING OPERATOR)	24.000 HR				
0640	631.14 GRADER (INCLUDING OPERATOR)	24.000 HR				
0650	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	24.000 HR				



SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009184.60

PROJECT(S): NH-9184(600)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	24.000 HR				
0670	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	8.000 HR				
0680	631.22 FRONT END LOADER (INCLUDING OPERATOR)	24.000 HR				
0690	631.221 SMALL FRONT-END LOADER (INCLUDING OPERATOR)	24.000 HR				
0700	639.18 FIELD OFFICE TYPE A	1.000 EA				
0710	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			
0720	652.31 TYPE I BARRICADE	10.000 EA				
0730	652.311 TYPE II BARRICADE	10.000 EA				
0740	652.33 DRUM	100.000 EA				
0750	652.34 CONE	200.000 EA				
0760	652.35 CONSTRUCTION SIGNS	50.000 M2				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009184.60

PROJECT(S): NH-9184(600)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0770	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	450.000 CD				
0780	652.38 FLAGGER	12000.000 HR				
0790	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA				
0800	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0810	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	7.000 M2				
0820	659.10 MOBILIZATION	LUMP	LUMP			
0830	660.21 ON-THE-JOB TRAINING (BID)	2000.000 HR				
SECTION 0001 TOTAL						.

SECTION 0002 ALTERNATE 1

0840	304.09 AGGREGATE BASE COURSE - CRUSHED	13300.000 M3				
0850	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	19700.000 M3				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 009184.60

PROJECT(S): NH-9184(600)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0860	403.207 HOT MIX ASPHALT 19.0 MM NOMINAL MAX SIZE	5750.000 MG				
SECTION 0002 TOTAL						
SECTION 0003 ALTERNATE 2						
0870	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	21100.000 M3				
0880	304.1311 DENSE-GRADED CRUSHED AGGREGATE BASE	11700.000 M3				
0890	403.207 HOT MIX ASPHALT 19.0 MM NOMINAL MAX SIZE	5100.000 MG				
SECTION 0003 TOTAL						
TOTAL BID						

