

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 010014.10

PROJECTS

NH-1001(410)E

COUNTY : ANDROSCOGGIN

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 2

CONTRACT ID : 010014.10

POLAND, HIGHWAY RECONSTRUCTION. WORK INCLUDES GRADING,
DRAINAGE, BASE, HOT MIX ASPHALT, CURB, PLANTING TREES AND
SHRUBS, AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	08/14/09	\$ 900.00
01	11/01/08	\$ 1000.00
02	INCREMENTAL PERIOD	\$ 900.00

FOLLOWING GROUPS ARE ALTERNATES :

- GROUP AP1 PAVEMENT ALTERNATE 1
- GROUP AP2 PAVEMENT ALTERNATE 2

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

CONTRACT ID: 010014.10

PROJECT(S): NH-1001(410)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 PROJECT ITEMS						

0010	201.11 CLEARING	1.200				
		HA				

0020	201.23 REMOVING SINGLE TREE TOP ONLY	15.000				
		EA				

0030	201.24 REMOVING STUMP	16.000				
		EA				

0040	202.08 REMOVING BUILDING NO.: 1		LUMP	LUMP		

0050	202.08 REMOVING BUILDING NO.: 2		LUMP	LUMP		

0060	202.08 REMOVING BUILDING NO.: 3 (FERGUSON HO.)		LUMP	LUMP		

0070	202.2005 RELOCATION OF BARN		LUMP	LUMP		

0080	202.203 PAVEMENT BUTT JOINTS	300.000				
		M2				

0090	203.20 COMMON EXCAVATION	16500.000				
		M3				

0100	203.2312 HEALTH AND SAFETY PLAN		LUMP	LUMP		

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010014.10

PROJECT(S): NH-1001(410)E

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	203.2333 DISPOSAL OF SPECIAL EXCAVATION	50.000 MG				
0120	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	50.000 M3				
0130	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	50.000 M3				
0140	409.15 BITUMINOUS TACK COAT APPLIED	2475.000 L				
0150	502.341 STRUCTURAL CONCRETE ROADWAY MEDIAN	128.000 M3				
0160	603.159 300 MM CULVERT PIPE OPTION III	28.000 M				
0170	603.16 375 MM CULVERT PIPE OPTION I	53.000 M				
0180	603.169 375 MM CULVERT PIPE OPTION III	149.000 M				
0190	603.17 450 MM CULVERT PIPE OPTION I	8.000 M				
0200	603.175 450 MM RCP CLASS III	43.000 M				
0210	603.179 450 MM CULVERT PIPE OPTION III	18.000 M				

SCHEDULE OF ITEMS

CONTRACT ID: 010014.10

PROJECT(S): NH-1001(410)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	603.189 525 MM CULVERT PIPE OPTION III	3.000 M				
0230	603.195 600 MM RCP CLASS III	22.000 M				
0240	604.09 CATCH BASIN TYPE B1	2.000 EA				
0250	604.092 CATCH BASIN TYPE B1-C	20.000 EA				
0260	604.11 CATCH BASIN TYPE C1	1.000 EA				
0270	604.244 CATCH BASIN TYPE F4	1.000 EA				
0280	604.246 CATCH BASIN TYPE F5	1.000 EA				
0290	605.09 150 MM UNDERDRAIN TYPE B	391.000 M				
0300	605.10 150 MM UNDERDRAIN OUTLET	5.000 M				
0310	605.11 300 MM UNDERDRAIN TYPE C	162.000 M				
0320	605.12 375 MM UNDERDRAIN TYPE C	290.000 M				

SCHEDULE OF ITEMS

CONTRACT ID: 010014.10

PROJECT(S): NH-1001(410)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	605.13 450 MM UNDERDRAIN TYPE C	41.000 M				
0340	606.47 SINGLE WOOD POST	10.000 EA				
0350	609.31 CURB TYPE 3	465.000 M				
0360	609.34 CURB TYPE 5	230.000 M				
0370	609.35 CURB TYPE 5 - CIRCULAR	18.000 M				
0380	610.08 PLAIN RIPRAP	67.000 M3				
0390	613.319 EROSION CONTROL BLANKET	4875.000 M2				
0400	615.07 LOAM	1150.000 M3				
0410	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	25.000 UN				
0420	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	103.000 UN				
0430	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	78.000 UN				

SCHEDULE OF ITEMS

CONTRACT ID: 010014.10

PROJECT(S): NH-1001(410)E

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	619.1201 MULCH - PLAN QUANTITY	205.000 UN				
0450	620.58 EROSION CONTROL GEOTEXTILE	170.000 M2				
0460	621.031 EVERGREEN TREES (1200 MM - 1500 MM) GROUP A	6.000 EA				
0470	621.032 EVERGREEN TREES (1200 MM - 1500 MM) GROUP B	12.000 EA				
0480	621.037 EVERGREEN TREES (1500 MM - 1800 MM) GROUP A	12.000 EA				
0490	621.195 MEDIUM DECIDUOUS TREE (45 MM - 50 MM CALIPER) GROUP A	12.000 EA				
0500	621.397 DWARF EVERGREENS (450 MM - 600 MM) GROUP C	6.000 EA				
0510	621.54 DECIDUOUS SHRUBS (450 MM - 600 MM) GROUP A	36.000 EA				
0520	621.552 DECIDUOUS SHRUBS (900 MM - 1200 MM) GROUP A	12.000 EA				
0530	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	5400.000 M				
0540	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	83.000 M2				

SCHEDULE OF ITEMS

CONTRACT ID: 010014.10

PROJECT(S): NH-1001(410)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0560	629.05 HAND LABOR, STRAIGHT TIME	100.000 HR				
0570	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	30.000 HR				
0580	631.13 BULLDOZER (INCLUDING OPERATOR)	30.000 HR				
0590	631.14 GRADER (INCLUDING OPERATOR)	30.000 HR				
0600	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	30.000 HR				
0610	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	30.000 HR				
0620	631.22 FRONT END LOADER (INCLUDING OPERATOR)	30.000 HR				
0630	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	30.000 HR				
0640	639.18 FIELD OFFICE TYPE A	1.000 EA				
0650	652.31 TYPE I BARRICADE	10.000 EA				

SCHEDULE OF ITEMS

CONTRACT ID: 010014.10

PROJECT(S): NH-1001(410)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	652.311 TYPE II BARRICADE	10.000 EA				
0670	652.33 DRUM	60.000 EA				
0680	652.34 CONE	60.000 EA				
0690	652.35 CONSTRUCTION SIGNS	85.000 M2				
0700	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0710	652.38 FLAGGER	6000.000 HR				
0720	652.41 PORTABLE - CHANGEABLE MESSAGE SIGN	4.000 EA				
0730	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0740	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	440.000 M2				
0750	659.10 MOBILIZATION	LUMP	LUMP			
0760	660.21 ON-THE-JOB TRAINING (BID)	1000.000 HR				

SCHEDULE OF ITEMS

CONTRACT ID: 010014.10

PROJECT(S): NH-1001(410)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0770	832.071 CONTRACTOR ALLOWANCE (BARN REHABILITATION)	LUMP	LUMP			
	SECTION 0001 TOTAL					.

SECTION 0002 PAVEMENT ALTERNATE 1
ALT GROUP AP1

0780	304.09 AGGREGATE BASE COURSE - CRUSHED	M3	5150.000			
0790	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	M3	8075.000			
0800	403.207 HOT MIX ASPHALT 19.0 MM NOMINAL MAX SIZE	MG	2700.000			
0810	403.208 HOT MIX ASPHALT 12.5 MM, SURFACE	MG	1850.000			
0820	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	MG	200.000			
0830	403.211 HOT MIX ASPHALT (SHIM)	MG	100.000			
0840	403.213 HOT MIX ASPHALT 12.5 MM, BASE	MG	2050.000			
	SECTION 0002 TOTAL					.

SECTION 0003 PAVEMENT ALTERNATE 2
ALT GROUP AP2

SCHEDULE OF ITEMS

CONTRACT ID: 010014.10

PROJECT(S): NH-1001(410)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0850	304.09 AGGREGATE BASE COURSE - CRUSHED	10600.000 M3				
0860	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	3450.000 M3				
0870	403.207 HOT MIX ASPHALT 19.0 MM NOMINAL MAX SIZE	1975.000 MG				
0880	403.208 HOT MIX ASPHALT 12.5 MM, SURFACE	1850.000 MG				
0890	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	200.000 MG				
0900	403.211 HOT MIX ASPHALT (SHIM)	100.000 MG				
0910	403.213 HOT MIX ASPHALT 12.5 MM, BASE	2050.000 MG				
	SECTION 0003 TOTAL					
	TOTAL BID					

