

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010017.00

PROJECT(S): STP-1001(700)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 HIGHWAY ITEMS						

0010	201.11 CLEARING	8.000 HA				

0020	201.23 REMOVING SINGLE TREE TOP ONLY	270.000 EA				

0030	201.24 REMOVING STUMP	300.000 EA				

0040	202.15 REMOVING MANHOLE OR CATCH BASIN	10.000 EA				

0050	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			

0060	202.202 REMOVING PAVEMENT SURFACE	360.000 M2				

0070	203.20 COMMON EXCAVATION	118552.000 M3				

0080	203.21 ROCK EXCAVATION	4600.000 M3				

0090	203.213 FRACTURING EXISTING SUBGRADE LEDGE	5000.000 M2				

0100	203.214 EXPLORATORY DRILLING	25.000 M				

SCHEDULE OF ITEMS

CONTRACT ID: 010017.00

PROJECT(S): STP-1001(700)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	203.2318 DISPOSAL OF SPECIAL WASTE	20.000 MG				
0120	203.242 DIRTY BORROW	6450.000 M3				
0130	203.25 GRANULAR BORROW	380.000 M3				
0140	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	200.000 M3				
0150	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	120.000 M3				
0160	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	10.000 M3				
0170	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	98325.000 M3				
0180	403.207 HOT MIX ASPHALT 19.0 MM NOMINAL MAX SIZE	13825.000 MG				
0190	403.208 HOT MIX ASPHALT 12.5 MM, SURFACE	11675.000 MG				
0200	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	1475.000 MG				
0210	403.213 HOT MIX ASPHALT 12.5 MM, BASE	11775.000 MG				

SCHEDULE OF ITEMS

CONTRACT ID: 010017.00

PROJECT(S): STP-1001(700)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	409.15 BITUMINOUS TACK COAT APPLIED	L 16450.000				
0230	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0240	502.56 CONCRETE FILL	M3 92.000				
0250	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	KG 6000.000				
0260	503.13 REINFORCING STEEL, PLACING	KG 6000.000				
0270	509.20 ALUMINUM ALLOY STRUCTURAL PLATE ARCH	LUMP	LUMP			
0280	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			
0290	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			
0300	514.06 CURING BOX FOR CONCRETE CYLINDERS	EA 1.000				
0310	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0320	603.16 375 MM CULVERT PIPE OPTION I	M 1464.000				

SCHEDULE OF ITEMS

CONTRACT ID: 010017.00

PROJECT(S): STP-1001(700)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	603.169 375 MM CULVERT PIPE OPTION III	M 140.000				
0340	603.17 450 MM CULVERT PIPE OPTION I	M 125.000				
0350	603.179 450 MM CULVERT PIPE OPTION III	M 341.000				
0360	603.199 600 MM CULVERT PIPE OPTION III	M 346.000				
0370	603.209 750 MM CULVERT PIPE OPTION III	M 68.000				
0380	603.219 900 MM CULVERT PIPE OPTION III	M 22.000				
0390	603.229 1050 MM CULVERT PIPE OPTION III	M 89.000				
0400	603.239 1200 MM CULVERT PIPE OPTION III	M 28.000				
0410	604.092 CATCH BASIN TYPE B1-C	EA 40.000				
0420	604.246 CATCH BASIN TYPE F5	EA 3.000				
0430	605.09 150 MM UNDERDRAIN TYPE B	M 3237.000				

SCHEDULE OF ITEMS

CONTRACT ID: 010017.00

PROJECT(S): STP-1001(700)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	605.10 150 MM UNDERDRAIN OUTLET	M 224.000				
0450	605.11 300 MM UNDERDRAIN TYPE C	M 653.000				
0460	605.12 375 MM UNDERDRAIN TYPE C	M 1117.000				
0470	605.13 450 MM UNDERDRAIN TYPE C	M 376.000				
0480	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	M 177.170				
0490	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	EA 8.000				
0500	606.356 UNDERDRAIN DELINEATOR POST	EA 100.000				
0510	606.366 GUARDRAIL, REMOVE & RESET TYPE 3C	M 40.000				
0520	606.47 SINGLE WOOD POST	EA 150.000				
0530	606.79 GUARDRAIL 350 FLARED TERMINAL	EA 4.000				
0540	609.31 CURB TYPE 3	M 4475.000				

MAINE DEPARTMENT OF TRANSPORTATION
SCHEDULE OF ITEMS

PAGE: 6
DATE: 090707
REVISED:

CONTRACT ID: 010017.00

PROJECT(S): STP-1001(700)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	609.34 CURB TYPE 5	24.000 M				
0560	609.35 CURB TYPE 5 - CIRCULAR	8.000 M				
0570	610.08 PLAIN RIPRAP	730.000 M3				
0580	610.18 STONE DITCH PROTECTION	2275.000 M3				
0590	613.319 EROSION CONTROL BLANKET	19128.000 M2				
0600	615.07 LOAM	2550.000 M3				
0610	618.13 SEEDING METHOD NUMBER 1	255.000 UN				
0620	618.14 SEEDING METHOD NUMBER 2	910.000 UN				
0630	618.141 SEEDING METHOD NUMBER 3	376.000 UN				
0640	619.12 MULCH	1541.000 UN				
0650	619.13 BARK MULCH	10.000 UN				

SCHEDULE OF ITEMS

CONTRACT ID: 010017.00

PROJECT(S): STP-1001(700)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	620.54 STABILIZATION GEOTEXTILE	500.000 M2				
0670	620.58 NON WOVEN GEOTEXTILE	102.000 M2				
0680	621.02 EVERGREEN TREES (600 MM - 900 MM) GROUP B	20.000 EA				
0690	621.021 EVERGREEN TREES (600 MM - 900 MM) GROUP C	20.000 EA				
0700	621.025 EVERGREEN TREES (900 MM - 1200 MM) GROUP A	25.000 EA				
0710	621.031 EVERGREEN TREES (1200 MM - 1500 MM) GROUP A	65.000 EA				
0720	621.037 EVERGREEN TREES (1500 MM - 1800 MM) GROUP A	46.000 EA				
0730	621.044 EVERGREEN TREES (1800 MM - 2400 MM) GROUP B	10.000 EA				
0740	621.045 EVERGREEN TREES (1800 MM - 2400 MM) GROUP C	5.000 EA				
0750	621.048 EVERGREEN TREES (2400MM - 2700MM) GROUP C	3.000 EA				
0760	621.121 SMALL DECIDUOUS TREES (1500 MM - 1800 MM) GROUP B	15.000 EA				

SCHEDULE OF ITEMS

CONTRACT ID: 010017.00

PROJECT(S): STP-1001(700)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0770	621.126 SMALL DECIDUOUS TREES (1800 MM - 2400 MM) GROUP A	15.000 EA				
0780	621.18 MEDIUM DECIDUOUS TREES (1800 MM - 2400 MM) GROUP C	9.000 EA				
0790	621.202 MEDIUM DECIDUOUS TREE (50 MM - 65 MM CALIPER) GROUP B	22.000 EA				
0800	621.245 LARGE DECIDUOUS TREES (600 MM - 900 MM) GROUP A	20.000 EA				
0810	621.255 LARGE DECIDUOUS TREES (2400 MM - 3000 MM) GROUP A	23.000 EA				
0820	621.257 LARGE DECIDUOUS TREES (2400 MM - 3000 MM) GROUP C	1.000 EA				
0830	621.273 LARGE DECIDUOUS TREE (50 MM - 65 MM CALIPER) GROUP A	58.000 EA				
0840	621.285 LARGE DECIDUOUS TREE (75 MM - 90 MM CALIPER) GROUP A	6.000 EA				
0850	621.396 DWARF EVERGREENS (450 MM - 600 MM) GROUP B	12.000 EA				
0860	621.402 DWARF EVERGREENS (600 MM - 750 MM) GROUP B	12.000 EA				
0870	621.487 BROADLEAF EVERGREENS (450 MM - 600 MM) GROUP B	10.000 EA				

SCHEDULE OF ITEMS

CONTRACT ID: 010017.00

PROJECT(S): STP-1001(700)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0880	621.498 BROADLEAF EVERGREENS (750 MM - 900 MM) GROUP A	3.000 EA				
0890	621.511 DECIDUOUS SHRUBS (450MM - 600MM) GROUP A	90.000 EA				
0900	621.546 DECIDUOUS SHRUBS (600 MM - 900 MM) GROUP A	16.000 EA				
0910	621.552 DECIDUOUS SHRUBS (900 MM - 1200 MM) GROUP A	44.000 EA				
0920	621.558 DECIDUOUS SHRUBS (1200 MM - 1500 MM) GROUP A	6.000 EA				
0930	621.711 HERBACEOUS PERENNIALS GROUP B	30.000 EA				
0940	621.80 ESTABLISHMENT PERIOD	LUMP	LUMP			
0950	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	34200.000 M				
0960	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	55.000 M2				
0970	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0980	629.05 HAND LABOR, STRAIGHT TIME	100.000 HR				

SCHEDULE OF ITEMS

CONTRACT ID: 010017.00

PROJECT(S): STP-1001(700)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0990	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	100.000 HR				
1000	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR				
1010	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	20.000 HR				
1020	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	20.000 HR				
1030	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR				
1040	639.18 FIELD OFFICE TYPE A	1.000 EA				
1050	643.60 FLASHING BEACON AT: CROWLEY RD. & BOWDOINHAM RD.	LUMP	LUMP			
1060	643.60 FLASHING BEACON AT: UPLAND RD. & GOULD RD.	LUMP	LUMP			
1070	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			
1080	652.31 TYPE I BARRICADE	20.000 EA				
1090	652.312 TYPE III BARRICADE	5.000 EA				

MAINE DEPARTMENT OF TRANSPORTATION
SCHEDULE OF ITEMS

PAGE: 11
DATE: 090707
REVISED:

CONTRACT ID: 010017.00

PROJECT(S): STP-1001(700)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1100	652.33 DRUM	100.000 EA				
1110	652.34 CONE	150.000 EA				
1120	652.35 CONSTRUCTION SIGNS	120.000 M2				
1130	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	500.000 CD				
1140	652.38 FLAGGER	21000.000 HR				
1150	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
1160	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	24.000 M2				
1170	659.10 MOBILIZATION	LUMP	LUMP			
1180	660.21 ON-THE-JOB TRAINING (BID)	3000.000 HR				
1190	822.3732 300MM DUCTILE IRON PIPE SLEEVE - INSTALL ONLY	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					