

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010018.00

PROJECT(S): NH-1001(800)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.11 CLEARING	0.100 HA				
0020	201.23 REMOVING SINGLE TREE TOP ONLY	10.000 EA				
0030	201.24 REMOVING STUMP	10.000 EA				
0040	202.08 REMOVING BUILDING NO.: 1	LUMP	LUMP			
0050	202.08 REMOVING BUILDING NO.: 2	LUMP	LUMP			
0060	202.11 REMOVING PORTLAND CEMENT CONCRETE PAVEMENT	50.000 M2				
0070	202.15 REMOVING MANHOLE OR CATCH BASIN	35.000 EA				
0080	202.191 REMOVING EXISTING PIPE	LUMP	LUMP			
0090	203.20 COMMON EXCAVATION	23710.000 M3				
0100	203.21 ROCK EXCAVATION	500.000 M3				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010018.00

PROJECT(S): NH-1001(800)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	203.213 SHATTER SOLID ROCK SUBGRADE	M2 1000.000				
0120	203.214 EXPLORATORY DRILLING	M 100.000				
0130	203.2312 HEALTH AND SAFETY PLAN	LUMP	LUMP			
0140	203.2333 DISPOSAL OF SPECIAL EXCAVATION	MG 1460.000				
0150	203.26 GRAVEL BORROW	M3 100.000				
0160	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	M3 430.000				
0170	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	M3 400.000				
0180	304.09 AGGREGATE BASE COURSE - CRUSHED	M3 4960.000				
0190	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	M3 12030.000				
0200	403.207 HOT MIX ASPHALT 19.0 MM NOMINAL MAX SIZE	MG 8370.000				
0210	403.208 HOT MIX ASPHALT 12.5 MM, SURFACE	MG 3080.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010018.00

PROJECT(S): NH-1001(800)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	1750.000 MG				
0230	409.15 BITUMINOUS TACK COAT APPLIED	3800.000 L				
0240	518.60 REPAIR OF VERTICAL SURFACES < 200 MM	40.000 M2				
0250	525.326 FIELD STONE RETAINING WALL	25.000 M2				
0260	603.155 300 MM RCP CLASS III	294.000 M				
0270	603.165 375 MM RCP CLASS III	107.000 M				
0280	603.175 450 MM RCP CLASS III	236.000 M				
0290	603.195 600 MM RCP CLASS III	115.000 M				
0300	603.205 750 MM REINFORCED CONCRETE PIPE CLASS III	147.000 M				
0310	603.215 900 MM REINFORCED CONCRETE PIPE CLASS III	82.000 M				
0320	604.072 CATCH BASIN TYPE A1-C	61.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010018.00

PROJECT(S): NH-1001(800)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	604.077 1800MM CATCH BASIN TYPE A1-C	5.000 EA				
0340	604.092 CATCH BASIN TYPE B1-C	21.000 EA				
0350	604.096 1500 MM CATCH BASIN TYPE B1-C	4.000 EA				
0360	604.15 MANHOLE	10.000 EA				
0370	604.153 1500 MM MANHOLE	2.000 EA				
0380	604.154 1800 MM MANHOLE	1.000 EA				
0390	604.16 ALTERING CATCH BASIN TO MANHOLES	1.000 EA				
0400	604.246 CATCH BASIN TYPE F5	2.000 EA				
0410	604.248 CATCH BASIN TYPE F6	1.000 EA				
0420	605.09 150 MM UNDERDRAIN TYPE B	941.000 M				
0430	605.11 300 MM UNDERDRAIN TYPE C	876.000 M				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010018.00

PROJECT(S): NH-1001(800)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	605.12 375 MM UNDERDRAIN TYPE C	M 270.000				
0450	605.13 450 MM UNDERDRAIN TYPE C	M 250.000				
0460	605.15 600 MM UNDERDRAIN TYPE C	M 228.000				
0470	605.17 750 MM UNDERDRAIN TYPE C	M 85.000				
0480	605.18 900 MM UNDERDRAIN TYPE C	M 40.000				
0490	606.24 GUARDRAIL TYPE 3D - SINGLE RAIL	M 10.000				
0500	606.78 LOW VOLUME GUARDRAIL END - TYPE 3	EA 1.000				
0510	607.163 CHAIN LINK FENCE - 1.2 METER P.V.C. COATED	M 220.000				
0520	608.08 REINFORCED CONCRETE SIDEWALK	M2 120.000				
0530	608.26 CURB RAMP DETECTABLE WARNING FIELD	M2 30.000				
0540	609.11 VERTICAL CURB TYPE 1	M 1984.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010018.00

PROJECT(S): NH-1001(800)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	609.113 VERTICAL CURB TYPE 1 - 300 MM REVEAL	50.000 M				
0560	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	210.000 M				
0570	609.234 TERMINAL CURB TYPE 1 - 1.2 METER	43.000 EA				
0580	609.2341 TERMINAL CURB TYPE 1 -1.2 M CIRCULAR	13.000 EA				
0590	609.237 TERMINAL CURB TYPE 1 - 2.1 METER	197.000 EA				
0600	609.2371 TERMINAL CURB TYPE 1- 2.1M - CIRCULAR	46.000 EA				
0610	609.31 CURB TYPE 3	700.000 M				
0620	610.08 PLAIN RIPRAP	40.000 M3				
0630	615.07 LOAM	820.000 M3				
0640	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	82.000 UN				
0650	619.1201 MULCH - PLAN QUANTITY	82.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010018.00

PROJECT(S): NH-1001(800)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	620.54 STABILIZATION GEOTEXTILE	1800.000 M2				
0670	621.126 SMALL DECIDUOUS TREES (1800 MM - 2400 MM) GROUP A	5.000 EA				
0680	621.138 SMALL DECIDUOUS TREE (40 MM - 50 MM CALIPER) GROUP A	5.000 EA				
0690	621.268 LARGE DECIDUOUS TREE (45 MM - 50 MM CALIPER) GROUP B	5.000 EA				
0700	621.401 DWARF EVERGREENS (600 MM - 750 MM) GROUP A	36.000 EA				
0710	621.523 BAYBERRY (375 MM - 450 MM)	36.000 EA				
0720	621.54 DECIDUOUS SHRUBS (450 MM - 600 MM) GROUP A	31.000 EA				
0730	621.80 ESTABLISHMENT PERIOD	LUMP	LUMP			
0740	626.11 PRECAST CONCRETE JUNCTION BOX: _____	5.000 EA				
0750	626.22 NON-METALLIC CONDUIT	190.000 M				
0760	626.31 450 MM FOUNDATION	5.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010018.00

PROJECT(S): NH-1001(800)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0770	626.331 900 MM FOUNDATION	2.000 EA				
0780	626.35 CONTROLLER CABINET FOUNDATION	1.000 EA				
0790	627.733 100 MM WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	6860.000 M				
0800	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	500.000 M2				
0810	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0820	629.05 HAND LABOR, STRAIGHT TIME	100.000 HR				
0830	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	50.000 HR				
0840	631.11 AIR TOOL (INCLUDING OPERATOR)	50.000 HR				
0850	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	50.000 HR				
0860	631.14 GRADER (INCLUDING OPERATOR)	50.000 HR				
0870	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	50.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010018.00

PROJECT(S): NH-1001(800)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0880	631.22 FRONT END LOADER (INCLUDING OPERATOR)	50.000 HR				
0890	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR				
0900	635.32 WET CAST SMALL LANDSCAPE BLOCK WALL	420.000 M2				
0910	636.29 RETAINING WALL STEPS	65.000 EA				
0920	639.18 FIELD OFFICE TYPE A	1.000 EA				
0930	642.17 CAST-IN-PLACE CONCRETE STEPS	10.000 M3				
0940	643.80 TRAFFIC SIGNALS AT MAIN / BRIDGE	LUMP	LUMP			
0950	643.83 VIDEO DETECTION SYSTEM	LUMP	LUMP			
0960	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	25.000 M2				
0970	645.306 FLEXIBLE REFLECTORIZED DELINEATOR	1.000 EA				
0980	652.33 DRUM	200.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010018.00

PROJECT(S): NH-1001(800)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0990	652.34 CONE	200.000 EA				
1000	652.35 CONSTRUCTION SIGNS	100.000 M2				
1010	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	400.000 CD				
1020	652.38 FLAGGER	15000.000 HR				
1030	652.381 TRAFFIC OFFICER	50.000 HR				
1040	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	3.000 EA				
1050	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
1060	659.10 MOBILIZATION	LUMP	LUMP			
1070	660.21 ON-THE-JOB TRAINING (BID)	2000.000 HR				
1080	801.17 200 MM PVC SANITARY SEWER (SDR-35)	465.000 M				
1090	801.18 300 MM PVC SANITARY SEWER (SDR-35)	795.000 M				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010018.00

PROJECT(S): NH-1001(800)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1100	801.19 375 MM PVC SANITARY SEWER (SDR-35)	35.000 M				
1110	803.01 TEST PITS	9.000 EA				
1120	803.135 150MM SERVICE LATERAL	1050.000 M				
1130	803.17 REMOVE / ABANDON MANHOLE	27.000 EA				
1140	803.173 SEWER MANHOLE - 1.2M DIAMETER	28.000 EA				
1150	812.162 ADJUST SEWER MANHOLE TO GRADE	19.000 EA				
1160	822.33 150 MM CLASS 52 DI PIPE	180.000 M				
1170	822.331 150 MM NITRILE GASKET	2.000 EA				
1180	822.34 200 MM CLASS 52 DI PIPE	905.000 M				
1190	822.340 200 MM NITRILE GASKET	6.000 EA				
1200	822.36 300 MM CLASS 52 DI PIPE	1010.000 M				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010018.00

PROJECT(S): NH-1001(800)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1210	822.360 300 MM NITRILE GASKET	20.000 EA				
1220	823.31 300 MM GATE VALVE	14.000 EA				
1230	823.325 200 MM GATE VALVE	9.000 EA				
1240	823.331 150 MM GATE VALVE	20.000 EA				
1250	824.30 FIRE HYDRANTS	12.000 EA				
1260	825.311 19 MM CORPORATION	90.000 EA				
1270	825.312 19 MM CURB STOP	90.000 EA				
1280	825.32 50 MM CORPORATION	1.000 EA				
1290	825.3211 30 MM CORPORATION	3.000 EA				
1300	825.3212 40 MM CORPORATION	1.000 EA				
1310	825.322 50 MM CURB STOP	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010018.00

PROJECT(S): NH-1001(800)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1320	825.33 25 MM CORPORATION	2.000 EA				
1330	825.331 25 MM CURB STOP	2.000 EA				
1340	825.3311 30 MM CURB STOP	3.000 EA				
1350	825.3312 40 MM CURB STOP	1.000 EA				
1360	825.41 19 MM COPPER SERVICE	720.000 M				
1370	825.43 25 MM COPPER SERVICE	20.000 M				
1380	825.435 30 MM COPPER SERVICE	35.000 M				
1390	825.436 40 MM COPPER SERVICE	10.000 M				
1400	825.437 50 MM COPPER SERVICE	25.000 M				
1410	825.45 EXISTING SERVICE CONNECTION	6.000 EA				
1420	827.31 UNSUITABLE SOIL EXCAVATION REMOVE AND REPLACE	150.000 M3				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010018.00

PROJECT(S): NH-1001(800)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1430	827.311 UNSUITABLE SOIL EXCAVATION, REMOVE AND REFILL- BELOW GRADE	150.000 M3				
1440	827.33 TRENCH INSULATION	105.000 M				
	SECTION 0001 TOTAL					
	TOTAL BID					