

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 010198.01

PROJECTS

-----  
BR-1018(401)X  
BR-1019(801)X

COUNTY : ANDROSCOGGIN

CONTRACT ID : 010198.01

TURNER-LEEDS, BRIDGE REPLACEMENTS. WORK INCULDES BRIDGE REPLACEMENTS OVER THE ANDROSCOGGIN RIVER AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	10/01/09	\$ 1000.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010198.01

PROJECT(S): BR-1018(401)X  
BR-1019(801)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 Project I

0010	201.11 CLEARING	0.500 HA				
0020	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0030	203.20 COMMON EXCAVATION	4550.000 M3				
0040	203.21 ROCK EXCAVATION	375.000 M3				
0050	203.24 COMMON BORROW	5400.000 M3				
0060	203.25 GRANULAR BORROW	1090.000 M3				
0070	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	40.000 M3				
0080	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	160.000 M3				
0090	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	67.000 M3				
0100	206.10 STRUCTURAL EARTH EXCAVATION - PIERS	60.000 M3				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010198.01

PROJECT(S): BR-1018(401)X  
BR-1019(801)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	206.11 STRUCTURAL ROCK EXCAVATION - PIERS	40.000 M3				
0120	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	5100.000 M3				
0130	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	20.000 MG				
0140	403.210 HOT MIX ASPHALT 9.5 MM NOMINAL MAX SIZE	1726.000 MG				
0150	403.213 HOT MIX ASPHALT 12.5 MM, BASE	1093.000 MG				
0160	409.15 BITUMINOUS TACK COAT APPLIED	660.000 L				
0170	501.231 DYNAMIC LOADING TEST	1.000 EA				
0180	501.50 STEEL H-BEAM PILES 132 KG/M, DELIVERED	63.000 M				
0190	501.501 STEEL H-BEAM PILES 132 KG/M, IN PLACE	63.000 M				
0200	501.90 PILE TIPS	4.000 EA				
0210	501.91 PILE SPLICES	2.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010198.01

PROJECT(S): BR-1018(401)X  
BR-1019(801)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0230	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	M3 535.000				
0240	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0250	502.239 STRUCTURAL CONCRETE PIERS	LUMP	LUMP			
0260	502.24 STRUCTURAL CONCRETE PIERS (PLACED UNDER WATER)	M3 270.000				
0270	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP			
0280	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0290	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP	LUMP			
0300	502.56 CONCRETE FILL	M3 70.000				
0310	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	KG 44900.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010198.01

PROJECT(S): BR-1018(401)X  
BR-1019(801)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	503.13 REINFORCING STEEL, PLACING	44900.000 KG				
0330	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP	LUMP			
0340	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0350	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0360	507.0834 WYOMING STEEL BRIDGE RAILING	LUMP	LUMP			
0370	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0380	511.07 COFFERDAM: PIER NO. 1	LUMP	LUMP			
0390	511.07 COFFERDAM: PIER NO. 2	LUMP	LUMP			
0400	512.081 FRENCH DRAINS	LUMP	LUMP			
0410	514.06 CURING BOX FOR CONCRETE CYLINDERS	2.000 EA				

SCHEDULE OF ITEMS

CONTRACT ID: 010198.01

PROJECT(S): BR-1018(401)X  
BR-1019(801)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0420	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0430	520.21 EXPANSION DEVICE - GLAND SEAL	2.000 EA				
0440	523.52 BEARING INSTALLATION	21.000 EA				
0450	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	4.000 EA				
0460	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	17.000 EA				
0470	526.34 PERMANENT CONCRETE TRANSITION BARRIER	8.000 EA				
0480	603.169 375 MM CULVERT PIPE OPTION III	15.000 M				
0490	603.17 450 MM CULVERT PIPE OPTION I	15.000 M				
0500	604.092 CATCH BASIN TYPE B1-C	5.000 EA				
0510	604.246 CATCH BASIN TYPE F5	1.000 EA				
0520	605.09 150 MM UNDERDRAIN TYPE B	440.000 M				

SCHEDULE OF ITEMS

CONTRACT ID: 010198.01

PROJECT(S): BR-1018(401)X  
BR-1019(801)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	605.10 150 MM UNDERDRAIN OUTLET	35.000 M				
0540	605.11 300 MM UNDERDRAIN TYPE C	130.000 M				
0550	606.1721 BRIDGE TRANSITION - TYPE 1	8.000 EA				
0560	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	302.000 M				
0570	606.232 GUARDRAIL TYPE 3C - OVER 4.5 M RADIUS	23.000 M				
0580	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	3.000 EA				
0590	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	21.000 EA				
0600	606.79 GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0610	609.31 CURB TYPE 3	450.000 M				
0620	610.08 PLAIN RIPRAP	685.000 M3				
0630	610.16 HEAVY RIPRAP	80.000 M3				



SCHEDULE OF ITEMS

CONTRACT ID: 010198.01

PROJECT(S): BR-1018(401)X  
BR-1019(801)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0640	610.18 STONE DITCH PROTECTION	M3 92.000				
0650	613.319 EROSION CONTROL BLANKET	M2 520.000				
0660	615.07 LOAM	M3 1590.000				
0670	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	UN 18.000				
0680	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	UN 30.000				
0690	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	UN 48.000				
0700	619.1201 MULCH - PLAN QUANTITY	UN 48.000				
0710	619.1401 EROSION CONTROL MIX	M3 480.000				
0720	620.58 EROSION CONTROL GEOTEXTILE	M2 1025.000				
0730	621.01 EVERGREEN TREES (200 MM - 300 MM)	EA 50.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010198.01

PROJECT(S): BR-1018(401)X  
BR-1019(801)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0740	621.019 EVERGREEN TREES (600 MM - 900 MM) GROUP A	3.000 EA				
0750	621.025 EVERGREEN TREES (900 MM - 1200 MM) GROUP A	3.000 EA				
0760	621.031 EVERGREEN TREES (1200 MM - 1500 MM) GROUP A	3.000 EA				
0770	621.037 EVERGREEN TREES (1500 MM - 1800 MM) GROUP A	2.000 EA				
0780	621.043 EVERGREEN TREES (1800 MM - 2400 MM) GROUP A	10.000 EA				
0790	621.045 EVERGREEN TREES (1800 MM - 2400 MM) GROUP C	1.000 EA				
0800	621.047 EVERGREEN TREES (2400 MM - 2700 MM) GROUP B	7.000 EA				
0810	621.121 SMALL DECIDUOUS TREES (1500 MM - 1800 MM) GROUP B	5.000 EA				
0820	621.196 MEDIUM DECIDUOUS TREE (45 MM - 50 MM CALIPER) GROUP B	1.000 EA				
0830	621.246 LARGE DECIDUOUS TREES (900 MM - 1200 MM) GROUP A	12.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 010198.01

PROJECT(S): BR-1018(401)X  
BR-1019(801)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0840	621.255 LARGE DECIDUOUS TREES (2400 MM - 3000 MM) GROUP A	6.000 EA				
0850	621.273 LARGE DECIDUOUS TREE (50 MM - 65 MM CALIPER) GROUP A	1.000 EA				
0860	621.388 DWARF EVERGREENS (300 MM - 375 MM)	15.000 EA				
0870	621.487 BROADLEAF EVERGREENS (450 MM - 600 MM) GROUP B	3.000 EA				
0880	621.498 BROADLEAF EVERGREENS (750 MM - 900 MM) GROUP A	1.000 EA				
0890	621.51 DECIDUOUS SHRUBS (375 MM - 450 MM)	18.000 EA				
0900	621.511 DECIDUOUS SHRUBS (450MM - 600MM) GROUP A	25.000 EA				
0910	621.52 DECIDUOUS SHRUBS (200 MM - 375 MM) ROOTED CUTTINGS	40.000 EA				
0920	621.546 DECIDUOUS SHRUBS (600 MM - 900 MM) GROUP A	16.000 EA				
0930	621.552 DECIDUOUS SHRUBS (900 MM - 1200 MM) GROUP A	17.000 EA				
0940	621.616 BLUEBERRY SOD	6.000 M2				

SCHEDULE OF ITEMS

CONTRACT ID: 010198.01

PROJECT(S): BR-1018(401)X  
BR-1019(801)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0950	621.711 HERBACEOUS PERENNIALS GROUP B	54.000 EA				
0960	621.80 ESTABLISHMENT PERIOD	LUMP	LUMP			
0970	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY )	2520.000 M				
0980	629.05 HAND LABOR, STRAIGHT TIME	45.000 HR				
0990	631.121 HEAVY DUTY ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	45.000 HR				
1000	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	45.000 HR				
1010	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	50.000 HR				
1020	631.36 FOREPERSON	20.000 HR				
1030	637.071 DUST CONTROL	LUMP	LUMP			
1040	639.18 FIELD OFFICE TYPE A	1.000 EA				

SCHEDULE OF ITEMS

CONTRACT ID: 010198.01

PROJECT(S): BR-1018(401)X  
BR-1019(801)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1050	639.261 INSTRUMENTATION GEOTECHNICAL - TRADITIONAL SETTLEMENT PLATFORM TRADITIONAL SETTLEMENT PLATFORMS	LUMP	LUMP			
1060	652.38 FLAGGER	1000.000 HR				
1070	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
1080	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
1090	659.10 MOBILIZATION	LUMP	LUMP			
1100	660.21 ON-THE-JOB TRAINING (BID)	3000.000 HR				
1110	835.15 BOAT RAMP	LUMP	LUMP			
1120	841.481 REMOVABLE BOLLARD	2.000 EA				
	SECTION 0001 TOTAL					
	TOTAL BID					