

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 011049.00

PROJECTS

BH-1104 (900) X

COUNTY : SAGADAHOC

CONTRACT ID : 011049.00

ARROWSIC & GEORGETOWN, BRIDGE REPLACEMENT. WORK INCLUDES
 BACK RIVER BRIDGE REPLACEMENT, TEMPORARY BRIDGE, AND OTHER
 INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	05/28/10	\$ 1875.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011049.00

PROJECT(S): BH-1104(900)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.11 CLEARING	0.500 AC				
0020	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0030	202.20 REMOVING BITUMINOUS CONCRETE PAVEMENT	1450.000 SY				
0040	203.20 COMMON EXCAVATION	1915.000 CY				
0050	203.25 GRANULAR BORROW	800.000 CY				
0060	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	250.000 CY				
0070	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	1500.000 CY				
0080	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	200.000 CY				
0090	206.10 STRUCTURAL EARTH EXCAVATION - PIERS	70.000 CY				
0100	206.11 STRUCTURAL ROCK EXCAVATION - PIERS	80.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011049.00

PROJECT(S): BH-1104(900)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	2065.000 CY				
0120	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	12.000 T				
0130	403.210 HOT MIX ASPHALT 9.5 MM HMA	622.000 T				
0140	409.15 BITUMINOUS TACK COAT - APPLIED	115.000 G				
0150	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	625.000 CY				
0160	502.23 STRUCTURAL CONCRETE PIERS	190.000 CY				
0170	502.24 STRUCTURAL CONCRETE PIERS (PLACED UNDER WATER)	275.000 CY				
0180	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0190	502.41 STRUCTURAL CONCRETE SUPERSTRUCTURE SLAB	375.000 CY				
0200	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0210	502.56 CONCRETE FILL	50.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011049.00

PROJECT(S): BH-1104(900)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	144500.000 LB				
0230	503.13 REINFORCING STEEL, PLACING	144500.000 LB				
0240	503.24 MMFX 2 REINF. STEEL FAB & DELV.	36000.000 LB				
0250	503.25 MMFX 2 REINFORCING STEEL, PLACING	36000.000 LB				
0260	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP	LUMP			
0270	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0280	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0290	506.9102 ZINC RICH COATING SYSTEM (SHOP APPLIED)	LUMP	LUMP			
0300	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP	LUMP			
0310	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011049.00

PROJECT(S): BH-1104(900)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	510.10 SPECIAL DETOUR ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 20 FT. WIDE	LUMP	LUMP			
0330	511.07 COFFERDAM: PIER	LUMP	LUMP			
0340	512.081 FRENCH DRAINS	LUMP	LUMP			
0350	514.06 CURING BOX FOR CONCRETE CYLINDERS	EA 1.000				
0360	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	SY 500.000				
0370	520.21 EXPANSION DEVICE - GLAND SEAL	EA 2.000				
0380	523.52 BEARING INSTALLATION	EA 12.000				
0390	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	EA 4.000				
0400	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	EA 8.000				
0410	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	LF 400.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011049.00

PROJECT(S): BH-1104(900)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0420	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0430	527.34 WORK ZONE CRASH CUSHIONS	6.000 UN				
0440	603.179 18 INCH CULVERT PIPE OPTION III	86.000 LF				
0450	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0460	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	325.000 LF				
0470	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	25.000 LF				
0480	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	13.000 LF				
0490	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA				
0500	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0510	606.79 GUARDRAIL 350 FLARED TERMINAL	2.000 EA				
0520	610.08 PLAIN RIPRAP	1000.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011049.00

PROJECT(S): BH-1104(900)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	610.18 STONE DITCH PROTECTION	60.000 CY				
0540	613.319 EROSION CONTROL BLANKET	130.000 SY				
0550	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	19.000 UN				
0560	619.1401 EROSION CONTROL MIX	230.000 CY				
0570	620.58 EROSION CONTROL GEOTEXTILE	1200.000 SY				
0580	621.02 EVERGREEN TREES (2 FOOT - 3 FOOT) GROUP B	24.000 EA				
0590	621.043 EVERGREEN TREES (6 FOOT - 8 FOOT) GROUP A	6.000 EA				
0600	621.045 EVERGREEN TREES (6 FOOT - 8 FOOT) GROUP C	6.000 EA				
0610	621.273 LARGE DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP A	6.000 EA				
0620	621.546 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP A	12.000 EA				
0630	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	2850.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011049.00

PROJECT(S): BH-1104(900)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0640	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0650	631.121 HEAVY DUTY ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0660	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	10.000 HR				
0670	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR				
0680	631.36 FOREPERSON	10.000 HR				
0690	637.071 DUST CONTROL	LUMP	LUMP			
0700	639.18 FIELD OFFICE TYPE A	1.000 EA				
0710	652.38 FLAGGER	10.000 HR				
0720	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0730	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0740	659.10 MOBILIZATION	LUMP	LUMP			

SCHEDULE OF ITEMS

CONTRACT ID: 011049.00

PROJECT(S): BH-1104(900)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0750	660.21 ON-THE-JOB TRAINING (BID)	100.000 HR				
	SECTION 0001 TOTAL					
	TOTAL BID					

SCHEDULE OF ITEMS

DATE:
REVISED:

CONTRACT ID: 011049.00

PROJECT(S): BH-1104(900)X

LIST ITEMS ON THIS PAGE BY AMENDMENT

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
			.		.	
			.		.	
			.		.	
			.		.	
			.		.	
			.		.	
			.		.	
			.		.	
TOTAL BID			.		.	

SPECIAL PROVISIONS ATTACHED