

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 011055.00

PROJECTS

-----  
BR-1105(500)X

COUNTY : KNOX

MAINE DEPARTMENT OF TRANSPORTATION

PAGE: 2

CONTRACT ID : 011055.00

WARREN-THOMASTON, BRIDGE REPLACEMENT. WORK INCLUDES OYSTER RIVER BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	06/01/09	\$ 750.00

FOLLOWING GROUPS ARE ALTERNATES :

- GROUP AS1 BOX BEAM ALTERNATE
- GROUP AS2 NEW ENGLAND BULB TEE ALTERNATE

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

CONTRACT ID: 011055.00

PROJECT(S): BR-1105(500)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 COMMON ITEMS						
0010	201.23 REMOVING SINGLE TREE TOP ONLY	EA 2.000				
0020	201.24 REMOVING STUMP	EA 3.000				
0030	202.19 REMOVING EXISTING BRIDGE 1062	LUMP	LUMP			
0040	203.20 COMMON EXCAVATION	CY 1700.000				
0050	203.24 COMMON BORROW	CY 200.000				
0060	203.25 GRANULAR BORROW	CY 375.000				
0070	203.35 CRUSHED STONE FILL	CY 1.000				
0080	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	CY 40.000				
0090	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	CY 305.000				
0100	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY 1390.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011055.00

PROJECT(S): BR-1105(500)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	18.000 T				
0120	403.210 HOT MIX ASPHALT 9.5 MM HMA	186.000 T				
0130	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	165.000 T				
0140	409.15 BITUMINOUS TACK COAT - APPLIED	50.000 G				
0150	603.17 18 INCH CULVERT PIPE OPTION I	10.000 LF				
0160	603.173 18 INCH CORRUGATED ALUMINUM PIPE	2.000 LF				
0170	604.092 CATCH BASIN TYPE B1-C	3.000 EA				
0180	604.244 CATCH BASIN TYPE F4	1.000 EA				
0190	605.09 6 INCH UNDERDRAIN TYPE B	210.000 LF				
0200	605.13 18 INCH UNDERDRAIN TYPE C	350.000 LF				
0210	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				

SCHEDULE OF ITEMS

CONTRACT ID: 011055.00

PROJECT(S): BR-1105(500)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	238.000 LF				
0230	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	50.000 LF				
0240	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA				
0250	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0260	606.79 GUARDRAIL 350 FLARED TERMINAL	2.000 EA				
0270	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	2.000 EA				
0280	609.31 CURB TYPE 3	240.000 LF				
0290	610.08 PLAIN RIPRAP	1000.000 CY				
0300	610.16 HEAVY RIPRAP	700.000 CY				
0310	610.18 STONE DITCH PROTECTION	30.000 CY				
0320	613.319 EROSION CONTROL BLANKET	1800.000 SY				

SCHEDULE OF ITEMS

CONTRACT ID: 011055.00

PROJECT(S): BR-1105(500)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	615.07 LOAM	40.000 CY				
0340	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	4.000 UN				
0350	619.1401 EROSION CONTROL MIX	5.000 CY				
0360	620.58 EROSION CONTROL GEOTEXTILE	900.000 SY				
0370	620.604 GEOCELL CONFINEMENT SYSTEM	750.000 SF				
0380	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	1650.000 LF				
0390	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0400	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0410	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0420	631.36 FOREPERSON	10.000 HR				
0430	635.14 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	1252.000 SF				

SCHEDULE OF ITEMS

CONTRACT ID: 011055.00

PROJECT(S): BR-1105(500)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	637.071 DUST CONTROL	LUMP	LUMP			
0450	639.19 FIELD OFFICE TYPE B	EA 1.000				
0460	652.38 FLAGGER	HR 10.000				
0470	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0480	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0490	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					.

SECTION 0002 BOX BEAM ALTERNATE  
ALT GROUP AS1

0500	501.231 DYNAMIC LOADING TEST	EA 1.000				
0510	501.46 STEEL H-BEAM PILES 73 LBS/FT, DELIVERED	LF 430.000				
0520	501.461 STEEL H-BEAM PILES 73 LBS/FT, IN PLACE	LF 430.000				

SCHEDULE OF ITEMS

CONTRACT ID: 011055.00

PROJECT(S): BR-1105(500)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	501.90 PILE TIPS	10.000 EA				
0540	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0550	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0560	502.25 STRUCTURAL CONCRETE SUPERSTRUCTURE SLABS	LUMP	LUMP			
0570	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0580	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0590	503.14 EPOXY COATED REINFORCING STEEL, FABRICATED AND DELIVERED	4200.000 LB				
0600	503.15 EPOXY COATED REINFORCING STEEL PLACING	4200.000 LB				
0610	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP	LUMP			
0620	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0630	512.081 FRENCH DRAINS	LUMP	LUMP			



SCHEDULE OF ITEMS

CONTRACT ID: 011055.00

PROJECT(S): BR-1105(500)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0640	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0650	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0660	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0670	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0680	535.62 PRESTRESSED STRUCTURAL CONCRETE BOX BEAM	LUMP	LUMP			
	SECTION 0002 TOTAL					.

SECTION 0003 NEW ENGLAND BULB TEE ALTERNATE  
ALT GROUP AS2

0690	501.231 DYNAMIC LOADING TEST	1.000 EA				
0700	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	360.000 LF				
0710	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	360.000 LF				
0720	501.90 PILE TIPS	8.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011055.00

PROJECT(S): BR-1105(500)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0730	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0740	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0750	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP	LUMP			
0760	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0770	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0780	503.14 EPOXY COATED REINFORCING STEEL, FABRICATED AND DELIVERED	LB 9000.000				
0790	503.15 EPOXY COATED REINFORCING STEEL PLACING	LB 9000.000				
0800	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP	LUMP			
0810	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0820	512.081 FRENCH DRAINS	LUMP	LUMP			

SCHEDULE OF ITEMS

CONTRACT ID: 011055.00

PROJECT(S): BR-1105(500)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0830	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0840	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0850	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0860	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0870	535.61 PRESTRESSED STRUCTURAL CONCRETE I-GIRDERS	LUMP	LUMP			
	SECTION 0003 TOTAL					
	TOTAL BID					

