

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 011077.00

PROJECTS

NH-1107(700)E

NH-1107(800)E

COUNTY : SOMERSET

CONTRACT ID : 011077.00

CANAAN, HIGHWAY REHABILITATION. WORK INCLUDES GRADING,
DRAINAGE, BASE, RECYCLED PAVEMENT, HOT MIX ASPHALT,
GUARDRAIL, AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	08/01/09	\$ 1875.00

FOLLOWING GROUPS ARE ALTERNATES :

- GROUP AP1 PAVEMENT ALT. PMRAP
- GROUP AP2 PAVEMENT ALT. FOAMED ASPHALT
- GROUP AP1 PAVEMENT ALT. PMRAP
- GROUP AP2 PAVEMENT ALT. FOAMED ASPHALT

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011077.00

PROJECT(S): NH-1107(700)E
NH-1107(800)E

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.11 CLEARING	2.700 AC				
0020	201.23 REMOVING SINGLE TREE TOP ONLY	74.000 EA				
0030	201.24 REMOVING STUMP	74.000 EA				
0040	202.203 PAVEMENT BUTT JOINTS	365.000 SY				
0050	203.20 COMMON EXCAVATION	24800.000 CY				
0060	203.21 ROCK EXCAVATION	2200.000 CY				
0070	203.242 DIRTY BORROW	3100.000 CY				
0080	203.25 GRANULAR BORROW	1000.000 CY				
0090	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	100.000 CY				
0100	304.08 AGGREGATE BASE COURSE - SCREENED	17400.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011077.00

PROJECT(S): NH-1107(700)E
NH-1107(800)E

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1500.000 CY				
0120	403.207 HOT MIX ASPHALT 19.0 MM HMA	5050.000 T				
0130	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	550.000 T				
0140	403.210 HOT MIX ASPHALT 9.5 MM HMA	4400.000 T				
0150	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	5900.000 T				
0160	409.15 BITUMINOUS TACK COAT - APPLIED	4325.000 G				
0170	411.09 UNTREATED AGGREGATE SURFACE COURSE	200.000 CY				
0180	504.069 CONCRETE PIPE TIES	4.000 EA				
0190	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			
0200	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011077.00

PROJECT(S): NH-1107(700)E
NH-1107(800)E

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT		
			DOLLARS	CTS	DOLLARS	CTS	
0210	534.71 PRECAST CONCRETE BOX CULVERT DISTRIBUTION SLAB BOX CULVERT WITH WEIRS	LUMP	LUMP				
0220	603.16 15 INCH CULVERT PIPE OPTION I	LF 1400.000					
0230	603.17 18 INCH CULVERT PIPE OPTION I	LF 330.000					
0240	603.179 18 INCH CULVERT PIPE OPTION III	LF 260.000					
0250	603.199 24 INCH CULVERT PIPE OPTION III	LF 360.000					
0260	603.43 36 INCH REINFORCED CONCRETE PIPE CLASS IV	LF 80.000					
0270	605.09 6 INCH UNDERDRAIN TYPE B	LF 320.000					
0280	605.10 6 INCH UNDERDRAIN OUTLET	LF 40.000					
0290	606.24 GUARDRAIL TYPE 3D - SINGLE RAIL	LF 2350.500					
0300	606.241 GUARDRAIL TYPE 3D - 15 FOOT RADIUS AND LESS	LF 112.500					

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011077.00

PROJECT(S): NH-1107(700)E
NH-1107(800)E

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0310	606.242 GUARDRAIL TYPE 3D - OVER 15 FOOT RADIUS	112.500 LF				
0320	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	9.000 EA				
0330	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	19.000 EA				
0340	606.355 GUARDRAIL MOWING DELINEATORS	15.000 EA				
0350	606.47 SINGLE WOOD POST	10.000 EA				
0360	606.79 GUARDRAIL 350 FLARED TERMINAL	5.000 EA				
0370	609.31 CURB TYPE 3	1540.000 LF				
0380	610.08 PLAIN RIPRAP	120.000 CY				
0390	613.319 EROSION CONTROL BLANKET	7200.000 SY				
0400	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	490.000 UN				
0410	619.1201 MULCH - PLAN QUANTITY	490.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011077.00

PROJECT(S): NH-1107(700)E
NH-1107(800)E

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0420	620.58 EROSION CONTROL GEOTEXTILE	200.000 SY				
0430	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0440	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				
0450	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR				
0460	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	5.000 HR				
0470	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	80.000 HR				
0480	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR				
0490	639.19 FIELD OFFICE TYPE B	1.000 EA				
0500	641.78 HANDICAP RAMP	1.000 EA				
0510	652.312 TYPE III BARRICADE	10.000 EA				
0520	652.33 DRUM	100.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011077.00

PROJECT(S): NH-1107(700)E
NH-1107(800)E

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	652.34 CONE	100.000 EA				
0540	652.35 CONSTRUCTION SIGNS	1092.000 SF				
0550	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	280.000 CD				
0560	652.38 FLAGGER	5000.000 HR				
0570	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0580	659.10 MOBILIZATION	LUMP	LUMP			
0590	660.21 ON-THE-JOB TRAINING (BID)	1000.000 HR				
	SECTION 0001 TOTAL					.

SECTION 0002 PAVEMENT ALT. PMRAP
ALT GROUP AP1

0600	310.26 PLANT MIX RECYCLED ASPHALT PAVEMENT - 6 INCH DEPTH	34700.000 SY				
	SECTION 0002 TOTAL					.

SECTION 0003 PAVEMENT ALT. FOAMED ASPHALT
ALT GROUP AP2

SCHEDULE OF ITEMS

CONTRACT ID: 011077.00

PROJECT(S): NH-1107(700)E
 NH-1107(800)E

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0610	309.36 FULL DEPTH REC PAVEMENT W/FOAM ASPHALT 6 INCH DEPTH	34700.000 SY				
	SECTION 0003 TOTAL					
	TOTAL BID					

SCHEDULE OF ITEMS

DATE:

REVISED:

CONTRACT ID: 011077.00

PROJECT(S): NH-1107(700)E
NH-1107(800)E

LIST ITEMS ON THIS PAGE BY AMENDMENT

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
TOTAL BID				.		.

SPECIAL PROVISIONS ATTACHED