

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 011090.00

PROJECTS

BH-A109(000)X

COUNTY : CUMBERLAND

CONTRACT ID : 011090.00

HARPSWELL, BRIDGE REHABILITATION. WORK INCLUDES BAILEY ISLAND BRIDGE REHABILITATION OVER WILLS STRAIT AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	11/30/11	\$ 1875.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

CONTRACT ID: 011090.00

PROJECT(S): BH-A109(000)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.10 REMOVING EXISTING SUPERSTRUCTURE (PROPERTY OF CONTRACTOR)	LUMP	LUMP			
0020	202.121 REMOVING EXISTING CONCRETE	LUMP	LUMP			
0030	202.13 REMOVING EXISTING RAILINGS (RETAINED BY DEPARTMENT)	LF 2350.000				
0040	202.17 REMOVING EXISTING STRUCTURAL CONCRETE	LUMP	LUMP			
0050	203.20 COMMON EXCAVATION	CY 1410.000				
0060	203.21 ROCK EXCAVATION	CY 10.000				
0070	203.24 COMMON BORROW	CY 10.000				
0080	203.25 GRANULAR BORROW	CY 35.000				
0090	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY 1260.000				
0100	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	T 37.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011090.00

PROJECT(S): BH-A109(000)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.210 HOT MIX ASPHALT 9.5 MM HMA	628.000 T				
0120	409.15 BITUMINOUS TACK COAT - APPLIED	96.000 G				
0130	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	68.000 CY				
0140	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0150	502.248 UNDERWATER GROUT BAGS	3.000 CY				
0160	502.25 STRUCTURAL CONCRETE SUPERSTRUCTURE SLABS	LUMP	LUMP			
0170	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0180	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0190	502.56 CONCRETE FILL	20.000 CY				
0200	503.24 MMFX 2 REINF. STEEL FAB & DELV.	286100.000 LB				
0210	503.25 MMFX 2 REINFORCING STEEL, PLACING	286100.000 LB				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011090.00

PROJECT(S): BH-A109(000)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	503.32 STAINLESS STEEL REINFORCING STEEL FAB & DEL	LUMP	LUMP			
0230	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0240	510.10 SPECIAL DETOUR ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED SUBSTRUCTURE	LUMP	LUMP			
0250	510.10 SPECIAL DETOUR ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED SUPERSTRUCTURE (RETAINED BY DEPARTMENT)	LUMP	LUMP			
0260	512.081 FRENCH DRAINS	LUMP	LUMP			
0270	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0280	515.2101 EPOXY COATING FOR CONCRETE SURFACE	LUMP	LUMP			
0290	525.30 GRANITE MASONRY	SF 110.000				
0300	525.50 GRANITE REPLACEMENT STONE	EA 100.000				
0310	525.51 GRANITE SUPPORT STONE	EA 480.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011090.00

PROJECT(S): BH-A109(000)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	525.52 GRANITE PINNING OR WEDGING STONE	150.000 CY				
0330	528.9101 GLUE - LAMINATED TIMBER BRIDGE RAIL	LUMP	LUMP			
0340	528.9101 GLUE - LAMINATED TIMBER BRIDGE RAIL (Modified)	LUMP	LUMP			
0350	528.9104 GLUE-LAM TIMBER BRIDGE RAIL, 4 BAR	LUMP	LUMP			
0360	535.30 PRECAST DECK PANEL	LUMP	LUMP			
0370	535.62 PRESTRESSED STRUCTURAL CONCRETE BOX BEAM	LUMP	LUMP			
0380	603.15 12 INCH CULVERT PIPE OPTION I	90.000 LF				
0390	604.13 24 INCH CATCH BASIN TYPE E	1.000 EA				
0400	606.613 TIMBER BRIDGE TRANSITION	4.000 EA				
0410	610.16 HEAVY RIPRAP	35.000 CY				
0420	610.18 STONE DITCH PROTECTION	38.000 CY				

SCHEDULE OF ITEMS

CONTRACT ID: 011090.00

PROJECT(S): BH-A109(000)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	615.07 LOAM	20.000 CY				
0440	618.13 SEEDING METHOD NUMBER 1	3.000 UN				
0450	619.12 MULCH	3.000 UN				
0460	620.58 EROSION CONTROL GEOTEXTILE	125.000 SY				
0470	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	4950.000 LF				
0480	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0490	629.07 STONE MASON	8000.000 HR				
0500	629.08 LABORER	12000.000 HR				
0510	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0520	631.14 GRADER (INCLUDING OPERATOR)	10.000 HR				
0530	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				

SCHEDULE OF ITEMS

CONTRACT ID: 011090.00

PROJECT(S): BH-A109(000)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	631.36 FOREPERSON	4000.000 HR				
0550	639.18 FIELD OFFICE TYPE A	1.000 EA				
0560	642.183 GRANITE STEP	LUMP	LUMP			
0570	652.38 FLAGGER	500.000 HR				
0580	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0590	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0600	659.10 MOBILIZATION	LUMP	LUMP			
0610	660.21 ON-THE-JOB TRAINING (BID)	4000.000 HR				
0620	845.20 UTILITY ACCESS DOOR	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

