

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 011189.00

PROJECTS

STP-1118(900)X

SR-1634(300)X

COUNTY : ANDROSCOGGIN

CONTRACT ID : 011189.00

INTERSECTION IMPROVEMENTS AND SCHOOL ZONE FLASHING BEACONS

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
------	---------------	--------------------

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011189.00

PROJECT(S): STP-1118(900)X
SR-1634(300)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.202 REMOVING PAVEMENT SURFACE	726.000 SY				
0020	203.20 COMMON EXCAVATION	870.000 CY				
0030	203.25 GRANULAR BORROW	100.000 CY				
0040	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	50.000 CY				
0050	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	410.000 CY				
0060	403.1021 TEXTURED ASPHALT PAVEMENT	370.000 SY				
0070	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	102.000 T				
0080	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	100.000 T				
0090	403.213 HOT MIX ASPHALT 12.5 MM BASE	110.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011189.00

PROJECT(S): STP-1118(900)X

SR-1634(300)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	409.15 BITUMINOUS TACK COAT - APPLIED	60.000 G				
0110	411.09 UNTREATED AGGREGATE SURFACE COURSE	10.000 CY				
0120	603.16 15 INCH CULVERT PIPE OPTION I	16.000 LF				
0130	603.169 15 INCH CULVERT PIPE OPTION III	48.000 LF				
0140	603.201 30 INCH CORRUGATED METAL PIPE	32.000 LF				
0150	604.092 CATCH BASIN TYPE B1-C	3.000 EA				
0160	604.096 60 INCH CATCH BASIN TYPE B1-C	1.000 EA				
0170	604.16 ALTERING CATCH BASIN TO MANHOLES	1.000 EA				
0180	608.26 CURB RAMP DETECTABLE WARNING FIELD	64.000 SF				
0190	609.31 CURB TYPE 3	950.000 LF				
0200	609.34 CURB TYPE 5	490.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011189.00

PROJECT(S): STP-1118(900)X
SR-1634(300)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	609.35 CURB TYPE 5 - CIRCULAR	65.000 LF				
0220	609.40 RESET CURB TYPE 5	150.000 LF				
0230	610.08 PLAIN RIPRAP	2.000 CY				
0240	613.319 EROSION CONTROL BLANKET	40.000 SY				
0250	615.0701 LOAM - PLAN QUANTITY	170.000 CY				
0260	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	14.000 UN				
0270	619.1201 MULCH - PLAN QUANTITY	14.000 UN				
0280	620.58 EROSION CONTROL GEOTEXTILE	10.000 SY				
0290	626.11 PRECAST CONCRETE JUNCTION BOX	3.000 EA				
0300	626.22 NON-METALLIC CONDUIT	200.000 LF				
0310	626.31 18 INCH FOUNDATION	3.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011189.00

PROJECT(S): STP-1118(900)X
SR-1634(300)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	626.33 30 INCH FOUNDATION	2.000 EA				
0330	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	7900.000 LF				
0340	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	1050.000 SF				
0350	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0360	627.77 REMOVING PAVEMENT MARKINGS	1620.000 SF				
0370	627.95 STREETPRINT DURATHERM PAVEMENT MARKING	72.000 SF				
0380	629.05 HAND LABOR, STRAIGHT TIME	25.000 HR				
0390	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0400	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	25.000 HR				
0410	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	5.000 HR				
0420	631.22 FRONT END LOADER (INCLUDING OPERATOR)	20.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011189.00

PROJECT(S): STP-1118(900)X
SR-1634(300)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	5.000 HR				
0440	639.18 FIELD OFFICE TYPE A	1.000 EA				
0450	643.60 FLASHING BEACON AT: Rte.11 & Rte.26	LUMP	LUMP			
0460	643.60 FLASHING BEACON AT: Southbound Approach Rte.26	LUMP	LUMP			
0470	643.6002 SOLAR POWERED LED SCHOOL ZONE BEACON	2.000 EA				
0480	643.93 STRAIN POLE	2.000 EA				
0490	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	22.000 EA				
0500	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	17.000 EA				
0510	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	125.000 SF				
0520	652.31 TYPE I BARRICADE	5.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011189.00

PROJECT(S): STP-1118(900)X
SR-1634(300)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	652.311 TYPE II BARRICADE	5.000 EA				
0540	652.33 DRUM	50.000 EA				
0550	652.34 CONE	70.000 EA				
0560	652.35 CONSTRUCTION SIGNS	910.000 SF				
0570	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0580	652.38 FLAGGER	1750.000 HR				
0590	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0600	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	365.000 SY				
0610	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					