

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 012622.00

PROJECTS

-----

BR-1262(200)X

COUNTY : FRANKLIN

CONTRACT ID : 012622.00

CHESTERVILLE, BRIDGE REPLACEMENT. WORK INCLUDES BRIDGE REPLACEMENT OVER LITTLE NORRIDGEWOCK STREAM AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	09/30/08	\$ 400.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012622.00

PROJECT(S): BR-1262(200)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 BRIDGE ITEMS						
0010	202.192 REMOVE AND REPLACE EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	520.000 CY				
0030	203.24 COMMON BORROW	10.000 CY				
0040	203.25 GRANULAR BORROW	630.000 CY				
0050	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	800.000 CY				
0060	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	530.000 T				
0070	409.15 BITUMINOUS TACK COAT - APPLIED	50.000 G				
0080	502.331 CONCRETE REINFORCING COLLAR	LUMP	LUMP			
0090	509.19 ALUMINUM ALLOY STRUCTURAL PLATE PIPE ARCH	LUMP	LUMP			
0100	511.07 COFFERDAM: downstream	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012622.00

PROJECT(S): BR-1262(200)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	511.07 COFFERDAM: upstream	LUMP	LUMP			
0120	603.15 12 INCH CULVERT PIPE OPTION I	44.000 LF				
0130	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	338.000 LF				
0140	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA				
0150	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0160	606.59 GUARDRAIL TYPE 3 - 15 FOOT RADIUS AND LESS	25.000 LF				
0170	606.79 GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0180	610.08 PLAIN RIPRAP	330.000 CY				
0190	615.07 LOAM	21.000 CY				
0200	618.14 SEEDING METHOD NUMBER 2	4.000 UN				
0210	618.15 TEMPORARY SEEDING	5.000 LB				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012622.00

PROJECT(S): BR-1262(200)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	619.12 MULCH	7.000 UN				
0230	620.58 EROSION CONTROL GEOTEXTILE	665.000 SY				
0240	627.4071 REFLECTORIZING PLASTIC, WHITE OR YELLOW PAVE MARKING	975.000 LF				
0250	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0260	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0270	631.14 GRADER (INCLUDING OPERATOR)	10.000 HR				
0280	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR				
0290	639.19 FIELD OFFICE TYPE B	1.000 EA				
0300	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0310	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0320	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012622.00

PROJECT(S): BR-1262(200)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
	TOTAL BID					

SCHEDULE OF ITEMS

DATE :  
REVISED :

CONTRACT ID: 012622.00

PROJECT(S): BR-1262(200)X

LIST ITEMS ON THIS PAGE BY AMENDMENT

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
TOTAL BID						

SPECIAL PROVISIONS ATTACHED