

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 012635.00

PROJECTS

012635.00

COUNTY : SOMERSET

CONTRACT ID : 012635.00

NEW PORTLAND, BARTLETT BRIDGE REPLACEMENT. WORK INCLUDES
BARTLETT BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	05/15/10	\$ 750.00
01	10/15/09	\$ 1000.00
02	21 CALENDAR DAYS	\$ 500.00
03	14 CALENDAR DAYS	\$ 500.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012635.00

PROJECT(S): 012635.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.08 REMOVING BUILDING NO.: 1	LUMP	LUMP			
0020	202.15 REMOVING MANHOLE OR CATCH BASIN	1.000 EA				
0030	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0040	203.20 COMMON EXCAVATION	650.000 CY				
0050	203.24 COMMON BORROW	1150.000 CY				
0060	203.25 GRANULAR BORROW	365.000 CY				
0070	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	1200.000 CY				
0080	206.09 STRUCTURAL ROCK EXCAVATION - ABUTMENTS AND RETAINING WALLS	10.000 CY				
0090	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1825.000 CY				
0100	403.207 HOT MIX ASPHALT 19.0 MM HMA	435.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012635.00

PROJECT(S): 012635.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	36.000 T				
0120	403.210 HOT MIX ASPHALT 9.5 MM HMA	500.000 T				
0130	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	290.000 T				
0140	409.15 BITUMINOUS TACK COAT - APPLIED	220.000 G				
0150	501.231 DYNAMIC LOADING TEST	1.000 EA				
0160	501.46 STEEL H-BEAM PILES 73 LBS/FT, DELIVERED	139.000 LF				
0170	501.461 STEEL H-BEAM PILES 73 LBS/FT, IN PLACE	139.000 LF				
0180	501.90 PILE TIPS	5.000 EA				
0190	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0200	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0210	502.25 STRUCTURAL CONCRETE SUPERSTRUCTURE SLABS	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012635.00

PROJECT(S): 012635.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0230	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0240	502.56 CONCRETE FILL	22.000 CY				
0250	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	47600.000 LB				
0260	503.13 REINFORCING STEEL, PLACING	47600.000 LB				
0270	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP	LUMP			
0280	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0290	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0300	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			
0310	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0320	512.081 FRENCH DRAINS	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012635.00

PROJECT(S): 012635.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0340	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0350	523.52 BEARING INSTALLATION	5.000 EA				
0360	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	5.000 EA				
0370	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0380	603.169 15 INCH CULVERT PIPE OPTION III	225.000 LF				
0390	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	1.000 EA				
0400	604.246 CATCH BASIN TYPE F5	1.000 EA				
0410	606.17 GUARDRAIL TYPE 3B - SINGLE RAIL	525.000 LF				
0420	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0430	606.21 GUARDRAIL TYPE 3B - 15 FOOT RADIUS AND LESS	50.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012635.00

PROJECT(S): 012635.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0450	609.31 CURB TYPE 3	500.000 LF				
0460	610.08 PLAIN RIPRAP	650.000 CY				
0470	615.0701 LOAM - PLAN QUANTITY	120.000 CY				
0480	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	5.500 UN				
0490	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	9.000 UN				
0500	619.12 MULCH	14.500 UN				
0510	619.1401 EROSION CONTROL MIX	240.000 CY				
0520	620.58 NON WOVEN GEOTEXTILE	825.000 SY				
0530	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	2450.000 LF				
0540	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP		LUMP		

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012635.00

PROJECT(S): 012635.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0560	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0570	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	10.000 HR				
0580	635.14 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	1020.000 SF				
0590	639.18 FIELD OFFICE TYPE A	1.000 EA				
0600	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0610	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0620	659.10 MOBILIZATION	LUMP	LUMP			
0630	834.322 DRY HYDRANT - INSTALL ONLY	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

