

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 012637.00

PROJECTS

AC-BH-1263(700)X

COUNTY : WALDO

CONTRACT ID : 012637.00

SCOPE OF WORK: MILL BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK. IN WALDO COUNTY, PROJECT IS LOCATED OVER THE SAINT GEORGE RIVER ON ROUTE 131 & 173 APPROXIMATELY 4 MILES EAST OF THE TOWN LINE.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	06/15/10	\$ 750.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012637.00

PROJECT(S): AC-BH-1263(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.24 REMOVING STUMP	2.000 EA				
0020	202.08 REMOVING BUILDING NO.: 1	LUMP	LUMP			
0030	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0040	203.20 COMMON EXCAVATION	2150.000 CY				
0050	203.24 COMMON BORROW	20.000 CY				
0060	203.25 GRANULAR BORROW	1175.000 CY				
0070	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	10.000 CY				
0080	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	200.000 CY				
0090	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	100.000 CY				
0100	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	2810.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012637.00

PROJECT(S): AC-BH-1263(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.207 HOT MIX ASPHALT 19.0 MM HMA	540.000 T				
0120	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	350.000 T				
0130	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	77.000 T				
0140	409.15 BITUMINOUS TACK COAT - APPLIED	80.000 G				
0150	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	110.000 CY				
0160	502.56 CONCRETE FILL	10.000 CY				
0170	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	4000.000 LB				
0180	503.13 REINFORCING STEEL, PLACING	4000.000 LB				
0190	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			
0200	511.07 COFFERDAM: WALL NO. 1	LUMP	LUMP			
0210	511.07 COFFERDAM: WALL NO. 2	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012637.00

PROJECT(S): AC-BH-1263(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0230	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN				
0240	534.70 PRECAST STRUCTURAL CONCRETE ARCH	LUMP	LUMP			
0250	603.15 12 INCH CULVERT PIPE OPTION I	34.000 LF				
0260	603.16 15 INCH CULVERT PIPE OPTION I	44.000 LF				
0270	603.17 18 INCH CULVERT PIPE OPTION I	56.000 LF				
0280	604.092 CATCH BASIN TYPE B1-C	5.000 EA				
0290	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	1.000 EA				
0300	605.09 6 INCH UNDERDRAIN TYPE B	300.000 LF				
0310	605.10 6 INCH UNDERDRAIN OUTLET	20.000 LF				
0320	605.11 12 INCH UNDERDRAIN TYPE C	60.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012637.00

PROJECT(S): AC-BH-1263(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	605.12 15 INCH UNDERDRAIN TYPE C	190.000 LF				
0340	605.13 18 INCH UNDERDRAIN TYPE C	300.000 LF				
0350	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	337.500 LF				
0360	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	75.000 LF				
0370	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	3.000 EA				
0380	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0390	606.79 GUARDRAIL 350 FLARED TERMINAL	1.000 EA				
0400	609.31 CURB TYPE 3	775.000 LF				
0410	610.08 PLAIN RIPRAP	200.000 CY				
0420	610.18 STONE DITCH PROTECTION	55.000 CY				
0430	613.319 EROSION CONTROL BLANKET	80.000 SY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012637.00

PROJECT(S): AC-BH-1263(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	613.329 EXTENDED USE EROSION CONTROL BLANKETS	120.000 SY				
0450	615.0701 LOAM - PLAN QUANTITY	100.000 CY				
0460	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	9.000 UN				
0470	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	7.000 UN				
0480	618.15 TEMPORARY SEEDING	12.000 LB				
0490	619.1201 MULCH - PLAN QUANTITY	16.000 UN				
0500	620.58 NON WOVEN GEOTEXTILE	350.000 SY				
0510	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	2300.000 LF				
0520	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP		LUMP		
0530	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0540	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012637.00

PROJECT(S): AC-BH-1263(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR				
0560	635.14 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	1300.000 SF				
0570	639.18 FIELD OFFICE TYPE A	1.000 EA				
0580	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			
0590	652.33 DRUM	60.000 EA				
0600	652.34 CONE	60.000 EA				
0610	652.35 CONSTRUCTION SIGNS	250.000 SF				
0620	652.38 FLAGGER	300.000 HR				
0630	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0640	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0650	659.10 MOBILIZATION	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012637.00

PROJECT(S): AC-BH-1263(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	890.01 SPECIAL WORK #1 WATER MAIN	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

SCHEDULE OF ITEMS

DATE:
REVISED:

CONTRACT ID: 012637.00

PROJECT(S): AC-BH-1263(700)X

LIST ITEMS ON THIS PAGE BY AMENDMENT

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
			.			.
			.			.
			.			.
			.			.
			.			.
			.			.
			.			.
			.			.
	TOTAL BID		.			.

SPECIAL PROVISIONS ATTACHED