

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 012645.00

PROJECTS

-----

BR-1264(500)X

COUNTY : AROOSTOOK

CONTRACT ID : 012645.00

CRYSTAL, BRIDGE REPLACEMENT. WORK INCLUDES FISH STREAM  
BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	10/30/09	\$ 750.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012645.00

PROJECT(S): BR-1264(500)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 BRIDGE ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	1360.000 CY				
0030	203.25 GRANULAR BORROW	1255.000 CY				
0040	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	700.000 CY				
0050	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	460.000 CY				
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1100.000 CY				
0070	403.210 HOT MIX ASPHALT 9.5 MM HMA	265.000 T				
0080	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	90.000 T				
0090	409.15 BITUMINOUS TACK COAT - APPLIED	72.000 G				
0100	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	340.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012645.00

PROJECT(S): BR-1264(500)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	502.22 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS (PLACED UNDER WATER)	375.000 CY				
0120	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0130	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0140	502.56 CONCRETE FILL	10.000 CY				
0150	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	34300.000 LB				
0160	503.13 REINFORCING STEEL, PLACING	34300.000 LB				
0170	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			
0180	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0190	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 16'	LUMP	LUMP			
0200	511.07 COFFERDAM: ABUTMENT 1	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012645.00

PROJECT(S): BR-1264(500)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	511.07 COFFERDAM: ABUTMENT 2	LUMP	LUMP			
0220	512.081 FRENCH DRAINS	LUMP	LUMP			
0230	514.06 CURING BOX FOR CONCRETE CYLINDERS	EA 1.000				
0240	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0250	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0260	526.34 PERMANENT CONCRETE TRANSITION BARRIER	EA 4.000				
0270	527.34 WORK ZONE CRASH CUSHIONS	UN 6.000				
0280	535.62 PRESTRESSED STRUCTURAL CONCRETE BOX BEAM	LUMP	LUMP			
0290	606.1721 BRIDGE TRANSITION - TYPE 1	EA 4.000				
0300	606.178 GUARDRAIL BEAM	LF 100.000				
0310	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	EA 8.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012645.00

PROJECT(S): BR-1264(500)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	606.366 GUARDRAIL, REMOVE & RESET TYPE 3C	520.000 LF				
0330	610.08 PLAIN RIPRAP	570.000 CY				
0340	613.329 EXTENDED USE EROSION CONTROL BLANKETS	50.000 SY				
0350	615.07 LOAM	50.000 CY				
0360	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	4.000 UN				
0370	620.58 EROSION CONTROL GEOTEXTILE	700.000 SY				
0380	627.18 12 " SOLID WHITE PAVEMENT MARKING	24.000 LF				
0390	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	1200.000 LF				
0400	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0410	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0420	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012645.00

PROJECT(S): BR-1264(500)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	639.19 FIELD OFFICE TYPE B	1.000 EA				
0440	643.72 TEMPORARY TRAFFIC SIGNAL CRYSTAL SIDE	LUMP	LUMP			
0450	643.72 TEMPORARY TRAFFIC SIGNAL ISLAND FALLS SIDE	LUMP	LUMP			
0460	652.38 FLAGGER	100.000 HR				
0470	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0480	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0490	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

