

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 012781.00

PROJECTS

STP-1278(100)X

COUNTY : PENOBSCOT

CONTRACT ID : 012781.00

CHESTER - WOODVILLE, HIGHWAY IMPROVEMENTS. WORK INCLUDES
 HOT MIX ASPHALT, FULL DEPTH RECYCLED ASPHALT PAVEMENT WITH
 CEMENT, EXCAVATION, AGGREGATE SUBBASE COURSE GRAVEL,
 DRAINAGE, SAFETY IMPROVEMENTS, AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	10/11/08	\$ 1875.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012781.00

PROJECT(S): STP-1278(100)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 Category Number 0001						
0010	201.11 CLEARING	1.250 AC				
0020	201.23 REMOVING SINGLE TREE TOP ONLY	9.000 EA				
0030	201.24 REMOVING STUMP	9.000 EA				
0040	202.203 PAVEMENT BUTT JOINTS	160.000 SY				
0050	203.20 COMMON EXCAVATION	12750.000 CY				
0060	203.21 ROCK EXCAVATION	1600.000 CY				
0070	203.25 GRANULAR BORROW	2970.000 CY				
0080	211.20 INSLOPE EXCAVATION	23540.000 LF				
0090	211.30 DITCH EXCAVATION	30740.000 LF				
0100	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	5490.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012781.00

PROJECT(S): STP-1278(100)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	304.103 AGGREGATE SUBBASE - GRAVEL (TRUCK MEASURE)	510.000 CY				
0120	304.20 COLD IN-PLACE RECYCLING SHIMMING AGGREGATE	9000.000 CY				
0130	308.36 FULL DEPTH RECYCLED PAVEMENT WITH CEMENT	97807.000 SY				
0140	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	50.000 T				
0150	403.210 HOT MIX ASPHALT 9.5 MM HMA	6970.000 T				
0160	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	10010.000 T				
0170	409.15 BITUMINOUS TACK COAT - APPLIED	6000.000 G				
0180	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	360.000 CY				
0190	411.12 CRUSHED STONE SURFACE	10.000 T				
0200	509.131 STEEL STRUCTURAL PLATE ARCH MODIFICATION	LUMP	LUMP			
0210	603.16 15 INCH CULVERT PIPE OPTION I	785.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012781.00

PROJECT(S): STP-1278(100)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	603.17 18 INCH CULVERT PIPE OPTION I	318.000 LF				
0230	603.179 18 INCH CULVERT PIPE OPTION III	1261.000 LF				
0240	603.19 24 INCH CULVERT PIPE OPTION I	60.000 LF				
0250	603.199 24 INCH CULVERT PIPE OPTION III - TRUCK MEASURE	103.000 LF				
0260	603.205 30 INCH REINFORCED CONCRETE PIPE CLASS III	64.000 LF				
0270	603.235 48 INCH REINFORCED CONCRETE PIPE CLASS III	192.000 LF				
0280	605.09 6 INCH UNDERDRAIN TYPE B	200.000 LF				
0290	605.10 6 INCH UNDERDRAIN OUTLET	20.000 LF				
0300	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	287.500 LF				
0310	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	25.000 LF				
0320	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012781.00

PROJECT(S): STP-1278(100)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0340	606.47 SINGLE WOOD POST	14.000 EA				
0350	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0360	606.79 GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0370	609.31 CURB TYPE 3	440.000 LF				
0380	610.08 PLAIN RIPRAP	570.000 CY				
0390	610.18 STONE DITCH PROTECTION	300.000 CY				
0400	613.319 EROSION CONTROL BLANKET	13970.000 SY				
0410	615.07 LOAM	200.000 CY				
0420	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	1002.000 UN				
0430	619.1201 MULCH - PLAN QUANTITY	1002.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012781.00

PROJECT(S): STP-1278(100)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	620.54 STABILIZATION GEOTEXTILE	300.000 SY				
0450	620.58 EROSION CONTROL GEOTEXTILE	450.000 SY				
0460	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	270.000 SF				
0470	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0480	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0490	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	10.000 HR				
0500	631.11 AIR TOOL (INCLUDING OPERATOR)	10.000 HR				
0510	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR				
0520	631.132 SMALL BULLDOZER (INCLUDING OPERATOR)	20.000 HR				
0530	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0540	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	120.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012781.00

PROJECT(S): STP-1278(100)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	20.000 HR				
0560	639.19 FIELD OFFICE TYPE B	1.000 EA				
0570	652.31 TYPE I BARRICADE	35.000 EA				
0580	652.33 DRUM	50.000 EA				
0590	652.34 CONE	180.000 EA				
0600	652.35 CONSTRUCTION SIGNS	1215.000 SF				
0610	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	230.000 CD				
0620	652.38 FLAGGER	6000.000 HR				
0630	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0640	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

