

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 012797.00

PROJECTS

STP-1133(500)X

STP-1133(710)X

STP-1279(700)X

COUNTY : HANCOCK

CONTRACT ID : 012797.00

BAR HARBOR, HIGHWAY RESURFACING & INTERSECTION IMPROVEMENTS.
WORK INCLUDES GRADING, DRAINAGE, BASE, REMOVING PAVEMENT
SURFACE, HOT MIX ASPHALT, GUARDRAIL, CURB, GRANITE PAVERS,
PLANTING TREES AND SHRUBS, RETAINING WALL, TRAFFIC SIGNALS
AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	06/19/10	\$ 900.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012797.00

PROJECT(S): STP-1133(500)X
 STP-1133(710)X
 STP-1279(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 PROJECT ITEMS

0010	201.11 CLEARING	2.500 AC				
0020	201.23 REMOVING SINGLE TREE TOP ONLY	3.000 EA				
0030	201.24 REMOVING STUMP	4.000 EA				
0040	202.08 REMOVING BUILDING NO.: 1	LUMP	LUMP			
0050	202.08 REMOVING BUILDING NO.: 2	LUMP	LUMP			
0060	202.202 REMOVING PAVEMENT SURFACE	15310.000 SY				
0070	202.203 PAVEMENT BUTT JOINTS	470.000 SY				
0080	203.20 COMMON EXCAVATION	10200.000 CY				
0090	203.21 ROCK EXCAVATION	1000.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012797.00

PROJECT(S): STP-1133(500)X
 STP-1133(710)X
 STP-1279(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	203.2312 HEALTH AND SAFETY PLAN	LUMP	LUMP			
0110	203.2333 DISPOSAL OF SPECIAL EXCAVATION	50.000 T				
0120	203.25 GRANULAR BORROW	100.000 CY				
0130	205.51 WIDENING OF EXISTING SHOULDER - PLAN QUANTITY	186.000 SY				
0140	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	100.000 CY				
0150	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	575.000 CY				
0160	211.20 INSLOPE EXCAVATION	19030.000 LF				
0170	211.22 INSLOPE EXCAVATION - GUARDRAIL	2771.000 LF				
0180	211.30 DITCH EXCAVATION	3310.000 LF				
0190	304.09 AGGREGATE BASE COURSE - CRUSHED	6250.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012797.00

PROJECT(S): STP-1133(500)X
 STP-1133(710)X
 STP-1279(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	175.000 CY				
0210	304.103 AGGREGATE SUBBASE - GRAVEL (TRUCK MEASURE)	30.000 CY				
0220	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	325.000 T				
0230	403.210 HOT MIX ASPHALT 9.5 MM HMA	8920.000 T				
0240	403.211 HOT MIX ASPHALT (SHIMMING)	3740.000 T				
0250	403.213 HOT MIX ASPHALT 12.5 MM BASE	2000.000 T				
0260	409.15 BITUMINOUS TACK COAT - APPLIED	5460.000 G				
0270	411.09 UNTREATED AGGREGATE SURFACE COURSE	100.000 CY				
0280	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	60.000 CY				
0290	502.341 STRUCTURAL CONCRETE ROADWAY MEDIAN	35.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012797.00

PROJECT(S): STP-1133(500)X
 STP-1133(710)X
 STP-1279(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0300	527.303 ENERGY ABSORBING SYSTEM (ET-PLUS)	6.000 EA				
0310	603.159 12 INCH CULVERT PIPE OPTION III	265.000 LF				
0320	603.16 15 INCH CULVERT PIPE OPTION I	84.000 LF				
0330	603.169 15 INCH CULVERT PIPE OPTION III	14.500 LF				
0340	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	28.000 LF				
0350	603.179 18 INCH CULVERT PIPE OPTION III	221.000 LF				
0360	604.092 CATCH BASIN TYPE B1-C	18.000 EA				
0370	605.09 6 INCH UNDERDRAIN TYPE B	1800.000 LF				
0380	605.11 12 INCH UNDERDRAIN TYPE C	1040.000 LF				
0390	605.13 18 INCH UNDERDRAIN TYPE C	121.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012797.00

PROJECT(S): STP-1133(500)X
 STP-1133(710)X
 STP-1279(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0400	606.178 GUARDRAIL BEAM	250.000 LF				
0410	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	2436.000 LF				
0420	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	115.000 LF				
0430	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	50.000 LF				
0440	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	7.000 EA				
0450	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	48.000 EA				
0460	606.358 GUARDRAIL, MODIFY, TYPE 3B TO 3C	3813.500 LF				
0470	606.367 REPLACE UNUSABLE EXISTING GUARDRAIL POSTS	20.000 EA				
0480	606.48 SINGLE GALVANIZED STEEL POST	20.000 EA				
0490	606.79 GUARDRAIL 350 FLARED TERMINAL	15.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012797.00

PROJECT(S): STP-1133(500)X
 STP-1133(710)X
 STP-1279(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0500	608.28 GRANITE PAVERS WITH SAND BASE	51.000 SY				
0510	609.31 CURB TYPE 3	2420.000 LF				
0520	609.34 CURB TYPE 5	1000.000 LF				
0530	609.35 CURB TYPE 5 - CIRCULAR	370.000 LF				
0540	610.08 PLAIN RIPRAP	92.000 CY				
0550	610.20 FIELD STONE	18.000 EA				
0560	613.319 EROSION CONTROL BLANKET	1623.000 SY				
0570	615.07 LOAM	1490.000 CY				
0580	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	103.000 UN				
0590	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	210.000 UN				
0600	619.12 MULCH	100.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012797.00

PROJECT(S): STP-1133(500)X
 STP-1133(710)X
 STP-1279(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0610	619.1201 MULCH - PLAN QUANTITY	213.000 UN				
0620	619.1301 BARK MULCH	40.000 CY				
0630	620.56 DRAINAGE GEOTEXTILE	720.000 SY				
0640	620.58 NON WOVEN GEOTEXTILE	82.000 SY				
0650	621.044 EVERGREEN TREES (6 FOOT - 8 FOOT) GROUP B	1.000 EA				
0660	621.185 MEDIUM DECIDUOUS TREES (8 FOOT - 10 FOOT) GROUP B	1.000 EA				
0670	621.186 MEDIUM DECIDUOUS TREES (8 FOOT - 10 FOOT) GROUP C	1.000 EA				
0680	621.202 MEDIUM DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP B	18.000 EA				
0690	621.273 LARGE DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP A	1.000 EA				
0700	621.279 LARGE DECIDUOUS TREE (2.50 INCH - 3 INCH CALIPER) GROUP A	8.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012797.00

PROJECT(S): STP-1133(500)X
 STP-1133(710)X
 STP-1279(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0710	621.389 DWARF EVERGREENS (15 INCH - 18 INCH) GROUP A	50.000 EA				
0720	621.395 DWARF EVERGREENS (18 INCH - 24 INCH) GROUP A	50.000 EA				
0730	621.401 DWARF EVERGREENS (2 FOOT - 2.50 FOOT) GROUP A	50.000 EA				
0740	621.559 DECIDUOUS SHRUBS (4 FOOT - 5 FOOT) GROUP B	2.000 EA				
0750	621.711 HERBACEOUS PERENNIALS GROUP B	1960.000 EA				
0760	626.11 PRECAST CONCRETE JUNCTION BOX	4.000 EA				
0770	626.22 NON-METALLIC CONDUIT	300.000 LF				
0780	626.33 30 INCH FOUNDATION	2.000 EA				
0790	627.18 12 " SOLID WHITE PAVEMENT MARKING	9600.000 LF				
0800	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	24024.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012797.00

PROJECT(S): STP-1133(500)X
 STP-1133(710)X
 STP-1279(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0810	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	1200.000 SF				
0820	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0830	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				
0840	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	20.000 HR				
0850	631.11 AIR TOOL (INCLUDING OPERATOR)	20.000 HR				
0860	631.111 TRACTOR MOUNTED HYDRAULIC HAMMER	10.000 HR				
0870	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	115.000 HR				
0880	631.132 SMALL BULLDOZER (INCLUDING OPERATOR)	10.000 HR				
0890	631.14 GRADER (INCLUDING OPERATOR)	60.000 HR				
0900	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	10.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012797.00

PROJECT(S): STP-1133(500)X
 STP-1133(710)X
 STP-1279(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0910	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	205.000 HR				
0920	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	35.000 HR				
0930	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	10.000 HR				
0940	631.22 FRONT END LOADER (INCLUDING OPERATOR)	10.000 HR				
0950	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	45.000 HR				
0960	635.31 PREFAB CONCRETE BLOCK GRAVITY WALL	765.000 SF				
0970	639.18 FIELD OFFICE TYPE A	1.000 EA				
0980	643.80 TRAFFIC SIGNALS AT	LUMP	LUMP			
0990	643.93 STRAIN POLE	2.000 EA				
1000	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	16.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012797.00

PROJECT(S): STP-1133(500)X
 STP-1133(710)X
 STP-1279(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1010	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	13.000 EA				
1020	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	100.000 SF				
1030	652.31 TYPE I BARRICADE	8.000 EA				
1040	652.311 TYPE II BARRICADE	75.000 EA				
1050	652.33 DRUM	170.000 EA				
1060	652.34 CONE	240.000 EA				
1070	652.35 CONSTRUCTION SIGNS	1192.000 SF				
1080	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
1090	652.38 FLAGGER	10415.000 HR				
1100	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012797.00

PROJECT(S): STP-1133(500)X
 STP-1133(710)X
 STP-1279(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1110	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	450.000 SY				
1120	659.10 MOBILIZATION	LUMP	LUMP			
1130	660.21 ON-THE-JOB TRAINING (BID)	1000.000 HR				
	SECTION 0001 TOTAL					
	TOTAL BID					

SCHEDULE OF ITEMS

DATE:
REVISED:

CONTRACT ID: 012797.00

PROJECT(S): STP-1133(500)X
STP-1133(710)X
STP-1279(700)X

LIST ITEMS ON THIS PAGE BY AMENDMENT

CONTRACTOR :

Table with columns: LINE NO, ITEM DESCRIPTION, APPROX. QUANTITY AND UNITS, UNIT PRICE (DOLLARS, CTS), BID AMOUNT (DOLLARS, CTS). Includes a total bid row at the bottom.

SPECIAL PROVISIONS ATTACHED