

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 012926.00

PROJECTS

IM-1292 (600) E
IM-1294 (200) E
IM-95-1294 (900) E

COUNTY : PENOBSCOT

CONTRACT ID : 012926.00

HERMON TO OLD TOWN, HIGHWAY RESURFACING & BRIDGE REPAIR.
WORK INCLUDES HOT MIX ASPHALT OVERLAY, MILLING, BRIDGE
REPAIRS, DRAINAGE, GUARDRAIL SAFETY UPDATES, AND OTHER
INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	06/27/08	\$ 1875.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012926.00

PROJECT(S): IM-1292(600)E
 IM-1294(200)E
 IM-95-1294(900)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 PROJECT ITEMS

0010	201.12 SELECTIVE CLEARING AND THINNING	AC 0.750				
0020	202.202 REMOVING PAVEMENT SURFACE	SY 410000.000				
0030	203.20 COMMON EXCAVATION BROADWAY	CY 24.000				
0040	203.242 DIRTY BORROW	CY 575.000				
0050	205.51 WIDENING OF EXISTING SHOULDER	SY 1800.000				
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL BROADWAY	CY 24.000				
0070	403.210 HOT MIX ASPHALT 9.5 MM HMA	T 32250.000				
0080	403.211 HOT MIX ASPHALT (SHIMMING)	T 2800.000				
0090	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	T 16000.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012926.00

PROJECT(S): IM-1292(600)E
 IM-1294(200)E
 IM-95-1294(900)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	403.324 ROSPHALT 50 HIGH PERFORMANCE RUBBERIZED ASPHALT	2100.000 T				
0110	409.15 BITUMINOUS TACK COAT - APPLIED	28250.000 G				
0120	424.3331 ASPHALT LOW MODULUS CRACK SEALER, APPLIED	15000.000 LB				
0130	424.3333 LOW MODULUS JOINT SEALER, APPLIED	195905.000 LF				
0140	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	3480.000 LB				
0150	503.13 REINFORCING STEEL, PLACING	3480.000 LB				
0160	504.069 CONCRETE PIPE TIES	14.000 EA				
0170	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			
0180	518.50 REPAIR OF UPWARD FACING SURFACES - TO REINFORCING STEEL < 7.9 IN.	3900.000 SF				
0190	518.51 REPAIR OF UPWARD FACING SURFACES - BELOW REINFORCING STEEL < 7.9 IN.	3650.000 SF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012926.00

PROJECT(S): IM-1292(600)E
 IM-1294(200)E
 IM-95-1294(900)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	518.60 REPAIR OF VERTICAL SURFACES < 7.9 IN.	1400.000 SF				
0210	518.61 REPAIR OF VERTICAL SURFACES > 7.9 IN.	9.000 CY				
0220	520.22 EXPANSION DEVICE - COMPRESSION SEAL	16.000 EA				
0230	524.30 TEMPORARY STRUCTURAL SUPPORT	1.000 EA				
0240	526.70 TEMPORARY CONCRETE BARRIER	2000.000 LF				
0250	527.34 WORK ZONE CRASH CUSHIONS	6.000 UN				
0260	603.16 15 INCH CULVERT PIPE OPTION I	720.000 LF				
0270	603.161 15 INCH CORRUGATED METAL PIPE	19.000 LF				
0280	603.215 36 INCH REINFORCED CONCRETE PIPE CLASS III	64.000 LF				
0290	603.225 42 INCH REINFORCED CONCRETE PIPE CLASS III	24.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012926.00

PROJECT(S): IM-1292(600)E
 IM-1294(200)E
 IM-95-1294(900)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0300	603.7418 REMOVE & RELAY 18 INCH CONCRETE PIPE	8.000 LF				
0310	604.092 CATCH BASIN TYPE B1-C	1.000 EA				
0320	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	39.000 EA				
0330	606.1721 BRIDGE TRANSITION - TYPE 1	15.000 EA				
0340	606.178 GUARDRAIL BEAM	1800.000 LF				
0350	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	10.000 EA				
0360	606.352 REFLECTORIZED BEAM GUARDRAIL DELINEATORS	1300.000 EA				
0370	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	94.000 EA				
0380	606.3581 GUARDRAIL, MODIFY EXISTING TO TYPE 3D	1050.000 LF				
0390	606.362 GUARDRAIL ADJUSTED	5500.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012926.00

PROJECT(S): IM-1292(600)E
 IM-1294(200)E
 IM-95-1294(900)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0400	606.363 GUARDRAIL REMOVE AND DISPOSE	75.000 LF				
0410	606.367 REPLACE UNUSABLE EXISTING GUARDRAIL POSTS	15.000 EA				
0420	606.63 THRIE BEAM RAIL BEAM	50.000 LF				
0430	606.79 GUARDRAIL 350 FLARED TERMINAL	38.000 EA				
0440	606.792 GUARDRAIL 350 MEDIAN TERMINAL SYSTEM FLARED	9.000 EA				
0450	607.421 SCREENING FENCE KENDUSKEAG AVE PIER REHAB	500.000 LF				
0460	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	6.000 EA				
0470	612.06 BITUMINOUS SEALING - BLACK	650.000 SY				
0480	613.319 EROSION CONTROL BLANKET	6000.000 SY				
0490	618.14 SEEDING METHOD NUMBER 2	250.000 UN				
0500	619.12 MULCH	250.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012926.00

PROJECT(S): IM-1292(600)E
 IM-1294(200)E
 IM-95-1294(900)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0510	627.18 12 " SOLID WHITE PAVEMENT MARKING	15500.000 LF				
0520	627.72 6 INCH WHITE PAVEMENT MARKING LINE	304000.000 LF				
0530	627.74 6 INCH YELLOW PAVEMENT MARKING LINE	157000.000 LF				
0540	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	8650.000 SF				
0550	627.77 REMOVING PAVEMENT MARKINGS	700.000 SF				
0560	627.781 TEMPORARY 6 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	600000.000 LF				
0570	629.05 HAND LABOR, STRAIGHT TIME	220.000 HR				
0580	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	280.000 HR				
0590	631.122 MINI ALL-PURPOSE EXCAVATOR (INCLUDING OPERATOR)	60.000 HR				
0600	631.133 SKID STEER (INCLUDING OPERATOR)	80.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012926.00

PROJECT(S): IM-1292(600)E
 IM-1294(200)E
 IM-95-1294(900)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0610	631.14 GRADER (INCLUDING OPERATOR)	90.000 HR				
0620	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	650.000 HR				
0630	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR				
0640	631.22 FRONT END LOADER (INCLUDING OPERATOR)	90.000 HR				
0650	631.52 SIGN CREW	200.000 HR				
0660	639.18 FIELD OFFICE TYPE A	1.000 EA				
0670	643.73 TEMPORARY TRAFFIC SIGNAL	2.000 EA				
0680	643.86 TRAFFIC SIGNAL LOOP DETECTORS	12.000 EA				
0690	645.306 FLEXIBLE REFLECTORIZED DELINEATOR	130.000 EA				
0700	652.30 FLASHING ARROW BOARD	6.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012926.00

PROJECT(S): IM-1292(600)E
 IM-1294(200)E
 IM-95-1294(900)E

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0710	652.312 TYPE III BARRICADE	10.000 EA				
0720	652.33 DRUM	700.000 EA				
0730	652.34 CONE	300.000 EA				
0740	652.35 CONSTRUCTION SIGNS	6200.000 SF				
0750	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	189.000 CD				
0760	652.38 FLAGGER	250.000 HR				
0770	652.41 PORTABLE - CHANGEABLE MESSAGE SIGN	10.000 EA				
0780	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0790	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

