

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 012975.00

PROJECTS

012975.00

COUNTY : WASHINGTON

CONTRACT ID : 012975.00

LAMBERT LAKE, CULVERT REPLACEMENT. WORK INCLUDES
INSTALLATION OF A PRE-CAST CONCRETE BOX CULVERT 4' X 8' X
56' AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	10/12/07	\$ 200.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

CONTRACT ID: 012975.00

PROJECT(S): 012975.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.11 CLEARING	0.030 AC				
0020	202.203 PAVEMENT BUTT JOINTS	130.000 SY				
0030	203.25 GRANULAR BORROW	90.000 CY				
0040	205.41 RECONSTRUCTION OF EXISTING SHOULDER PLAN QUANTITY	220.000 SY				
0050	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	110.000 CY				
0060	211.20 INSLOPE EXCAVATION	800.000 LF				
0070	304.13 DENSE GRADED CRUSHED AGGREGATE SUBBASE	870.000 CY				
0080	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	10.000 T				
0090	403.210 HOT MIX ASPHALT 9.5 MM HMA	130.000 T				
0100	403.211 HOT MIX ASPHALT (SHIMMING)	70.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012975.00

PROJECT(S): 012975.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	160.000 T				
0120	409.15 BITUMINOUS TACK COAT - APPLIED	60.000 G				
0130	534.71 PRECAST CONCRETE BOX CULVERT 4' X 8' X 56'	LUMP	LUMP			
0140	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	225.000 LF				
0150	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0160	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0170	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0180	610.08 PLAIN RIPRAP	90.000 CY				
0190	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	12.000 UN				
0200	619.1201 MULCH - PLAN QUANTITY	12.000 UN				
0210	620.58 EROSION CONTROL GEOTEXTILE	180.000 SY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012975.00

PROJECT(S): 012975.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0230	627.811 TEMPORARY BI-DIRECTIONAL YELLOW DELINEATORS	EA 20.000				
0240	629.05 HAND LABOR, STRAIGHT TIME	HR 5.000				
0250	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	HR 5.000				
0260	631.11 AIR TOOL (INCLUDING OPERATOR)	HR 5.000				
0270	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	HR 5.000				
0280	631.132 SMALL BULLDOZER (INCLUDING OPERATOR)	HR 5.000				
0290	631.14 GRADER (INCLUDING OPERATOR)	HR 5.000				
0300	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	HR 5.000				
0310	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	HR 5.000				
0320	652.31 TYPE I BARRICADE	EA 10.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012975.00

PROJECT(S): 012975.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	652.33 DRUM	10.000 EA				
0340	652.34 CONE	60.000 EA				
0350	652.35 CONSTRUCTION SIGNS	270.000 SF				
0360	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	60.000 CD				
0370	652.38 FLAGGER	190.000 HR				
0380	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0390	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

SCHEDULE OF ITEMS

CONTRACT ID: 012975.00

PROJECT(S): 012975.00

LIST ITEMS ON THIS PAGE BY AMENDMENT

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
TOTAL BID						

SPECIAL PROVISIONS ATTACHED