

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 013061.00

PROJECTS

STP-1306(100)X

COUNTY : ANDROSCOGGIN

CONTRACT ID : 013061.00

LEWISTON, HIGHWAY RECONSTRUCTION. WORK INCLUDES GRADING,
DRAINAGE, BASE, HOT MIX ASPHALT, CURB, PLANTING TREES AND
SHRUBS, TRAFFIC SIGNALS, AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	06/18/10	\$ 900.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013061.00

PROJECT(S): STP-1306(100)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.23 REMOVING SINGLE TREE TOP ONLY	EA 74.000				
0020	201.24 REMOVING STUMP	EA 74.000				
0030	202.15 REMOVING MANHOLE OR CATCH BASIN	EA 9.000				
0040	202.202 REMOVING PAVEMENT SURFACE	SY 13970.000				
0050	203.20 COMMON EXCAVATION	CY 7850.000				
0060	203.25 GRANULAR BORROW	CY 50.000				
0070	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	CY 50.000				
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY 5450.000				
0090	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	T 1700.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013061.00

PROJECT(S): STP-1306(100)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	T 245.000				
0110	403.211 HOT MIX ASPHALT (SHIMMING)	T 100.000				
0120	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	T 950.000				
0130	409.15 BITUMINOUS TACK COAT - APPLIED	G 870.000				
0140	502.35 STRUCTURAL CONCRETE, STAMPED COLORED CONCRETE PAVEMENT	SY 1150.000				
0150	603.155 12 INCH REINFORCED CONCRETE PIPE CLASS III	LF 18.000				
0160	603.169 15 INCH CULVERT PIPE OPTION III	LF 8.000				
0170	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	LF 52.000				
0180	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	LF 38.000				
0190	604.072 CATCH BASIN TYPE A1-C	EA 27.125				
0200	604.092 CATCH BASIN TYPE B1-C	EA 1.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013061.00

PROJECT(S): STP-1306(100)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	604.163 ABANDONING CATCH BASIN	EA 8.000				
0220	604.164 REBUILDING CATCH BASIN	EA 2.000				
0230	604.166 REBUILDING MANHOLE	EA 1.000				
0240	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	EA 1.000				
0250	605.09 6 INCH UNDERDRAIN TYPE B	LF 490.000				
0260	605.11 12 INCH UNDERDRAIN TYPE C	LF 1550.000				
0270	605.12 15 INCH UNDERDRAIN TYPE C	LF 2650.000				
0280	605.13 18 INCH UNDERDRAIN TYPE C	LF 1050.000				
0290	608.26 CURB RAMP DETECTABLE WARNING FIELD	SF 136.000				
0300	609.11 VERTICAL CURB TYPE 1	LF 1100.000				
0310	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	LF 290.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013061.00

PROJECT(S): STP-1306(100)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	609.234 TERMINAL CURB TYPE 1 - 4 FOOT	EA 13.000				
0330	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	EA 4.000				
0340	609.2371 TERMINAL CURB TYPE 1- 7 FT - CIRCULAR	EA 20.000				
0350	609.31 CURB TYPE 3	LF 18.000				
0360	609.34 CURB TYPE 5	LF 3680.000				
0370	609.35 CURB TYPE 5 - CIRCULAR	LF 48.000				
0380	609.38 RESET CURB TYPE 1	LF 3500.000				
0390	615.07 LOAM	CY 600.000				
0400	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	UN 43.000				
0410	619.1201 MULCH - PLAN QUANTITY	UN 43.000				
0420	619.1301 BARK MULCH	CY 10.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013061.00

PROJECT(S): STP-1306(100)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	621.025 EVERGREEN TREES (3 FOOT - 4 FOOT) GROUP A	EA 18.000				
0440	621.037 EVERGREEN TREES (5 FOOT - 6 FOOT) GROUP A	EA 48.000				
0450	621.043 EVERGREEN TREES (6 FOOT - 8 FOOT) GROUP A	EA 15.000				
0460	621.044 EVERGREEN TREES (6 FOOT - 8 FOOT) GROUP B	EA 48.000				
0470	621.045 EVERGREEN TREES (6 FOOT - 8 FOOT) GROUP C	EA 6.000				
0480	621.121 SMALL DECIDUOUS TREES (5 FOOT - 6 FOOT) GROUP B	EA 9.000				
0490	621.18 MEDIUM DECIDUOUS TREES (6 FOOT - 8 FOOT) GROUP C	EA 6.000				
0500	621.201 MEDIUM DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP A	EA 21.000				
0510	621.202 MEDIUM DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP B	EA 6.000				
0520	621.203 MEDIUM DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP C	EA 12.000				
0530	621.279 LARGE DECIDUOUS TREE (2.50 INCH - 3 INCH CALIPER) GROUP A	EA 9.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013061.00

PROJECT(S): STP-1306(100)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	621.28 LARGE DECIDUOUS TREE (2.50 INCH - 3 INCH CALIPER) GROUP B	EA 6.000				
0550	621.281 LARGE DECIDUOUS TREE (2.50 INCH - 3 INCH CALIPER) GROUP C	EA 6.000				
0560	621.54 DECIDUOUS SHRUBS (18 INCH - 24 INCH) GROUP A	EA 54.000				
0570	621.547 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP B	EA 12.000				
0580	621.552 DECIDUOUS SHRUBS (3 FOOT - 4 FOOT) GROUP A	EA 12.000				
0590	621.71 HERBACEOUS PERENNIALS GROUP A	EA 432.000				
0600	621.80 ESTABLISHMENT PERIOD	LUMP	LUMP			
0610	626.11 PRECAST CONCRETE JUNCTION BOX	EA 9.000				
0620	626.21 METALLIC CONDUIT	LF 50.000				
0630	626.22 NON-METALLIC CONDUIT	LF 1800.000				
0640	626.31 18 INCH FOUNDATION	EA 5.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013061.00

PROJECT(S): STP-1306(100)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0650	626.33 30 INCH FOUNDATION	EA 7.000				
0660	626.331 36 INCH FOUNDATION	EA 1.000				
0670	626.35 CONTROLLER CABINET FOUNDATION	EA 2.000				
0680	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	LF 16800.000				
0690	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	SF 1500.000				
0700	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0710	629.05 HAND LABOR, STRAIGHT TIME	HR 40.000				
0720	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	HR 25.000				
0730	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	HR 10.000				
0740	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	HR 10.000				
0750	639.18 FIELD OFFICE TYPE A	EA 1.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013061.00

PROJECT(S): STP-1306(100)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0760	642.15 PRECAST CONCRETE STEPS	EA 3.000				
0770	642.181 REMOVE AND RESET GRANITE STEPS	EA 2.000				
0780	643.60 FLASHING BEACON AT: Russell St. & Bardwell St.	LUMP	LUMP			
0790	643.80 TRAFFIC SIGNALS AT Central Ave.	LUMP	LUMP			
0800	643.80 TRAFFIC SIGNALS AT College St.	LUMP	LUMP			
0810	643.83 VIDEO DETECTION SYSTEM	LUMP	LUMP			
0820	643.90 INTERCONNECT WIRE BETWEEN College St. & Central Ave. (approx. 1350	LUMP	LUMP			
0830	643.91 MAST ARM POLE	EA 8.000				
0840	643.92 PEDESTAL POLE	EA 5.000				
0850	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	SF 40.000				
0860	652.33 DRUM	EA 25.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013061.00

PROJECT(S): STP-1306(100)X

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0870	652.34 CONE	EA 75.000				
0880	652.35 CONSTRUCTION SIGNS	SF 500.000				
0890	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0900	652.38 FLAGGER	HR 9500.000				
0910	659.10 MOBILIZATION	LUMP	LUMP			
0920	660.21 ON-THE-JOB TRAINING (BID)	HR 1000.000				
	SECTION 0001 TOTAL					
	TOTAL BID					

