

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013064.00

PROJECT(S): AC-STP-1306(400)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.111 CLEARING	LUMP	LUMP			
0020	201.23 REMOVING SINGLE TREE TOP ONLY	EA	54.000			
0030	201.24 REMOVING STUMP	EA	58.000			
0040	202.15 REMOVING MANHOLE OR CATCH BASIN	EA	1.000			
0050	203.20 COMMON EXCAVATION	CY	16775.000			
0060	203.21 ROCK EXCAVATION	CY	400.000			
0070	203.213 FRACTURING EXISTING SUBGRADE LEDGE	SY	670.000			
0080	203.214 EXPLORATORY DRILLING	LF	25.000			
0090	203.24 COMMON BORROW	CY	100.000			
0100	203.242 DIRTY BORROW	CY	860.000			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013064.00

PROJECT(S): AC-STP-1306(400)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	203.25 GRANULAR BORROW	100.000 CY				
0120	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	50.000 CY				
0130	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	38.000 CY				
0140	304.09 AGGREGATE BASE COURSE - CRUSHED	13000.000 CY				
0150	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	2110.000 T				
0160	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	160.000 T				
0170	403.213 HOT MIX ASPHALT 12.5 MM BASE	3510.000 T				
0180	409.15 BITUMINOUS TACK COAT - APPLIED	540.000 G				
0190	603.159 12 INCH CULVERT PIPE OPTION III	82.000 LF				
0200	603.16 15 INCH CULVERT PIPE OPTION I	680.000 LF				
0210	603.169 15 INCH CULVERT PIPE OPTION III	40.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013064.00

PROJECT(S): AC-STP-1306(400)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	603.179 18 INCH CULVERT PIPE OPTION III	288.000 LF				
0230	603.199 24 INCH CULVERT PIPE OPTION III	228.000 LF				
0240	604.09 CATCH BASIN TYPE B1	14.000 EA				
0250	605.09 6 INCH UNDERDRAIN TYPE B	3550.000 LF				
0260	605.10 6 INCH UNDERDRAIN OUTLET	110.000 LF				
0270	605.11 12 INCH UNDERDRAIN TYPE C	960.000 LF				
0280	605.12 15 INCH UNDERDRAIN TYPE C	440.000 LF				
0290	605.13 18 INCH UNDERDRAIN TYPE C	296.000 LF				
0300	606.356 UNDERDRAIN DELINEATOR POST	19.000 EA				
0310	606.47 SINGLE WOOD POST	37.000 EA				
0320	609.31 CURB TYPE 3	3650.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013064.00

PROJECT(S): AC-STP-1306(400)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	610.08 PLAIN RIPRAP	150.000 CY				
0340	610.18 STONE DITCH PROTECTION	67.000 CY				
0350	613.319 EROSION CONTROL BLANKET	4350.000 SY				
0360	615.07 LOAM	910.000 CY				
0370	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	73.000 UN				
0380	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	145.000 UN				
0390	619.1201 MULCH - PLAN QUANTITY	220.000 UN				
0400	621.031 EVERGREEN TREES (4 FOOT - 5 FOOT) GROUP A	10.000 EA				
0410	621.038 EVERGREEN TREES (5 FOOT - 6 FOOT) GROUP B	1.000 EA				
0420	621.267 LARGE DECIDUOUS TREE (1.75 INCH - 2 INCH CALIPER) GROUP A	11.000 EA				
0430	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	23500.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013064.00

PROJECT(S): AC-STP-1306(400)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	90.000 SF				
0450	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0460	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0470	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0480	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0490	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	20.000 HR				
0500	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	20.000 HR				
0510	639.18 FIELD OFFICE TYPE A	1.000 EA				
0520	652.31 TYPE I BARRICADE	10.000 EA				
0530	652.33 DRUM	100.000 EA				
0540	652.34 CONE	150.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 013064.00

PROJECT(S): AC-STP-1306(400)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	652.35 CONSTRUCTION SIGNS	450.000 SF				
0560	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	200.000 CD				
0570	652.38 FLAGGER	6000.000 HR				
0580	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0590	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					