

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 014924.00

PROJECTS

ME2007-1-FS

COUNTY : OXFORD

CONTRACT ID : 014924.00

BATCHELDERS GRANT, BRIDGE REPLACEMENT. LITTLE LARY BROOK
BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	05/30/09	\$ 400.00
01	04/01/09	\$ 300.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

CONTRACT ID: 014924.00

PROJECT(S): ME2007-1-FS

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 BRIDGE ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	202.203 PAVEMENT BUTT JOINTS	SY 200.000				
0030	203.20 COMMON EXCAVATION	CY 325.000				
0040	203.24 COMMON BORROW	CY 10.000				
0050	203.25 GRANULAR BORROW	CY 95.000				
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	CY 175.000				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY 380.000				
0080	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	T 96.000				
0090	409.15 BITUMINOUS TACK COAT - APPLIED	G 15.000				
0100	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 014924.00

PROJECT(S): ME2007-1-FS

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP			
0120	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0130	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	18300.000 LB				
0140	503.13 REINFORCING STEEL, PLACING	18300.000 LB				
0150	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0160	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0170	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			
0180	507.0812 STEEL APPROACH RAILING : 2-BAR	4.000 EA				
0190	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0200	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	240.000 SY				
0210	523.52 BEARING INSTALLATION	8.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 014924.00

PROJECT(S): ME2007-1-FS

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	EA 4.000				
0230	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	EA 4.000				
0240	606.151 GUARDRAIL TYPE 3AA - SINGLE RAIL	LF 125.000				
0250	606.1722 BRIDGE TRANSITION - TYPE 2	EA 4.000				
0260	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	EA 8.000				
0270	606.78 LOW VOLUME GUARDRAIL ENDS - TYPE 3	EA 4.000				
0280	610.08 PLAIN RIPRAP	CY 10.000				
0290	610.16 HEAVY RIPRAP AVERAGE WEIGHT 700 LBS.	CY 405.000				
0300	619.1401 EROSION CONTROL MIX	CY 105.000				
0310	629.05 HAND LABOR, STRAIGHT TIME	HR 10.000				
0320	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	HR 12.000				

SCHEDULE OF ITEMS

CONTRACT ID: 014924.00

PROJECT(S): ME2007-1-FS

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	631.131 SMALL BULLDOZER-GRADER (INCLUDING OPERATOR)	12.000 HR				
0340	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	12.000 HR				
0350	631.27 VIBRATING ROLLER (INCLUDING OPERATOR)	12.000 HR				
0360	639.19 FIELD OFFICE TYPE B	1.000 EA				
0370	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	120.000 CD				
0380	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0390	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0400	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

