

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015087.00

PROJECTS

BH-1508(700)X

COUNTY : KENNEBEC

CONTRACT ID : 015087.00

SCOPE OF WORK: RIGGS BROOK BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK. IN KENNEBEC COUNTY, PROJECT IS LOCATED ON ROUTE 100/ 201 APPROXIMATELY 3.2 MILES SOUTH OF THE TOWN LINE.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	05/01/10	\$ 750.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015087.00

PROJECT(S): BH-1508(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.11 CLEARING	1.000 AC				
0020	201.23 REMOVING SINGLE TREE TOP ONLY	1.000 EA				
0030	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0040	202.1913 REMOVE ABANDONED ASBESTOS-CONTAINING PIPE	200.000 LF				
0050	203.20 COMMON EXCAVATION	3200.000 CY				
0060	203.24 COMMON BORROW	10.000 CY				
0070	203.25 GRANULAR BORROW	1500.000 CY				
0080	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	10.000 CY				
0090	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	1100.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015087.00

PROJECT(S): BH-1508(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	17.000 CY				
0110	304.08 AGGREGATE BASE COURSE - SCREENED	2350.000 CY				
0120	403.207 HOT MIX ASPHALT 19.0 MM HMA	300.000 T				
0130	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	43.000 T				
0140	403.210 HOT MIX ASPHALT 9.5 MM HMA	560.000 T				
0150	403.213 HOT MIX ASPHALT 12.5 MM BASE	200.000 T				
0160	409.15 BITUMINOUS TACK COAT - APPLIED	180.000 G				
0170	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	200.000 CY				
0180	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	14400.000 LB				
0190	503.13 REINFORCING STEEL, PLACING	14400.000 LB				
0200	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015087.00

PROJECT(S): BH-1508(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 24'	LUMP	LUMP			
0220	511.07 COFFERDAM: FOOTING NO.1	LUMP	LUMP			
0230	511.07 COFFERDAM: FOOTING NO.2	LUMP	LUMP			
0240	512.081 FRENCH DRAINS	LUMP	LUMP			
0250	514.06 CURING BOX FOR CONCRETE CYLINDERS	EA 1.000				
0260	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0270	527.34 WORK ZONE CRASH CUSHIONS	UN 6.000				
0280	534.70 PRECAST STRUCTURAL CONCRETE ARCH	LUMP	LUMP			
0290	603.17 18 INCH CULVERT PIPE OPTION I	LF 60.000				
0300	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	EA 4.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015087.00

PROJECT(S): BH-1508(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0310	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	430.000 LF				
0320	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	100.000 LF				
0330	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	4.000 EA				
0340	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0350	606.47 SINGLE WOOD POST	3.000 EA				
0360	606.51 MULTIPLE MAILBOX SUPPORT	1.000 EA				
0370	607.24 REMOVE AND RESET FENCE	20.000 LF				
0380	609.31 CURB TYPE 3	440.000 LF				
0390	610.08 PLAIN RIPRAP	380.000 CY				
0400	610.18 STONE DITCH PROTECTION	10.000 CY				
0410	613.319 EROSION CONTROL BLANKET	58.000 SY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015087.00

PROJECT(S): BH-1508(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0420	615.07 LOAM	83.000 CY				
0430	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	4.000 UN				
0440	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	6.500 UN				
0450	619.1201 MULCH - PLAN QUANTITY	10.000 UN				
0460	619.1401 EROSION CONTROL MIX	170.000 CY				
0470	627.18 12 " SOLID WHITE PAVEMENT MARKING	17.000 LF				
0480	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	2700.000 LF				
0490	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	46.000 SF				
0500	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				
0510	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0520	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015087.00

PROJECT(S): BH-1508(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	20.000 HR				
0540	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0550	637.071 DUST CONTROL	LUMP	LUMP			
0560	639.18 FIELD OFFICE TYPE A	1.000 EA				
0570	652.31 TYPE I BARRICADE	10.000 EA				
0580	652.312 TYPE III BARRICADE	3.000 EA				
0590	652.33 DRUM	50.000 EA				
0600	652.34 CONE	100.000 EA				
0610	652.35 CONSTRUCTION SIGNS	200.000 SF				
0620	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0630	652.38 FLAGGER	240.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015087.00

PROJECT(S): BH-1508(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0640	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0650	659.10 MOBILIZATION	LUMP	LUMP			
0660	890.01 SPECIAL WORK #1 TEMPORARY WATER MAIN	LUMP	LUMP			
0670	890.021 SPECIAL WORK #2 RELOCATED WATER MAIN	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

