

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015088.00

PROJECT(S): BR-1508(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.10 REMOVING EXISTING SUPERSTRUCTURE (PROPERTY OF CONTRACTOR) (139 CY)	LUMP	LUMP			
0020	202.17 REMOVING EXISTING STRUCTURAL CONCRETE (5 CY)	LUMP	LUMP			
0030	202.202 REMOVING PAVEMENT SURFACE	515.000 SY				
0040	202.205 RUMBLE STRIPS - SHOULDER	6800.000 LF				
0050	403.210 HOT MIX ASPHALT 9.5 MM	44.000 T				
0060	403.213 HOT MIX ASPHALT 12.5 MM BASE	5.000 T				
0070	409.15 BITUMINOUS TACK COAT - APPLIED	130.000 G				
0080	502.23 STRUCTURAL CONCRETE PIERS	18.000 CY				
0090	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK (16 CY)	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015088.00

PROJECT(S): BR-1508(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	5700.000 LB				
0110	503.13 REINFORCING STEEL, PLACING	5700.000 LB				
0120	505.08 SHEAR CONNECTORS (2448 EA.)	LUMP	LUMP			
0130	506.142 FIELD PAINTING EXISTING STRUCTURAL STEEL	LUMP	LUMP			
0140	506.17 SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL	LUMP	LUMP			
0150	506.18 CONTAINMENT AND POLLUTION CONTROL	LUMP	LUMP			
0160	506.191 DISPOSAL OF SPECIAL WASTE OR HAZARDOUS WASTE MATERIAL	LUMP	LUMP			
0170	507.081 STEEL BRIDGE RAILING, 2 BAR	307.000 LF				
0180	508.13 MEMBRANE WATERPROOFING (10 SY)	LUMP	LUMP			
0190	513.40 SLOPE PROTECTION - REPAIR	150.000 SY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015088.00

PROJECT(S): BR-1508(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES (590 SY)	1230.000 SY				
0210	518.52 REPAIR OF UPWARD FACING SURFACES > 7.9 IN.	0.100 CY				
0220	518.60 REPAIR OF VERTICAL SURFACES < 7.9 IN.	375.000 SF				
0230	518.61 REPAIR OF VERTICAL SURFACES > 7.9 IN.	3.000 CY				
0240	518.70 REPAIR OF OVERHEAD SURFACES < 7.9 IN.	30.000 SF				
0250	518.71 REPAIR OF OVERHEAD SURFACES > 7.9 IN.	0.100 CY				
0260	520.22 EXPANSION DEVICE - COMPRESSION SEAL	2.000 EA				
0270	524.30 TEMPORARY STRUCTURAL SUPPORT	2.000 EA				
0280	524.40 PROTECTIVE SHIELD	LUMP	LUMP			
0290	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	980.000 LF				
0300	526.301 TEMPORARY CONCRETE BARRIER TYPE I (288 LF)	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015088.00

PROJECT(S): BR-1508(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0310	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0320	527.34 WORK ZONE CRASH CUSHIONS	7.000 UN				
0330	530.03 PREFABRICATED DECK PANEL (6276 SF)	LUMP	LUMP			
0340	606.1721 BRIDGE TRANSITION - TYPE 1	2.000 EA				
0350	606.3651 GUARDRAIL-REMOVE, MODIFY, AND RESET EXISTING TO 3D	50.000 LF				
0360	607.184 CHAIN LINK SNOW FENCE 3 FOOT	124.000 LF				
0370	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1035.000 LF				
0380	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	24.000 HR				
0390	631.11 AIR TOOL (INCLUDING OPERATOR)	24.000 HR				
0400	631.22 FRONT END LOADER (INCLUDING OPERATOR)	30.000 HR				
0410	639.18 FIELD OFFICE TYPE A	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015088.00

PROJECT(S): BR-1508(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0420	652.30 FLASHING ARROW BOARD	1.000 EA				
0430	652.312 TYPE III BARRICADE	16.000 EA				
0440	652.32 BATTERY OPERATED LIGHT	260.000 EA				
0450	652.33 DRUM	100.000 EA				
0460	652.35 CONSTRUCTION SIGNS	505.000 SF				
0470	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	88.000 CD				
0480	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0490	652.38 FLAGGER	355.000 HR				
0500	652.381 TRAFFIC OFFICER	180.000 HR				
0510	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	3.000 EA				
0520	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015088.00

PROJECT(S): BR-1508(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					